NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Shubhshree Engineering & Constructions Pvt Ltd
Aurangabad

Date : 28.1.2020
Quote NO : SQT.19.20.1365R6
Kind Attn : Mr. Manish Sharma
Email Id : manishsharma@shubhshree.co.in
Contact No: 7391000686

Project Name & Location: Endress + Hausser Flowtech India Pvt Ltd

Subject : Quotation for Scissor Lift, Dock Leveler, Dock Shelter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Dock Leveler	2000	2500	4	560,000	2,240,000	Inclusive	
2	Scissor Lift	2000	2500	4	1,230,320	4,921,280	Inclusive	
3	Dock Shelter	3450	3400	4	150,800	603,200	Inclusive	
				Total		**7,764,480**		-
4	P&F Charges			Nil				
	Total Without Taxes					**7,764,480**		**-**
	GST Extra @ 18%			18%		1,397,606		-
	Total With Taxes					**9,162,086**		**-**
5	Transportation Charges					**NIHVA Scope**		
6	Unloading Charges @ Site					**NIHVA Scope**		

NIHVA TECHNOLOGIES PVT. LTD.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax
chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

1 Dock Leveler

Sr. No	Description	Specification
1	Size	(W) 2000 mm x (H) 2500 mm
2	Quantity	4 Nos
3	Capacity	15 T
4	Control Unit Protection Class	IP54
5	European Standards	EN 1398
6	Coating	RAL 5010, Hot dip galvanized
7	Control unit	Supervision 105, 105A, i105, i305 Service & fault Indicator
8	Vertical working range	250 - 620 mm
9	Rise above dock	270 - 350 mm
10	Fall below dock	
11	Platform tear-plate thickness with platform reinforcements according to the load capacity	6/8, 8/10 mm
12	Lip material & length	Steel, 400 / 500 mm
13	Nominal voltage	400V 3-phase

2 Scissor Lift

Sr. NO	Description	Specification
1	Capacity	6 Ton (UDL)
2	Platform Size	(W) 2000 mm X (L) 2500 mm
3	Shut Ht	1000 mm
4	Max Ht	2200 mm
5	Lift Ht	1200 mm
6	Safety Railing	ALl sides
7	Manual Lip	3 Piece (240 + 1500 + 240) - 1 Side Only
8	Maintenance Stopper	2 NOS
10	Push Button Pendent	Flexible pendent with 5 mtr Cable - 1 No
11	Control Panel	Outside pit - 1 No
13	Safety Bellow	All side
14	Power Pack Inside Pit with Buzzer	15 HP, 3 Phase - Eaton make
15	Hydraulic Cylinder	Two numbers with Bore 150 X stroke 500 mm - Eaton make
16	Hot Dip Galvanised	IS 2629 / EN ISO 1461 / As per ASTM
17	Hose	Parker Hoses
19	Cable	Polycab cables
20	Hydraulic Oil	Grade 68 - 125 Ltr

3 Dock Shelter

Sr. No	Description	Specification
1	Size	(W) 3450 mm x (H) 3400 mm
2	Quantity	4 Nos
3	Normal Width x Normal Height	3450 mm x 3400 mm
4	Normal Depth	600 mm
5	Top Curtain	1000 mm
6	Side Curtain	600 mm
7	Curtain Colour	Black
8	Top and Side curtain	Double Layer High Quality Polyester
9	Thickness	3.0mm
10	Flammability all curtain	DIN 75200
11	Frame Material	Aluminum



NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax
chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : @ Site Aurangabad

Delivery : 10-12 weeks for Scissor lift from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Ravindra Kharat on 7410169333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd