

FOUNDATION LAYOUT



PLINTH LVL. FRAMING PLAN (UFL : +581.650 M)

NOTE:

'B' INDICATES BEAM SIZE 200x550, UNLESS SPECIFIED.

'M1' INDICATES STEEL COLUMN SIZE 150x150x8



ATTIC SLAB LEVEL PLAN (+584.650 M)

NOTE:

'B' INDICATES BEAM SIZE 200x450, UNLESS SPECIFIED.

'M1' INDICATES STEEL COLUMN SIZE 150x150x8



RAFTER END LVL PLAN (+585.520 M)

NOTE:

'M1' INDICATES STEEL COLUMN SIZE 150x150x8



RAFTER TOP LVL PLAN (+587.650 M)



GENERAL NOTES

1. REFERENCE CODE IS456-2000
2. ALL THE DIMENSIONS ARE IN MM UNLESS SPECIFIED.
3. ALL THE REINFORCEMENT BARS SHALL BE OF GRADE FE 500.
4. DIMENSIONS OTHER THAN STRUCTURAL TO BE VERIFIED WITH ARCHITECT.
5. SBC OF THE SOIL IS CONSIDERED AS 257T/Sqm AS PER GEOTECHNICAL REPORT
6. GRADE SLAB TO BE REST ON COMPACTED SOIL WITH PROCTOR DENSITY GREATER THAN 90%.

ITEMS	COVER	CONCRETE GRADE
FOUNDATION	50mm	M30
COLUMN	40mm	M30
BEAM	30mm	M30
SLAB	30mm	M30

FOOTING & COLUMN SCHEDULE

REMARK			STOP AT 582.645 LVL.	-	-	-	-
COLUMN NOS.			C1, C2	C3	C4	C5	C6
COLUMN DETAIL FROM FOOTING TO RAFTER END LVL	SIZE	M30	200 x 450	200 x 450	200 x 450	200 x 450	200 x 450
	REBAR [NO - DIA.]		4 T16 + 4 T12	4 T16 + 4 T12	4 T16 + 4 T12	4 T16 + 4 T12	4 T16 + 4 T12
COLUMN REINFORCEMENT AND LINK DETAIL			 T16 T12 LINK DETAIL	 LINK DETAIL T16 T12	 LINK DETAIL T16 T12	 LINK DETAIL T16 T12	 LINK DETAIL T16 T12
FOOTING REBAR	PARALLEL TO LENGTH		T10 - 150 (B2)	T10 - 150 (B2)	T10 - 125 (B2)	T10 - 150 (B2)	T10 - 150 (B2)
	PARALLEL TO WIDTH		T10 - 150 (B1)	T10 - 125 (B1)	T10 - 125 (B1)	T10 - 150 (B1)	T10 - 125 (B1)
FOOTING DEPTH	D (mm)	M30	500	500	500	500	500
FOOTING SIZE	L x B (mm)		1150 x 1150	1100 x 1350	1100 x 1350	1050 x 1300	950 x 1200
PCC (100mm)	L x B (mm)	M10	1350 x 1350	1300 x 1550	1300 x 1550	1250 x 1500	1150 x 1400
COLUMN NOS			C1, C2	C3	C4	C5	C6,
FOOTING NOS		FOOTING TYPE	F1,F2	F3	F4	F5	F6

BEAM SCHEDULE: PLINTH LVL.

BEAM	SIZE		BOTTOM BARS		TOP BARS			STIRRUPS			REMARK
	WIDTH	DEPTH	FULL	EXTRA	FULL	LEFT EXTRA	RIGHT EXTRA	S1	S2	S3	
B1	200	550	2 T12		2 T12			8-100	8-150	8-100	
B2	200	550	2 T12		2 T12			8-100	8-150	8-100	
B3-1	200	550	2 T12		2 T12			8-100	8-150	8-100	CANTILEVER BEAM
B3-2	200	550	2 T12		2 T12			8-100	8-125	8-100	
B4-1	200	550	2 T12		2 T12			8-100	8-125	8-100	
B4-2	200	550	2 T12		2 T12			8-100	8-150	8-100	
B5	REFER DETAIL		2 T12		2 T16			8-100	8-100	8-100	REFER B5 DETAIL
B6	200	550	2 T12		2 T12			8-100	8-150	8-100	
B7-1	200	550	2 T12		2 T12			8-100	8-150	8-100	SUNK 450mm
B7-2	200	550	2 T12		2 T12			8-100	8-150	8-100	

BEAM SCHEDULE: ATTIC LEVEL (+584.650 M)

BEAM	WIDTH	DEPTH	BOTTOM FULL	BOTTOM EXTRA	TOP FULL	LEFT EXTRA	RIGHT EXTRA	S1	S2	S3	REMARK
B1	200	450	2 T12		2 T12			8-100	8-150	8-100	
B2	200	450	2 T12		2 T12			8-100	8-100	8-100	
B3	200	450	2 T12		2 T12			8-100	8-100	8-100	
B4	200	450	2 T12		2 T12			8-100	8-100	8-100	
B5	200	450	2 T12		2 T12			8-100	8-150	8-100	



SECTION 1-1



FOUNDATION TO ROOF



TYPICAL FOUNDATION DETAILS



B5 DETAILS



SECTION 1-1



SECTION 2-2

LEGEND

▭	STRUCTURAL SLAB LEVEL
⊠	CUTOUT
▨	COLUMN TERMINATE



BEAM- TO COLUMN CONNECTION DETAILS



BOTTOM BARS DETAILS, WHEN DIFFERENT DEPTH BEAM MEETS AT COLUMN JUNCTION



BEAM- TO BEAM CONNECTION DETAILS



BEAM TO COLUMN CONNECTION DETAILS (PLAN)



Typical Beam Reinforcement details

LD IS DEVELOPMENT LENGTH OF THE BAR [56 x DIA], SHALL BE OF SMALLER BAR DIAMETER



TYPICAL GRADE SLAB DETAIL
[SECTION A-A]

FOR APPROVAL

REV.	DESCRIPTION	DATE

PROPOSED: CLUBHOUSE AT 106-LOHEGAON

UTILITY BUILDING-02 FRAMING PLANS,
FOUNDATION, COLUMN & BEAM
DETAILS

PROJECT NO.	DRAWING NO.	SCALE	DATE	REVISION
A-2411	A-2411-UTI-02-001	1:100	09.06.2025	R0

ARCHITECT

CLIENT