NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

SERUM INSTITUTE OF INDIA PVT LTD
Hadapsar
Pune 411028

Date : 14.10.2019
Quote NO : SQT.19.20.2156
Kind Attn : Mr. Rohit Shinde
Email Id : rohit.shinde@seruminstitute.com
Contact No:

Project Name & Location:

Subject : Quotation for Rolling Shutter/Sectional Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2 , 3
C.	General Conditions	4
D.	Terms & Condtions	4

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
	Option - 1							
1	**Single Skin Motorised Rolling Shutter**	3750	2400	12	91,000	10,92,000	Included in Supply Charges	
	Option - 2							
2	**Double Wall Motorised Rolling Shutter (100% Imported from Germany)**	3750	2400	12	3,23,000	38,76,000	Included in Supply Charges	
	Option - 3							
3	**Automatic Sectional Doors**	3750	2400	12	2,50,000	30,00,000	Included in Supply Charges	
				Total				
4	P&F Charges on Total Supply Value			NIL				
	GST Extra @ 18%			NIL	Due to SEZ			
5	Transportation Charges				**Extra at Actual**			
6	Unloading Charges @ Site				**In client scope**			

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Option 1 : NIHVA Make Single Skin Motorised Rolling Shutter

Sr. No	Description	Specifications
1	Rolling Shutter	Motorised Rolling Shutter with GI steel of thickness of 1 mm.
2	Mounting Location area	Inside area / Outside area
3	Curtain Panel	The panel made of 1.0mm thick GI steel
4	Curtain panel size	75mm wide
5	Curtain Profile	Curved
6	Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
7	Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
8	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
9	Side Brackets	MS Plate 3 mm to 10 mm thick, as per the opening dimension
10	Hood Cover	Made of GI Sheet Thickness 0.9 mm GI mm with 25x25x3mm angle stiffener
11	Surface finish	PU paint or Powder coated
12	Drive Unit & Mounting Type	Electric Motor - Indirect Mounting -Jielong (China Make motor)

Option 2 : 100% Imported Double Skin Motorised Rolling Shutter

Sr. No	Description	Specifications
1	Rolled Curtain Profile	Thermo teck Steel filled with PU foam
2	Roller door surface outside	Galvanised with protective fill
3	Door color inside/outside	Uniformly
4	Roller shutter type	Internal roller
5	Buffer drive side min/exist	300 mm
6	Buffer bear side min/exist	175 mm
7	Side Guide Profile	FS 85 Steel
8	Welding Shaft	Octagonal tube galvaised
9	Drive Type	Direct mount drive - 400V/3ph AWG. 12U/min
10	IP Protection	IP54
11	Drive mounting	Inside left
12	Emergency drive operation	Emergency hand crank
13	Drive Unit & Mounting Type	Electric Motor - Indirect Mounting -Jielong (China Make motor)
14	Control Unit	Dean man with built in triple button
15	Wind load class	Wind load resistance class 2

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA ASSA ABLOY Sectional Door

Sr. No	Description	Specifications
1	Model No	ASSA ABLOY - OH1042P
2	Vision Windows	2 Nos at central panel
3	Opening Direction & Mounting	Horizontal mounting
4	Door produced Based on which certification	Doors produced according to ISO 9000 or ISO 14000 certified.
5	Opening/Closing Speed	0,28 m/s
6	Door Material	GI Steel
7	Panel Thickness	42mm
8	Panel colour	RAL 9002 Powder coated
9	External surface of the panel	diamond grid design with a glossy finish at the section joints.
10	inside surface of the panel	Monolithic surface on the inside of the door
11	Panels are euipped with	Panels to have integrated steel reinforcement for fixation of hinges and hardware.
12	Door sealent	All door sealants made of EPDM rubber, temperature resistant -30/+70
13	All Panel height	All panels should be 545mm high
14	Panel Inside insulation metrial	Insulation material to be CFC free polyuretane foam.
15	Panel Flame Retardent standrad	Flame retardant polyurethane foam according DIN4102-class B2.
16	Steel component Material	All steel components to be electro galvanized
17	Hinge Material	Glass fibre reinforced Polyamide
18	Spring Material surface finish	Powder coated
19	Spings transport till plant	Pre tensioned spring package
20	Water Penetration	EN 12425 class 3
21	Air Permealibity	EN12426 class 3
22	Wind Load	EN21424 class 3
23	Thermal Transittance	EN 12428 1.10W /m2K
24	Bottom sealing	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber
25	Door saftey device 1	Doors equiped with spring break device
26	Door saftey device 2	Door equiped with pneumatic safety edge
27	Door saftey 3	Having hinges flush with the inside door surface is a safety feature that eliminates the risk of things or people getting caught by parts protuding from a moving door
28	Incase of Power failuer	Doors to be equiped with quick release fuction
29	Operator power conumption	Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W
30	Drive Unit & Mounting Type	Single phase 230V direct drive on shaft
31	Emergency Operation	by Disengagement rope manual
32	Operating Switch	Up/Down Keypad + stopbutton
33	Environmental Green Product Declaration Certification	as per ISO 14025 and EN 15804

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price	: Ex Works Pune
Delivery	: 6 - 7 Rolling Shutter, 11-12 Weeks for Double Wall Rolling Shutter and Sectional Door from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.
Payment	: 80% Advance along with Confirmed Purchase Order & Balance before dispatch.
Validity	: Validity of Offer is 15 days from the date of quotation
Warranty	: 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Arjun Patil on 8551096333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd