**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

## NIHVA Sales Quotation

**Laxmi Industries**
Door No.A-2/1 D, IDA Nacharam
Hyderabad-500076, Telangana

**Date : 31.08.2019**
**Quote NO : SQT/19-20/2006**
**Kind Attn : Paresh Patel**
**Email Id :** laxmiindustries1991@gmail.com
**Contact No: 9553587673**

**Subject : Quotation for Rolling Shutter.**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**


| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 3 |


**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Height (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | Motorized Rolling Shutter | 6100 | 3660 | 3 | 1,72,000 | 5,16,000 | 20,000 | 60,000 |
| | | | | **Total** | | **5,16,000** | | **60,000** |
| 2 | P&F Charges | | | 3% | | 15,480 | | |
| | **Total Without Taxes** | | | | | 5,31,480 | | 60,000 |
| | GST Extra @ 18% | | | 18% | | 95,666.40 | | 10,800 |
| | **Total With Taxes** | | | | | **6,27,146** | | **70,800** |
| 3 | Transportation Charges | | | | | In Client Scope | | |
| 4 | Unloading Charges @ Site | | | | | In Client Scope | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

| Sr .No. | Specification | Motorized Rolling Shutter |
|---|---|---|
| 1 | Description: | Motorised Rolling Shutter with MS Laths with thickness of 1 mm. |
| 2 | Mounting Location area | Inside area / Outside area |
| 3 | Mounting Surface | Side Brackets: Optional = On Concrete /Steel & Side |
| 4 | Curtain Panel | The panel made of 1.0mm thick MS. |
| 5 | Curtain panel size | 75mm wide |
| 6 | Curtain Profile | Curved |
| 7 | Bottom Profile | M. S. Plate 100 mm x 2.5 mm thick with angle stiffener |
| 8 | Side Guide Profile | M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension) |
| 9 | Roller Shaft | M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h |
| 10 | Side Brackets | MS Plate 3 mm to 10 mm thick, as per the opening dimension. |
| 11 | Hood Cover | Made of GI Sheet Thickness 0.9 mm GF mm with 25x25x3mm angle stiffener |
| 12 | Surface finish | PU paint or Powder coated |
| 13 | Drive Unit & Mounting Type | Indirect Drive, Electric Motor - Direct Mounting - Sprocket chain arrangement – IP54 Protection |
| 14 | Wind Pressure | 100km/hr |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description | Remark |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | In Client Scope |
| 2 | Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site | In Client Scope |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | In Client Scope |
| 4 | Any civil / masonry/structural work required | In Client Scope |
| 5 | All structure support required | In Client Scope |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | In Client Scope |
| 7 | Conduits, Cables required | In Client Scope |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 5 - 6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil on 8551096333** For any further Clarification /Information in this Concern.

With Best Regards
Filina
7410179333
For NIHVA Technologies Pvt Ltd