NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/19-20/01626 **Date:- 14.05.2019**

Grasim Industries Limited
Epoxy Division
Vilayat

Kind Attn: Mr. Naveen M Shetru
Email: naveen.shetru@adityabirla.com
Contact No: 9731266719

Project Name And Location :

Subject : Quotation for NIHVA ASSA ABLOY-ALBANY-RR392

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication. please find below our best offer.

Commercial Offer

Sr. No	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**ASSA ABLOY-ALBANY Rapid Rollup Door RR392 (100% Imported with all components – made in Germany)**				
Construction:	High-Speed Roller Door : Curtain RollTex Plus blue (RAL 5002), orange (RAL 2009) or grey (RAL 7001) without window. Door with curtain tension.				
Drive Unit:	motor IP 55, either RH or LH as an option, with control cable (standard length = height of door)				
Control system:	MCC Frequency converter for opening/closing speed up to 2,2 / 0,9 m/s.Power supply required 3L(N)PE 400/415 V, 50 Hz. Protection IP 55.				
Power supply:	3/(N)/PE/230/400/415 V, 50 Hz.				
Safety features:	Safety contact edge, Safety photocell transmitter / receiver inside side columns.				
1	**Size: (W) 5000 mm X (H) 6000 mm**	1	No	931,000	931,000
2	**Radar Sensor**	1	Pair	36,000	36,000
	Total				**967,000**

GST Pune	27AAECN0437H1ZM

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope

Terms and Conditions :

1	**Price**	:	Ex works Pune
2	**P & F Charges**	:	@ 3 % of total supply value
3	**Freight Notes**	:	Extra As applicable
4	**Delivery**	:	8 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% advance along with confirm purchase order & balance before dispatch
6	**Insurance**	:	Extra As applicable
7	**Tax**	:	GST@18% Extra
8	**Validity**	:	Validity of Offer is 15 days from the date of quotation
9	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact **Mr. Bhavin Jain** on - 8551092333. For any further Clarification /Information in this Concern.

With Best Regards

Varsha

8551091333

For NIHVA Technologies Pvt Ltd