NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Learn Nature Consultants
Engineers, Architects & Planners
D-8, SECTOR-2, AVANTI VIHAR RAIPUR - 492006 (C.G.) INDIA.
Maharashtra -India.

Date : 23.08.2019
Quote NO : SQT.19.20.1967R
Kind Attn : Mr. Abhishek Sharma
Email Id : lncmdco@gmail.com
Contact No: 9425202390

Project Name & Location:

Subject : Quotation for Sliding gate

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**NIHVA Sliding Gate**	5000	5000	2	5,16,000	10,32,000	25,000	50,000
				Total		**10,32,000**		**50,000**
2				P&F Charges	3%	**30,960**		
				Total Without Taxes		**10,62,960**		**50,000**
				GST Extra @ 18%	18%	1,91,333		9,000
				Total With Taxes		**12,54,293**		**59,000**
3				Transportation Charges		**In Client Scope**		
4				Unloading Charges @ Site		**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Sr. No	Description	Specifications For Sliding Gate
1	**Door type**	Motorized Sliding Gate
2	**Clear Opening gate dimension**	(W) 5000 mm X (H) 5000 mm
3	**Quantity**	2 No`s
4	**Opening Direction**	Horizontal - from left to right or reverse
5	**Mounting Location area**	Inside area
6	**Design Pattern**	Standard Tubular Design Pattern
7	**Outer Frame Tube Sizes**	72 x 72 x 3.2mm MS SQ. TUBE
8	**Internal Vertical Tube Sizes**	38x38x3.20mm/40x40x3.2 MS SQ. TUBE
9	**Gap Between Tubes**	125 MM
10	**Bottom Rail on ground**	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
11	**Bottom Rollers**	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
12	**Full Height Column sizes**	100 x 100 x 4mm MS SQ. TUBE
13	**Guide Rollers supporter during Gate movement**	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
14	**Painting**	Powder Coating
15	**El motor make**	BFT – Italy (100% imported)
16	**Emergency Operation**	Manual after turn the switch
17	**Operating Switch**	Push Button from inside
18	**Safety**	Photocells
19	**Metal Rack**	Zinc plated metal rack
20	**Installation Checks**	need to be check = space requirements + substructure + Mounting access + Access in the event of power cut
21	**Civil work**	Client scope – client need to grout the I beam in concrete to create track for sliding gate

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Arjun Patil on 8551096333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd