NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

CCTEB
Khade City,
Chakan Pune.

Date : 14.09.2019
Quote NO : SQT/19-20/2068
Kind Attn : Mr.Shrihari Lokhande
Email Id : lokhande.shriharee@gmail.com
Contact No: (955) 277-7917

Subject : Quotation for Sectional Door and Rolling Shutter. (Project -Hengtong Optical Fiber Cable Plant located in Khed city, Chakan, Pune.)

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	4

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**MS Motorized Rolling Shutter**	3600	3000	2	97,000	194,000	20,000	40,000
2	**MS Motorized Rolling Shutter**	4000	4000	2	122,000	244,000	20,000	40,000
3	**MS Motorized Rolling Shutter**	5500	3000	2	126,000	252,000	20,000	40,000
4	**MS Motorized Rolling Shutter**	5500	4000	1	156,000	156,000	20,000	20,000
5	**MS Motorized Rolling Shutter**	3000	3000	2	85,000	170,000	20,000	40,000
6	**2 Hrs Fire Rated Rolling Shutter**	1600	2100	3	201,625	604,875	20,000	60,000
7	**2 Hrs Fire Rated Rolling Shutter**	1800	2100	2	203,365	406,730	20,000	40,000
8	**2 Hrs Fire Rated Rolling Shutter**	3000	2300	2	205,465	410,930	20,000	40,000
9	**2 Hrs Fire Rated Rolling Shutter**	3000	3000	1	343,120	343,120	20,000	20,000
10	**2 Hrs Fire Rated Rolling Shutter**	1500	2100	1	200,215	200,215	20,000	20,000
11	**2 Hrs Fire Rated Rolling Shutter**	1200	2100	1	177,600	177,600	20,000	20,000
				Total		**3,159,470**		**380,000**
12	P&F Charges			3%		94,784		
	Total Without Taxes					3,254,254		380,000
	GST Extra @ 18%			18%		585,765.74		68,400
	Total With Taxes					**3,840,020**		**448,400**
13	Transportation Charges					In Client Scope		
14	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Sr .No.	Specification	SKB - BS476
1	**Shutter Curtain**	Single Skin Design
2	**Guide Rail**	Model : SKB-G65 powder coated
3	**Bottom Bar**	Model : SKB-T120 powder coated
4	**Type of Mounting**	Standard
5	**Motor Drive Unit**	Power Source: 110v 60Hz 1 phase 220v 6OHz 1 phase 230v 50Hz 1 phase 400v 50Hz 3 phase Insulation Class E Manual Chain Override One unit push button switch Gravity drop level Auto close by relay switch after receive of 24vdc fire signal

Sr .No.	Specification	MS Motorized Rolling Shutter
1	**Description:**	Motorised Rolling Shutter with MS Laths with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete /Steel & Side
4	**Curtain Panel**	The panel made of 1.0mm thick MS.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día - 100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 1.2 mm GF mm with 25x25x3mm angle stiffener
12	**Surface finish**	PU paint or Powder coated
13	**Drive Unit & Mounting Type**	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 9 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Bhavin Jain on 8551092333** For any further Clarification /Information in this Concern.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd