



Interior view, Door closed



SECTION C-C
Open door
Scale 1:50

SECTION C-C
Closed door
Scale 1:50

NOT INCLUDED IN DOOR SUPPLY:

1. Design and supply of all door supporting structural components.
2. Design and supply of all closure between door and adjacent steel.
3. Door jambs adjustable for overall door width and true to plumb.
4. Paint job after completed door installation.
5. Any frameworks being provided by ASSA ABLOY will be clearly indicated as "by ASSA ABLOY".

REQUIREMENTS ON BUILDING:

6. Door head support must be straight within 1/600 of span in the in/out direction and free from protrusions of any kind.
7. For a single door leaf, door head support should be horizontal and straight within 1/600 of span at distributed full door load.
8. Door side jambs must be smooth, straight and parallel, out of plumb must not exceed 2mm/m (total deviation at full length 5 mm) in any direction.
9. Any footings at bottom of jamb columns must not interfere with installation of guide rails at floor level.
10. At time of installation, finished floor, free from obstructions, out to a distance of 2 m on each side of door centreline must be available.
11. Header box must be accessible from both sides during installation.


DOOR PROPERTIES:

12. The door is designed to withstand a differential pressure of 1.15kPa x 1.5 FOS.
13. Metal trim: motor side
15. Guide rails, top- and intermediate beams in extruded aluminium with natural finish.
16. Color of header box: BLACK (NCS 9000-N, RAL 9005)
17. Color of door fabric: Color code of door fabric/ RAL 7004 (7072/ D3171)


ELECTRICAL:

14. One main control panel provided of PLC type.
15. Audible and visual alarm
16. Safety edge
17. Back-up power switch
18. Approx. size of main control panel: WxHxD (500mm x 600mm x 250 mm),
19. Power: 1.4kW
20. Nom. current: 3.3A
21. (max. allowed voltage drop at start: 5%)
25. Power supply required: 3 Phase, 440 Volts, 16 A


BELT HOIST UNITS:
Sk 773.1-90S/4 Z dual brake




SECTION B-B
Door leaf is not shown for clarification
Scale 1:50




SECTION A-A
Hole pattern for header box attachment
Scale 1:50



Force by differential pressure transferred to guide rail at each intermediate position.
F= 2.7 kN




Load on header box attachment (each screw), due to wind load and door weight




DETAIL B, SCALE (1:5)

GUIDE RAIL MOUNTING DETAILS



DETAIL A, SCALE (1:10)

HEADER BOX MOUNTING DETAILS



KEY PLAN (NOT TO SCALE)

NOTE:
1. 275 MM RCC COLUMN REQUIRED FOR GUIDE MOUNTING.
IF RCC COLUMN NOT AVAILABLE THEN WE WILL REQUIRE MS STRUCTURE FOR THE SAME.

REFERENCE DRAWINGS :

DIAL-LT-D-UTL-A-20-100 : ARFF4 FIRE STATION ELEVATIONS
DIAL-LT-D-UTL-A-20-101 : ARFF4 FIRE STATION ELEVATIONS
DIAL-LT-D-UTL-A-10-100 : ARFF4 FIRE STATION GROUND FLOOR PLAN

REV.	DESCRIPTION	DESIGNED	DRAWN	CHECKED	APPROVED
B	Revised, issued for approval.	G.L.P	G.L.P	A.K.	V.T.
		15.11.2021	15.11.2021	15.11.2021	15.11.2021
A	Issued for approval	G.L.P	G.L.P	A.K.	V.T.
		30.10.2021	30.10.2021	30.10.2021	30.10.2021

REVISIONS

CHECKED BY	SIGN	DATE
ARCHITECTURE		
CIVIL & STRUCTURAL		
ELECTRICAL		
ELV SYSTEM		

CHECKED BY	SIGN	DATE
HVAC		
FPS		
PIPING		
PHE		

CHECKED BY	SIGN	DATE
GIS		
GEOTECH.		
AIRPORT SYSTEMS		
INTERFACE		

DELHI INDIRA GANDHI INTERNATIONAL AIRPORT — GMR — L&T Construction

CLIENT : DIAL INTERNATIONAL AIRPORT LIMITED

CONCEPT : FIRSA ACKOY

PROJECT : NEW DELHI INTERNATIONAL AIRPORT PHASE-3A DEVELOPMENT WORKS

PROJECT CONSULTANT: Engineering Design and Research Center (EDRC), L&T Construction

DESIGNED AND SUPPLIED BY: MMM TECHNOLOGIES PVT LTD

JOB No : JOBNO.

	NAME	SIGN	DATE
DSGN	G.L.P		02.10.2021
DRWN	G.L.P		02.10.2021
CHKD	A.K.		02.10.2021
APPD	V.T.		02.10.2021

TITLE: ARFF5 MEGADOOR 5800 X 5360 (RS6)

SCALE: 1:50

DRAWING No. DIAL-LT-Q-UTL-A-10-103

PROJECTION: FIRST ANGLE

SIZE: A3

REV: B

SHEET

RELEASED FOR: ☐ PRELIMINARY ☐ TENDER ☐ INFORMATION ☑ APPROVAL ☐ CONSTRUCTION

L&T Construction
Buildings & Factories

A	APPROVED. PROCEED FOR MANUFACTURE/ CONSTRUCTION.
B	APPROVED WITH COMMENTS. PROCEED TO MANUFACTURE/ CONSTRUCTION SUBJECT TO COMPLIANCE OF ALL COMMENTS AND RESUBMIT THE DOCUMENTS ONLY FOR LEVEL A & B
C	RESUBMIT AFTER INCORPORATION OF ALL COMMENTS FOR REVIEW.
D	REJECTED. MAKE A RESUBMISSION ALTOGETHER FOR REVIEW.

REVIEW OF THIS DOCUMENT IS ONLY TO CHECK COMPATIBILITY WITH BASIC DESIGN. THIS DOES NOT ABSOLVE THE SUB-CONTRACTOR/ MANUFACTURER FROM HIS RESPONSIBILITY TO MEET THE REQUIREMENT AS PER SPECIFICATIONS, CODES & STANDARDS, APPLICABLE LAWS, STATUTORY RULES & REGULATIONS, AS EXISTING OR AS MAY BE AMENDED TIME TO TIME.

CHECKED
LETTER REF :

VERIFIED BY : DESIGNATION : HEAD ARCHITECT
DATE :
SIGNATURE :

Add note for manual override operation

Please mention visual fabric dimension also from front side

Fabric colour as per DIAL Approval

All dimensions / sizes shown in drawings to be verified at site by Vendor prior to proceeding to Production.

All material / finishes are subject to MAS / sample approval by DIAL.

Please submit the final shop drawings to DIAL for Approval.

SHOP DRAWING
Building: ARFF5

Anchor specification, grade (5.8) embedment

Mention material & thickness

Mention material & thickness


Provide Anchor Specification grade (5.8) & embedment

min edge distance 55 mm.


(i) Wiring Diagram & control scheme to be provided.

(ii) Show all control boxes in overall plan.

Refer comments provided on drwg no A-10-103.




Interior view, Door closed



please mention visual fabric dimension also from front side

SECTION C-C
Open door
Scale 1:50



SECTION C-C
Closed door
Scale 1:50

NOT INCLUDED IN DOOR SUPPLY:

1. Design and supply of all door supporting structural components.
2. Design and supply of all closure between door and adjacent steel.
3. Door jambs adjustable for overall door width and true to plumb.
4. Paint job after completed door installation.
5. Any frameworks being provided by ASSA ABLOY will be clearly indicated as "by ASSA ABLOY".

REQUIREMENTS ON BUILDING:

6. Door head support must be straight within 1/600 of span in the in/out direction and free from protrusions of any kind.
7. For a single door leaf, door head support should be horizontal and straight within 1/600 of span at distributed full door load.
8. Door side jambs must be smooth, straight and parallel, out of plumb must not exceed 2mm/m (total deviation at full length 5 mm) in any direction.
9. Any footings at bottom of jamb columns must not interfere with installation of guide rails at floor level.
10. At time of installation, finished floor, free from obstructions, out to a distance of 2 m on each side of door centreline must be available.
11. Header box must be accessible from both sides during installation.

DOOR PROPERTIES:


12. The door is designed to withstand a differential pressure of 1.15kPa x 1.5 FOS.
13. Guide rails, top- and intermediate beams in extruded aluminium with natural finish.
14. Color of header box: BLACK (NCS 9000-N, RAL 9005)
15. Color of door fabric: Color code of door fabric: RAL 7004 (7072/ D3171)
16. Metal trim: motor side

Add note for Manual overside operation

ELECTRICAL:

17. One main control panel provided of PLC type.
18. Audible and visual alarm
19. Back-up power switch
20. Safety edge
21. Approx. size of main control panel: WxHxD (500mm x 600mmx250 mm),
22. Power: 2.7kW
23. Nom. current: 6.4A
24. (max. allowed voltage drop at start: 5%)
25. Power supply required: 3 Phase, 440 Volts, 16 A

BELT HOIST UNITS:
SK 873.1-100L/4 Z dual brake




KEY PLAN (NOT TO SCALE)

NOTE:
1. 340 MM RCC COLUMN REQUIRED FOR GUIDE MOUNTING.
IF RCC COLUMN NOT AVAILABLE THEN WE WILL REQUIRE MS STRUCTURE FOR THE SAME.


REFERENCE DRAWINGS :

DIAL-LT-D-UTL-A-20-100 : ARFF4 FIRE STATION ELEVATIONS
DIAL-LT-D-UTL-A-20-101 : ARFF4 FIRE STATION ELEVATIONS
DIAL-LT-D-UTL-A-10-100 : ARFF4 FIRE STATION GROUND FLOOR PLAN




SECTION A-A (Scale 1:50)
Hole pattern for header box attachment


Show the actual column position from plan




SECTION B-B
Door leaf is not shown for clarification
Scale 1:50




DETAIL C, SCALE (1:10)
ANCHOR POSITION FROM COLUMN




DETAIL B, SCALE (1:10)
GUIDE RAIL MOUNTING DETAILS



DETAIL A, SCALE (1:10)
HEADER BOX MOUNTING DETAILS



Force by differential pressure transferred to guide rail at each intermediate position.
F=4.7 kN



Load on header box attachment (each screw), due to wind load and door weight

L&T Construction
Buildings & Factories

A	APPROVED. PROCEED FOR MANUFACTURE/ CONSTRUCTION.
B	APPROVED WITH COMMENTS. PROCEED TO MANUFACTURE/ CONSTRUCTION SUBJECT TO COMPLIANCE OF ALL COMMENTS AND RESUBMIT THE DOCUMENTS ONLY FOR LEVEL A APPROVAL.
C	RESUBMIT AFTER INCORPORATION OF ALL COMMENTS FOR REVIEW.
D	REJECTED. MAKE A RESUBMISSION ALTOGETHER FOR REVIEW.

REVIEW OF THIS DOCUMENT IS ONLY TO CHECK COMPATIBILITY WITH BASIC DESIGN. THIS DOES NOT ABSOLVE THE SUB-CONTRACTOR/ MANUFACTURER FROM HIS RESPONSIBILITY TO MEET THE REQUIREMENT AS PER SPECIFICATIONS, CODES & STANDARDS, APPLICABLE LAWS, STATUTORY RULES & REGULATIONS, AS EXISTING OR AS MAY BE AMENDED TIME TO TIME.

CHECKED
LETTER REF :
VERIFIED BY : DEBABRATA PAL
DESIGNATION : HEAD ARCHITECT
DATE :
SIGNATURE :

SHOP DRAWING
Building: ARFF5

REV NO.	DESCRIPTION	DESIGNED	DRAWN	CHECKED	APPROVED
B	Revised, issued for approval.	15.11.2021 CLP	15.11.2021 CLP	15.11.2021 AK.	15.11.2021 VZ.
A	Issued for approval	30.10.2021 CLP	30.10.2021 CLP	30.10.2021 AK.	30.10.2021 VZ.

REVISIONS

CHECKED BY	SIGN	DATE	CHECKED BY	SIGN	DATE	CHECKED BY	SIGN	DATE
ARCHITECTURE			HVAC			QS		
CIVIL & STRUCTURAL			FPS			GEOTECH.		
ELECTRICAL			PIPING			AIRPORT SYSTEMS		
ELV SYSTEM			PHE			INTERFACE		

DELHI INDIRA GANDHI INTERNATIONAL AIRPORT
GMR
L&T Construction


CLIENT : DELHI INTERNATIONAL AIRPORT LIMITED
PROJECT: INDIRA GANDHI INTERNATIONAL AIRPORT PHASE-3A DEVELOPMENT WORKS
CONCEPT : RENA MAZUR
PROJECT CONSULTANT: Engineering Design and Research Center L&T Construction
DETAILED AND SUPPLIED BY: NANA TECHNOLOGIES PVT LTD

JOB No : JOENG.	NAME	SIGN	DATE
DSGN	CLP		02.10.2021
DRWN	CLP		02.10.2021
CHKD	AK.		02.10.2021
APPD	VZ.		02.10.2021


TITLE: ARFF5 MEGADOOR 8760 X 4988 (RS7)
SCALE 1:50
DRAWING No. DIAL-LT-Q-UTL-A-10-104
SHEET:
PROJECTION FIRST ANGLE
SIZE A3
REV B

RELEASED FOR ☐ PRELIMINARY ☐ TENDER ☐ INFORMATION ☑ APPROVAL ☐ CONSTRUCTION


Refer general comments provided on drwg. no. A-10-103.




Interior view, Door closed



SECTION A-A (Scale 1:50)
Hole pattern for header box attachment




SECTION B-B
Door leaf is not shown for clarification
Scale 1:50




DETAIL C, SCALE (1:10)


ANCHOR POSITION FROM COLUMN



SECTION C-C
Open door
Scale 1:50




SECTION C-C
Closed door
Scale 1:50




DETAIL B, SCALE (1:10)

GUIDE RAIL MOUNTING DETAILS




DETAIL A, SCALE (1:10)

HEADER BOX MOUNTING DETAILS



Force by differential pressure transferred to guide rail at each intermediate position.
F=4.7 kN



Load on header box attachment (each screw), due to wind load and door weight

NOT INCLUDED IN DOOR SUPPLY:

1. Design and supply of all door supporting structural components.
2. Design and supply of all closure between door and adjacent steel.
3. Door jambs adjustable for overall door width and true to plumb.
4. Paint job after completed door installation.
5. Any frameworks being provided by ASSA ABLOY will be clearly indicated as "by ASSA ABLOY".

REQUIREMENTS ON BUILDING:

6. Door head support must be straight within 1/600 of span in the in/out direction and free from protrusions of any kind.
7. For a single door leaf, door head support should be horizontal and straight within 1/600 of span at distributed full door load.
8. Door side jambs must be smooth, straight and parallel, out of plumb must not exceed 2mm/m (total deviation at full length 5 mm) in any direction.
9. Any footings at bottom of jamb columns must not interfere with installation of guide rails at floor level.
10. At time of installation, finished floor, free from obstructions, out to a distance of 2 m on each side of door centreline must be available.
11. Header box must be accessible from both sides during installation.


DOOR PROPERTIES:

12. The door is designed to withstand a differential pressure of 1.15kPa x 1.5 FOS.
15. Guide rails, top- and intermediate beams in extruded aluminium with natural finish.
16. Color of header box: BLACK (NCS 9000-N, RAL 9005)
15. Color of door fabric: Color code of door fabric RAL 7004 (7072/ D3171)
16. Metal trim: motor side

ELECTRICAL:

17. One main control panel provided of PLC type.
18. Audible and visual alarm
19. Back-up power switch
20. Safety edge
21. Approx. size of main control panel: WxHxD (500mm x 600mmx250 mm),
22. Power: 2.7kW
23. Nom. current: 6.4A
24. (max. allowed voltage drop at start: 5%)
25. Power supply required: 3 Phase, 440 Volts, 16 A

BELT HOIST UNITS:
SK 873.1-100L/4 Z dual brake



KEY PLAN (NOT TO SCALE)

NOTE:
1. 340 MM RCC COLUMN REQUIRED FOR GUIDE MOUNTING.
IF RCC COLUMN NOT AVAILABLE THEN WE WILL REQUIRE MS STRUCTURE FOR THE SAME.

REFERENCE DRAWING :

DIAL-LT-D-UTL-A-20-300 : ARFF4 FIRE STATION ELEVATIONS
DIAL-LT-D-UTL-A-20-301 : ARFF4 FIRE STATION ELEVATIONS
DIAL-LT-D-UTL-A-10-300 : ARFF4 FIRE STATION GROUND FLOOR PLAN

L&T Construction
Buildings & Factories

A	APPROVED. PROCEED FOR MANUFACTURE/ CONSTRUCTION.
B	APPROVED WITH COMMENTS. PROCEED TO MANUFACTURE/ CONSTRUCTION SUBJECT TO COMPLIANCE OF ALL COMMENTS AND RESUBMIT THE DOCUMENTS ONLY FOR LEVEL A APPROVAL
C	RESUBMIT AFTER INCORPORATION OF ALL COMMENTS FOR REVIEW.
D	REJECTED. MAKE A RESUBMISSION ALTOGETHER FOR REVIEW.

REVIEW OF THIS DOCUMENT IS ONLY TO CHECK COMPATIBILITY WITH BASIC DESIGN. THIS DOES N OT ABSOLVE THE SUB-CONTRACTOR/ MANUFACTURER FROM HIS RESPONSIBILITY TO MEET THE REQUIREMENT AS PER SPECIFICATIONS, CODES & STANDARDS, APPLICABLE LAWS STATUTORY RULES & REGULATIONS, AS EXISTING OR AS MAY BE AMENDED TIME TO TIME

CHECKED
LETTER REF :
VERIFIED BY : DEBABRATA PAL
DESIGNATION : HEAD ARCHITECT
DATE :
SIGNATURE :

SHOP DRAWING
Building: ARFF4

REV	DESCRIPTION	DESIGNED	DRAWN	CHECKED	APPROVED
B	Revised, issued for approval.	15.11.2021 GJP	15.11.2021 GJP	15.11.2021 AK.	15.11.2021 VT.
A	Issued for approval	30.10.2021 GJP	30.10.2021 GJP	30.10.2021 AK.	30.10.2021 VT.

REVISIONS

CHECKED BY	SIGN	DATE	CHECKED BY	SIGN	DATE	CHECKED BY	SIGN	DATE
ARCHITECTURE			HVAC			GIS		
CIVIL & STRUCTURAL			FPS			GEOTECH.		
ELECTRICAL			PIPING			AIRPORT SYSTEMS		
ELV SYSTEM			PHE			INTERFACE		

DELHI INDIRA GANDHI INTERNATIONAL AIRPORT
GMR
DELHI INTERNATIONAL AIRPORT LIMITED.

L&T Construction

PROJECT: INDIRA GANDHI INTERNATIONAL AIRPORT PHASE-3A DEVELOPMENT WORKS

CLIENT : AIRPORT AUTHORITY OF INDIA

CONCEPT :

PROJECT CONSULTANT: Engineering Design and Research Center L&T Construction

INSTALLED AND SUPPLIED BY: NIBHA TECHNOLOGIES PVT LTD

JOB NO.	NAME	SIGN	DATE
DSGN	G.J.P		02.10.2021
DRWN	G.J.P		02.10.2021
CHKD	A.K.		02.10.2021
APPD	V.T.		02.10.2021

TITLE: ARFF4 MEGADOOR 8760 X 5400 (RS7)

SCALE 1:50

DRAWING No. DIAL-LT-Q-UTL-A-10-101


SHEET

PROJECTION FIRST ANGLE


SIZE A3 REV B

RELEASED FOR ☐ PRELIMINARY ☐ TENDER ☐ INFORMATION ☑ APPROVAL ☐ CONSTRUCTION

Refer general comments provided on drwg no A-10-103




Interior view, Door closed




SECTION B-B

Door leaf is not shown for clarification


Scale 1:50




Scale 1:50



Force by differential pressure transferred to guide rail at each intermediate position.
F= 2.7 kN




Load on header box attachment (each screw), due to wind load and door weight



SECTION C-C

Open door


Scale 1:50



SECTION C-C

Closed door

Scale 1:50



DETAIL B, SCALE (1:5)

GUIDE RAIL MOUNTING DETAILS

NOT INCLUDED IN DOOR SUPPLY:

1. Design and supply of all door supporting structural components.
2. Design and supply of all closure between door and adjacent steel.
3. Door jambs adjustable for overall door width and true to plumb.
4. Paint job after completed door installation.
5. Any frameworks being provided by ASSA ABLOY will be clearly indicated as "by ASSA ABLOY".

REQUIREMENTS ON BUILDING:

6. Door head support must be straight within 1/600 of span in the in/out direction and free from protrusions of any kind.
7. For a single door leaf, door head support should be horizontal and straight within 1/600 of span at distributed full door load.
8. Door side jambs must be smooth, straight and parallel, out of plumb must not exceed 2mm/m (total deviation at full length 5 mm) in any direction.
9. Any footings at bottom of jamb columns must not interfere with installation of guide rails at floor level.
10. At time of installation, finished floor, free from obstructions, out to a distance of 2 m on each side of door centreline must be available.
11. Header box must be accessible from both sides during installation.

DOOR PROPERTIES:


12. The door is designed to withstand a differential pressure of 1.15kPa x 1.5 FOS.
13. Metal trim: motor side
15. Guide rails, top- and intermediate beams in extruded aluminium with natural finish.
16. Color of header box: BLACK (NCS 9000-N, RAL 9005)
17. Color of door fabric: Color code of door fabric: RAL 7004 (7072/ D3171)

ELECTRICAL:

14. One main control panel provided of PLC type.
15. Audible and visual alarm
16. Safety edge
17. Back-up power switch
18. Approx. size of main control panel: WxHxD (500mm x 600mmx250 mm),
19. Power: 1.4kW
20. Nom. current: 3.3A
21. (max. allowed voltage drop at start: 5%)
25. Power supply required: 3 Phase, 440 Volts, 16 A


BELT HOIST UNITS:

Sk 773.1-90S/4 Z dual brake



DETAIL A, SCALE (1:10)

HEADER BOX MOUNTING DETAILS



KEY PLAN (NOT TO SCALE)

NOTE:

1. 275 MM RCC COLUMN REQUIRED FOR GUIDE MOUNTING.
   IF RCC COLUMN NOT AVAILABLE THEN WE WILL REQUIRE MS STRUCTURE FOR THE SAME.

REFERENCE DRAWING :

DIAL-LT-D-UTL-A-20-300 : ARFF4 FIRE STATION ELEVATIONS
DIAL-LT-D-UTL-A-20-301 : ARFF4 FIRE STATION ELEVATIONS
DIAL-LT-D-UTL-A-10-300 : ARFF4 FIRE STATION GROUND FLOOR PLAN

L&T Construction
Buildings & Factories

A APPROVED. PROCEED TO MANUFACTURE/ CONSTRUCTION.
B APPROVED WITH COMMENTS. PROCEED TO MANUFACTURE/ CONSTRUCTION SUBJECT TO COMPLIANCE OF ALL COMMENTS AND RESUBMIT THE DOCUMENTS ONLY FOR LEVEL A
C RESUBMIT AFTER INCORPORATION OF ALL COMMENTS FOR REVIEW.
D REJECTED. MAKE A RESUBMISSION ALTOGETHER FOR REVIEW.

REVIEW OF THIS DOCUMENT IS ONLY TO CHECK COMPATIBILITY WITH BASIC DESIGN. IT THIS DOES NOT ABSOLVE THE SUB-CONTRACTOR/ MANUFACTURER FROM HIS RESPONSIBILITY TO MEET THE REQUIREMENT AS PER SPECIFICATIONS, CODES & STANDARDS, APPLICABLE LAWS, STATUTORY RULES & REGULATIONS, AS EXISTING OR AS MAY BE AMENDED TIME TO TIME.

CHECKED
LETTER REF :
VERIFIED BY : DEBABRATA PAL
DESIGNATION : HEAD ARCHITECT
DATE :
SIGNATURE :

SHOP DRAWING

Building: ARFF4

REV.	DESCRIPTION	DESIGNED	DRAWN	CHECKED	APPROVED
B	Revised, issued for approval.	15.11.2021 GJP	15.11.2021 A.K.	15.11.2021 V.T.	15.11.2021
A	Issued for approval	30.10.2021 GJP	30.10.2021 GJP	30.10.2021 A.K.	30.10.2021 V.T.

REVISIONS

CHECKED BY	SIGN	DATE
ARCHITECTURE		
CIVIL & STRUCTURAL		
ELECTRICAL		
ELV SYSTEM		

CHECKED BY	SIGN	DATE
HVAC		
FPS		
PIPING		
PHE		

CHECKED BY	SIGN	DATE
GIS		
GEOTECH.		
AIRPORT SYSTEMS		
INTERFACE		

DELHI INDIRA GANDHI INTERNATIONAL AIRPORT — GMR — L&T Construction

CLIENT : DIAL INTERNATIONAL AIRPORT LIMITED

PROJECT : DIAL GMADA INTERNATIONAL AIRPORT PHASE-3A DEVELOPMENT WORKS

CONCEPT : ASSA ABLOY

PROJECT CONSULTANT: Engineering Design and Research Center L&T Construction (EDRC)

INSTALLED AND SUPPLIED BY: MEHA TECHNOLOGIES PVT LTD

JOB No : JOB NO.

	NAME	SIGN	DATE
DSGN	G.J.P		02.10.2021
DRWN	G.J.P		02.10.2021
CHKD	A.K.		02.10.2021
APPD	V.T.		02.10.2021

TITLE: ARFF4 MEGADOOR 5800 X 5400 (RS6)

SCALE 1:50

DRAWING No. DIAL-LT-Q-UTL-A-10-102

PROJECTION FIRST ANGLE

SIZE A3 REV B

RELEASED FOR ☐ PRELIMINARY ☐ TENDER ☐ INFORMATION ☑ APPROVAL ☐ CONSTRUCTION