NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Accute Engineers
Pune

Date : 21.12.2019
Quote NO : SQT-19.20.2316
Kind Attn : Mr. Sanghdip R. Labade
Email Id : dipsangh@gmail.com
Contact No: 96890 96494

Subject : Quotation for High Speed Door, Sliding Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Automatic Sliding Metal Door - CMM Room	2400	2400	1	300,000	300,000	15,000	15,000
2	High Speed Door (Albany - RP300)	2400	2400	1	618,000	618,000	20,000	20,000
	Total - (1 + 2A + 3)					**918,000**		**35,000**
3	P&F Charges			3%		**27,540**		NA
	Total Without Taxes					**945,540**		**35,000**
	GST Extra @ 18%			18%		170,197		6,300
	Total With Taxes					**1,115,737**		**41,300**
4	Transportation Charges					**In Client Scope**		
5	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

1 Automatic Sliding Door

- Automatic Double Leaf Sliding Door with Rockwool Infil Panel of 50mm thick
- Size: (W) 2400 mm X (H) 2400 mm
- Operator : ASSA ABLOY MAKE (100% Imported from Europe)
- Panel : Insulated Panel with 50 mm thickness
- Panel Sheet : Both Side GI Sheets
- Radar Sensor for Auto Open and Close
- With vision window

2 Machine Protection Door - TIG Weld Application

- Flexible High-performance door, opening in vertical direction for use as a machine protection door.
- Self-supporting side frames made of aluminium with integreated safety switches, all fittings galvanized.Front of side frame lifts of for generous access to safety limit switches and fixtures.
- Door curtain made of RollTex® Plus – colour blue (similar RAL 5002), orange (similar RAL 2009), grey (similar RAL 7001).
- Opening / closing speed: max 2.3/1.3 m/s
- Bottom profile: anodized aluminium
- Protection: IP 55
- Control system: Frequency converter control system Albany MCC, based on Vector control and including boost function at start-up. Can be upgraded with a graphic display and foil keypad for easy guided operation. Easy access to all important information for operation and service
- Supply voltage : 3L(N)/380/400/415/440/480V; 50/60 Hz.
- Safety devices: Electrical safety contact edge, Photocell
- Manual activation: by means of a crank.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price	: Ex Works Pune
Delivery	: 6 - 7 weeks for Sliding Door and 10 - 11 weeks for High Speed and Machine protection Door from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.
Payment	: 80% Advance along with Confirmed Purchase Order & Balance before dispatch.
Validity	: Validity of Offer is 15 days from the date of quotation
Warranty	: 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Arjun Patil on 8551096333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd