NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Kotak Mahindra Bank, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company
GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Oberoi Reality
Mumbai.

Date : 10.12.2025
Quote NO : RR_25.26.0038R2
Kind Attn : Ms. Deepti Nirbhavane
Email Id : deepti.nirbhavane@oberoirealty.com
Contact No: 9867106946

Project Name & Location: Mumbai.

Subject : Commercial Offer for "L" Shape Automatic Retractable Roof required at 65th Floor **" for project Elysian Goregaon East "**

Dear Sir / Ma'am,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Conceptual snap	1
C.	General Conditions	2
D.	Terms & Condtions	2

A) Commercial Offer

Sr no	Description	Size (mtr)	Qty	Supply & Installation Charges in INR	
1	**"L" shape Automatic Retractable Roof (with Polycarbonate sheet).**	• (W) 2.8 X (L) 3.5 X (H) 1.7 • Single Panel • Installation Inclusive	2	2,033,000	**₹ 4,066,000**
2	**Non Comprehensive AMC Charges :- Scope of Non-Comprehensive Maintenance Includes routine inspection, servicing, and breakdown support.Spare parts and major repairs are chargeable.Minimum 4 scheduled visits per year. Service reports to be submitted after each visit.**				
3	**First Year after DLP**		1	116,000	**₹ 116,000**
4	**Second Year after DLP**		1	147,000	**₹ 147,000**
5	**Third Year after DLP**		1	168,000	**₹ 168,000**
6	**Fourth Year after DLP**		1	198,000	**₹ 198,000**
7	**Total without Taxes**				
8	GST Extra @ 18%		18%		**Extra At Actual**
9	P&F Charges @ 3%		3%		**Extra At Actual**
10	Transportation Charges				**Included**
11	Unloading Charges @ desired floor				**Included**

B)

Annexure 1 -Technical Specification
1. Polycarbonate sheet- 5mm solid Clear Transparent /Embossed
2. Profile : Powder coated MS+Aluminium Profile. (DFT 70-80 micron)
3. Guide : Top Track & bottom track material is MS
4. Motor Mechanism with general control panel b) Single Phase Bi-directional Motor c) Electrical connection - 12 amp, 220v Single phase d) Mechanical Limit Switch e) Rack and Pinion Arrangement f) Motor Make- European make g) Fire Alarm sensor integrted with Motor. h) Powder caoting - "Exnoable"
5. EPDM Gaskets and sealants



Exclude - As per meeting with client on 08th Dec 2025

1 BMS system/ fire system integration or any other integration system do not consider
2 Preventive mainatance for 2 years (4 times / year), not considered
3 3rd Party insurance
4 Remote control
5 Fire Alarm sensor integrted with Motor

Note -

1 For Mathadi we have considered Rs 15k only, if any further amount needed client will handle Mathadi
2 Lifting charges nil due to can use Maint lift to take material at 65th floor
3 Required Push button from both side
4 Need to add firamn axe and kept outside / on tarrace to brake the roof , if needed from outside
5 There will not be any waitng period at site / documentation delyed / payment dealyed / action delayed, else charge extra

C) General Conditions

1 Continuous uninterrupted access to installation section or as agreed seperately.
2 Provision of 230 V power supply for hand tools.
3 A dry and secure area, not in direct sunlight is to be provided for storage of product component
4 Access to site between 7 am to 8 pm should be provided.
5 Any storage costs for material due to delay outside of NIHVA, will be in client scope.
6 The project time indicated does not take into account adverse weather conditions that may prevent safe and efficient working practice. We reserve the right to extend the period accordingly.
7 Installation will start after receiving of Site Readiness Photographs or written Email communication.
8 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation.
9 For any reason if we need to stop our installation and demobilize the team without completing the work, then extra cost will be applicable for Remobilizing the Team.
10 If any change in dimension on actual site, quoted price will affect accordingly which will be in client scope.
11 After 1 year warranty, Non comprehensive AMC will be provided by NIHVA at an additional cost.

Note: Please find below List which are in Client Scope

Sr. No		Remark
1	Secured and fully covered Store area to keep the material.	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site.	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required.	In Client Scope
5	All structure support required.	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material, the additional quantities and wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 11 - 12 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing Approval.

Payment : 50% Advance along with Confirmed Purchase Order.
40% Before dispatch.
10% After Installation.

Validity : Validity of offer is 15 days from the date of quotation.

Warranty : 24 months from the date of supply (Preventive Maintenance - 3 Visit per year). It only covers damage caused due to mechanical system not due to natural calamity.

With Best Regards

Ashwini Jadhav

7410169333
NIHVA Technologies Pvt Ltd