NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Date : 23.03.2021
Quote NO : SQT.20.21.3118
Kind Attn : Prashant Patil
Email Id : pspatil@suroj.in
Contact No : 7447459207

Client Name : SUROJ BUILDCON PVT. LTD
Address : Bungalow No. 3, Liberty Society Phase-I, North Main Road
Koregaon Park, Pune 411 001, Maharashtra, India.

Project Name & Location: KSB Ltd Nashik

Subject : Quotation for Motorised Rolling Shutters

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	MS Motorised Rolling Shutter	4500	6000	6	152,000	912,000	15,000	90,000
2	MS Motorised Rolling Shutter	4000	5000	1	125,000	125,000	15,000	15,000
3	MS Motorised Rolling Shutter	4000	3800	2	105,000	210,000	15,000	30,000
4	MS Motorised Rolling Shutter	3000	3800	1	90,000	90,000	15,000	15,000
5	MS Motorised Rolling Shutter with Grill	4000	4000	2	136,000	272,000	15,000	30,000
				Total		**1,609,000**		**180,000**
6	P&F Charges			3%		**48,270**		
Total Without Taxes						**1,657,270**		**180,000**
GST Extra @ 18%				18%		**298,309**		**32,400**
Total With Taxes						**1,955,579**		**212,400**
7	Transportation Charges					**Extra at actual**		
8	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Motorised Rolling Shutters





Sr .No.	Specification	MS Motorised Rolling Shutter
1	Description	Motorised Rolling Shutter with MS slats with thickness of 1 mm.
2	Mounting Location area	Inside area / Outside area
3	Mounting Surface	Side Brackets: Optional = On Concrete
4	Curtain Panel	The panel made of 1 mm thick MS
5	Curtain panel size	75mm wide
6	Curtain Profile	Curved
7	Bottom Profile	M. S. Plate 2.5 mm thick with angle stiffener
8	Side Guide Profile	M.S." U" Shaped profile
9	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -as per w x h
10	Hood Cover	Made of GI Sheet Thickness 0.9 mm GF mm
11	Surface finish	2 Coats (each coat of 35 microns DFT) of EPOXY polyamide-based enamel finish of approved color and make over a Coat (each one coat 25 microns DFT) of EPOXY polyamide based red oxide zinc phosphate primer
12	Operation	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1. Installation will start after receiving of Site Readyness Photographs or written Email communication.
2. We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation
3. For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.
4. If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil structural work required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price	: Ex Works Pune
Delivery	: 6-7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.
Payment	: 80% Advance along with Confirmed Purchase Order & Balance against readyness of material before dispatch.
Validity	: Validity of Offer is 15 days from the date of quotation
Warranty	: 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Shrikant Mirkute on 8551098333.**

With Best Regards

Pradeep Shinde

8551096333

For NIHVA Technologies Pvt Ltd