TENDER SPECIFICATION

FOR

BOOM BARRIER

Doc. No. 323-MD-026
Rev. 0, Date 24-Nov-2014

0	24/Nov/14	First Issue
Rev.	Date	Description

1. INTRODUCTION

JSW MI is setting up sitting & cut to length line project at Khed City Dist.-Pune (M.S.), India. The project site is near to Pune city. For this project, the items as per enclosed sheet/ drawings are required.

2. SITE CONDITION

Climatic conditions

Max. ambient air temperature	45°C
Max. relative humidity	87% (In rainy season)
Max. annual rainfall	1000 mm
Max. wind pressure	140.4 Km/hr
Altitude above mean sea level	700 m
Seismic zone	III

Working conditions

Input power supply	3 phase, 415 ±10% V, 50 ± 3% Hz
Temperature	10 – 50 °C
Relative humidity	87%

3. SCOPE OF THE WORK (supply & services)

The scope of work includes design, engineering, supply, testing, erection and commissioning (as may be applicable for the scope) of Boom Barrier as per the details given along with this document.

The bidder to submit the offer along with all relevant details, drawings, reference list and relevant documents as below:

- Intended deviations (if any) from the specified requirements / specifications.
- Design / drawing (wherever applicable).
- Standard catalogue (wherever applicable).
- Time schedule & delivery period.
- Make of standard bought out items.
- References of similar jobs done.
- Period and terms & conditions.
- List of inclusions / exclusions.
- Guarantee / warrantee.

4. PRICE

The price to be submitted including all expenses and towards the following

1. Designing, Engineering, manufacturing and supply including packing, forwarding, loading, freight & insurance charges for the delivery of all materials & services up to project site
2. Erection & commissioning (wherever applicable) including all expenses for air / train / taxi fare from the place of departure to project site, lodging & boarding, local transport and

any other expenses during stay of bidder`s representative at project site for required duration.

3. Taxes and duties as applicable.

5. SPECIAL NOTE

The scope of supply shall not be limited to the services / equipments mentioned in this document. If any additional equipments / services deemed to be required to complete the system / equipment / services then the same to be included in the offer.

6. TECHNICAL SPECIFICATION FOR BOOM BARRIER

Sr. No.	Particulars	Description
1.	Drive	Block-able continuous torque motor Electro- mechanical drive unit operated by micro processor based Control panel. The drive unit consists of gears, shaft, crank, safety clutch and ball bearings etc. Which shall be encapsulated in weather-proof, oil filled chamber for maintenance free and long lasting performance. The operation of the Drive Unit is silent and maintenance free.
2.	Location	Boom barrier shall be just after the 10 mtr sliding gate. In general the 10 mtr sliding gate will be keep opened for the length approx. 5-7.5 mtr and rest shall be opened as and when required. The opened sliding gate space shall be obstructed by the 5 mtr boom barrier. (Refer attached dwg.No. 323-A-020 Sheet 1/2 Rev.D)
3.	Qty.	1 Nos.
4.	Required width	5 Mtr.
5.	Application	Outdoor
6.	Running time	3 Sec.
7.	Wind resistance up to	140.4 Km/hr
8.	Operating temperature	-5 º to +55 º
9.	Boom specification	Boom length 5 Mtr., Rectangular boom with red reflecting warning tape & rubber buffer.
10.	Color	Combination of white & red. The paint used will be anti-corrosive and luminous for night & bad weather.
11.	Power-off	Manual opening possible
12.	Duty cycle	100 %
13.	Integration	To integrate with the sliding gate operation.
14.	Material of construction	Carbon steel with powder coated finish and the housing top cover is made out of high-impact engineering plastic with customizable SS sheets
15.	Safety	Loop detector / Infrared sensors to be used to prevent barriers from closing on the vehicle.
16.	Battery back-up	In case of power failure, battery backup operation is available
17.	Certification	CE certified
18.	Housing dimensions	Vendor to specify
19.	Power required	Vendor to specify
20.	Total Weight	Vendor to specify
	Standard Accessories/ Features:	
1.	Electrical equipment suitable for 3 phase 415 ± 10 % V / single phase 230 V/50 Hz AC supply.	
2.	Magnetic Loop Detector to be provided.	
3.	Additional Push Button to be provided.	

4.	Remote Control with receiver to be quoted extra.
5.	Key Switch to be provided.
6.	Safety Photocell to be provided.
7.	Optical wireless safety edge sensor to be provided.
8.	Flashing Light with Alarm to be provided.
9.	The barrier will automatically go back when it meets any obstacle during closing.
10.	Barrier opening and closing can also be controlled using a touch button or remote control.
11.	AC motor should be more powerful and maintenance free.
12.	Connection of infrared photocell, loop detector & IC system are reserved for other function.
13.	Green light or red light are used here for indicating the position of the beam.
14.	Manual operation in case of power failure.
15.	Built-in Motor Cooling fan to avoid overheating problems.
16.	Foundation bolts to be provided by supplier
17.	Highly compact dimensions & extremely silent operation.
18.	Motor protected by internal thermal switch.
19.	All equipment shall be dust and vermin proof and also capable to work in dusty environment.
20.	Necessary GA drawings to be provided.
21.	2 Sets of operational & maintenance manual.
22.	Set of spares for 2 years normal operation as per supplier`s recommendation.
23.	Supply, installation, erection and commissioning shall be in supplier’s scope.