NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Sahyadri Farmers Producer Co.Ltd.
Sr. No. 1102/8, zbehind Police Head Quarter,
A/P adgaon, Nashik 422003

Date : 09.04.2021
Quote NO : **AS_20.21.0005R2**
Kind Attn : Mr. Janardan Shelke
Email Id : janardan.shelke@sahyadrifarms.com
Contact No: 8411961929

Project Name & Location: Semi-Automated Rice Packaging Machine, Nashik

Subject : Quotation for Semi-Automated Rice Packaging Machine

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	General Conditions	2
C.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Semi-Automated Rice Packaging Machine** **Simplex Bagging Machine** Weighing Range: 5 to 50 kg Accuracy: +/- 10gm Speed: 450 bags/hour Construction: 3 feeding Gate, Corse feed, Fine feed and Super fine individual gates 2 Load Cell Based System Actuator: SMC Japan make Weighing Controller imported Construction: SS316 Recipe setting by touch of button Limit Switch: fpr the Bag holding (Schneider) Weight output signal will be given to potential Free Terminal blocks Packaging report available in the weighing The No's of bag packed and totalizer of the quantity packed Control panel with Schneider's Accessories **STITCHING CONVEYOR** Conveyor Length: 3000mm Type: Belt Conveyor/Slat Chain with Strips conveyor Drive motor: 1 HP Motor with Gear Box, Worm type (40 ratio) Control panel with Schneider accessories Conveyor Dimensions: L: 3000mm, W: 500mm, H: Adjustable By Screw (450mm – 600mm) Portable Stitching Stand Construction: MS with Powder Coating **TELESCOPIC STITCHING STAND AND HEAVY DUTY GABBER MACHINE** Telescopic Stand with Gear Adjustable 1HP Foot mount motor, 1400rpm Heavy Duty Bag Closing machine Control panel with Siemens Accessories Double Needlefour Thread Bottom Frame with movableT ape Attachment Stand	**1**	**1,170,300**	**1,170,300**	**Included**	**Included**
		Total		**1,170,300**		**Included**
		Special Discount for Sahyadri Farmers				**90,218.00**
		Final Amount After Discount				**1,080,082.00**
2	P&F Charges	3%				**Included**
	GST Extra @ 18%	18%				**Extra at Actual**
3	Transportation Charges					**Included**
4	Unloading Charges @ Site					**In Client Scope**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

B) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

C) Terms & Conditions

Price	: Ex Works Pune.
Delivery	: 6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.
Payment	: 40% Advance along with Confirmed Purchase Order, 40% Balance against readyness of material before dispatch and 20% immediately after installation.
Validity	: Validity of Offer is 15 days from the date of quotation.
Warranty	: 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Rohit Kadgave on 7410175333.**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd