NIHVA TECHNOLOGIES

Weight Estimation Sheet

CLIENT	SJ Contractor							DATE	1/8/2024
PROJECT	Motorised Sliding Gate							LOCATION-	Pune
FINISH SIZE	10M*2M								
	Sizes (In mm)								
Description	Material Grade	Sp.Gravity	Dia	Width	Height	Thickness	Length	QUANTITY	WEIGHT (KG)
A.Square Tube-Outer	MS	7.85		96	48	3.2	27200	1	188.0
B.Square Tube-Inner	MS	7.85		25	25	2.6	1904	65	226.3
Post	MS	7.85						5	260.0
MS BAR (in metre)	MS	7.85	25				24	1	92.5
IF ISMC 75 IN OUR SCOPE THEN(in metre)	MS	7.85					24	1	168.0
							Weight For Single Quantity		1121.8
							Weight For Required Quantity	1	1121.8

Motor Consider 1000 kg

Safety Factor Considered 1.2

Distance Between 2 Cons.Tubes Centre To Centre=175 mm

NIHVA TECHNOLOGIES

Weight Estimation Sheet

CLIENT	SJ Contractor							DATE	1/8/2024
PROJECT	Motorised Sliding Gate							LOCATION-	Pune
FINISH SIZE	12M*2M								
	Sizes (In mm)								
Description	Material Grade	Sp.Gravity	Dia	Width	Height	Thickness	Length	QUANTITY	WEIGHT (KG)
A.Square Tube-Outer	MS	7.85		96	48	3.2	31200	1	215.7
B.Square Tube-Inner	MS	7.85		25	25	2.6	1904	77	268.1
Post	MS	7.85						5	240.0
MS BAR (in metre)	MS	7.85	25				28	1	107.9
IF ISMB 75 IN OUR SCOPE THEN(in metre)	MS	7.85					28	1	196.0
							Weight For Single Quantity		1233.2
							Weight For Required Quantity	1	1233.2

Motor Consider 1000 kg

Safety Factor Considered 1.2

Distance Between 2 Cons.Tubes Centre To Centre=175 mm

Prepared by
Jayesh Shinde

weight of post