NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad. Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

SCON Projects Pvt. Ltd
Samarth House,S.NO.116, Hissa No.3/1, 3/3,3/10,
Pune- Bangalore Highway, Near Shell petrol Pump,
Warje, Pune- 411058

Date : 19.03.2020
Quote NO : SQT/19-20/2487
Kind Attn : Ms. Madhuri Date
Email Id : purchase@sconprojects.com
Contact No: 9553002148

Project : **Husqvarna Project Nasik**

Subject : Quotation for Dock Leveler, Full Height Turnstile

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2 , 3
C.	General Conditions	4

A) Commercial Offer


Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Option -1A : Swing Dock - NIHVA Make Dock Leveller 6 Ton	2000	2500	2	202,000	404,000	15,000	30,000
2	Option -1B : Swing Dock - ASSA ABLOY Make Dock Leveller 6 Ton	2000	2500	2	410,500	821,000	15,000	30,000
3	Option - 2 : Telescopic Dock - 6 Ton ASSA ABLOY Make	2000	2500	2	513,000	1,026,000	15,000	30,000
4	Dual Full Height Turnstile (Motorised)			2	685,000	1,370,000	15,000	30,000
				Total		**3,621,000**		**120,000**
5	P&F Charges			3%		108,630		
	Total Without Taxes					3,729,630		120,000
	GST Extra @ 18%			18%		671,333.40		21,600
	Total With Taxes					**4,400,963**		**141,600**
6	Transportation Charges					In Client Scope		
7	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad. Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

1 NIHVA Dock Leveler





Sr. No	Description	Specification
1	Hydraulic Power pack	1 HP, 3PH
2	Control Panel	By push button Deck UP & Deck Down
3	Deck / Lip operation	By push button Deck UP & Deck Down
4	Loading platform height from road Level	4 feet (1200 mm)
5	Travel above / below from Dock level height	350 mm ; 200 mm
6	Deck platform size	2000mm (W) x 3000mm (L)
7	Lip sizes	400 mm
8	Clear Pit dimensions	2040mm (W) x 3000mm (L) x 485mm (H)
9	Drive type	Drive by electric Motor
10	Power Consumption	0.75 kw Motor
11	Degree of protection for motor	IP 55
12	Motor RPM	1410 rpm
13	Pump design flow	1.8 LPM
14	Pump pressure	200 bar
15	Safety valve set pressure	90 bar
16	Pump type	Gear
17	In built safety valve	Yes
18	Volume of oil receiver	8 Ltr
19	No of Deck Cylinders	2 Nos
20	No of Lip Cylinders	1 No
21	Dock Bumpers	1 Pair included

2 ASSA ABLOY Swing Dock Leveler





Sr. No	Description	Specification
1	Capacity	6 T
2	Control Unit Protection Class	IP54
3	European Standards	EN 1398
4	Coating	RAL 5010
5	Control unit	Supervision 105, 105A, i105, i305 Service & fault Indicator
6	Vertical working range Rise above dock Fall below dock	250 - 620 mm270 - 350 mm
7	Lip material & length	Steel, 400 / 500 mm
8	Nominal voltage	400V 3-phase

3 **ASSA ABLOY Telescopic Dock Leveler**





Sr. No	Description	Specification
1	Frame type	T
2	Tear plate	8 mm
3	Capacity	60 KN
4	lip extension	500mm
5	Steel lip bevelled	40 mm
6	Lip material & length	Steel, 400 / 500 mm
7	Control Unit Protection Class	IP54
8	European Standards	EN 1398

4 **Dual Full Height Turnstile**



Sr. No.	Description	Specifications
1	Framework	304 /306 Stainless steel
2	Thickness	1.2 mm
3	Finishing	Brushed
4	Pass Width	500 -700 mm
5	Operation Direction	Both Sided / Bi direction
6	Power Voltage	AC 220V + /-10% 50-60 HZ
7	Work Environment	Indoor / Outdoor
8	Driving Voltage	DC 24 V

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune :

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Transportation : Extra as applicable

Delivery : 10 - 11 weeks for ASSA Abloy make and 5 -6 weeks forNIHVA make from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil on 8551096333** For any further Clarification /Information in this Concern.

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd