NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Brevion Technology
Belgum KA

Date : 27.08.2021
Quote NO : **MHE_21.22.0020R2**
Kind Attn : Mr. Pavan Shivangekar
Email Id : pavan.shivangekar312@gmail.com
Contact No: 9538568035

Project Name & Location: Brevion Technology, Belgum KA

Subject : Quotation for Take Up Conveyor

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges considering in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Take Up Conveyor (Height adjustment by Screw Mechanism)**	**2**	**2,77,000**	**5,54,000**	**20,000**	**40,000**
		Total		**5,54,000**		**40,000**
	P&F Charges	3%		**16,620**		
	Total Without Taxes			**5,70,620**		**40,000**
	GST Extra @ 18%	18%		**1,02,712**		**7,200**
	Total With Taxes			**6,73,332**		**47,200**
2	Transportation Charges					**Extra At Actual**
3	Insurance					**Extra At Actual**
4	Unloading Charges @ Site					**In Client Scope**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Take Up Conveyor

Sr. No.	Parameters	Specification
1	Product Type	Cement/Charcoal Bags
2	Product Weight	50 Kg
3	Loading/Unloading	Manual
4	Cantiliver Height	1500 mm
5	Belt Width	700 mm
6	Up & Down through	Screw Mechanism
7	Contact Parts	MS
8	Non Contact Parts	MS
9	Gear Motor	Bonfiglioli

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 8-9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance 20 % against readyness of material before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation.

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Rohit Kadgave on 7410175333.**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd