NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

COVENANT PROJECT MANAGEMENT PTE LTD
SINGAPORE

Date : 03.03.2022
Quote NO : **MHE_21.22.0061**
Kind Attn : Mr. Cindy Hooi
Email Id : cindy.hooi@covenantpm.com
Contact No: 65 81124005

Project Name & Location: COVENANT PROJECT MANAGEMENT PTE LTD SINGAPORE

Subject : Quotation for Telescopic Belt Conveyor

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in SGD(S$)		Installation Charges in SGD(S$)	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Telescopic Belt Conveyor** • Total Length- 15.9mtr (Fixed-6mtr, Extended-9.9mtr) • Capacity- 30mtr/min • Belt Width - 600 mm	**7**	**30,000**	**2,10,000**	**3,500**	**24,500**
	TOTAL EXCLUDING TAXES			**2,10,000**		**24,500**
2	GST Extra @ 18%	18%	**Extra At Actual**			
3	P&F Charges	3%	**Extra At Actual**			
4	Transportation Charges		**On CIF Basis**			
5	Insurance Charges		**Extra At Actual**			
6	Unloading Charges @ Site		**In Client Scope**			

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Telescopic Belt Conveyor

Sr. No.	Parameters	Specification
1	Material to be conveyed	Boxes
2	Capacity	50 kg/mtr
3	Telescoic speed	8-12 Mtr/min
4	Belt speed	15-30mtr/min
5	Belt Width	600 mm
6	Belt Type	2 Ply 3.2 mm PVC, with anti-collision strip
7	Conveyor Type	Collapsible boom type hinged Telescopic belt conveyor
8	Length Of Conveyor	Fixed Length : 6000 mm Telescopic (Expanded) : 9900 mm Total Length : 15900 mm
9	Main Body Of Conveyor	MS Powder coated
10	Direction	Both Forward and Reverse direction
11	Working height	Min.850 mm and Max. 1100 mm
12	Inclination Height	Max. 1000 mm
13	Inclination Angle	6 deg.
14	Speed adjustment	VFD (Schneider /Allen Bradley/Delta)
15	Gear Box	Bonfiglioli
16	Driven Motor Make	CG/BBL , IE2
17	Movement	Wheel for easy movability
18	Spot Light is provided at End of Conveyor. (Advanced feature)	

C) General Conditions

1 Installation will start after receiving of Site Readiness Photographs or Written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation.

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 After 1 year warranty, Non comprehensive AMC will be provided by NIHVA at an additional cost.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 10-12 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15days from the date of quotation.

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Vijay Tarak on 85510 93333.**

With Best Regards
Pratibha Mete
85308 72333
For NIHVA Technologies Pvt Ltd