Sales Quote

An ISO 9001:2008 Certified Company

Quote No: SQT.18-19.1673 **Date: 05/31/2019**

Aetherr Corp

H-7, Konark Campus, Viman Nagar,Nagar Road,
Pune - 411 014
Maharashtra -India

Kind Attention: Mr. Bhagyesh Vilas Gajbhar

Phone:- (901) 116-8007
Email ID: bhagyesh@aetherrcorp.in

Project Name And Location :

Subject : Quote for -High Speed Door and Motorised Rolling Shutter

Dear Sir,

Thank you for your opportunity and trust shown on “NIHVA.” your preferred partner for innovative solutions.This has reference to your above mentioned requirement as well as our subsequent communication. Please find below our best offer.

Commercial Offer :-

Sl.No.	Description	Price	Qty	Unit	Total
1.	High Speed Door RR392 ASSA ABLOY-ALBANY Rapid Roll up Door - RR 392 (100% Imported with all components – made in Germany) Size : (W) 2500 mm x (H) 6000 mm Technical Specifications: • Basic Equipment : High-Speed Roller Door with transparent curtain and blue (RAL 5002) reinforcement stripes, optional red (RAL 3002). Door with curtain tension. • Drive Unit : Motor IP 55, either RH or LH as an option, with control cable. • Control system : MCC Vector Control - frequency converter control system for opening/closing speed 1,0 m/s • Power supply : 3/(N)/PE/230/400/415 v; 50 Hz • Safety : Safety contact edge, Safety photocell transmitter / receiver inside side columns. (Supply + Installation)	₹ 821,000.00	5	Nos	₹ 4,105,000.00
2.	Motorised Rolling Shutter Size : (W) 5820 mm x (H) 6000 mm Technical Specifications : M S Slat : 1 mm Thick, Curved Type Profile with Heavy duty Shaft, Guide, Hood Cover, Motor Indirect Drive with Painting	₹ 248,000.00	1	Nos	₹ 248,000.00

Sales Quote

An ISO 9001:2008 Certified Company

Quote No: SQT.18-19.1673					Date: 05/31/2019
Sl.No.	**Description**	**Price**	**Qty**	**Unit**	**Total**
	(Supply + Installation)				
3.	Motorised Sliding Gate Size : (W) 4000 mm x (H) 2500 mm	₹ 316,000.00	1	Nos	₹ 316,000.00
4.	Motorised Sliding Gate Size : (W) 5000 mm x (H) 2500 mm	₹ 327,000.00	1	Nos	₹ 327,000.00
5.	High Speed Door HS9020G ASSA ABLOY (Albany)- HS9020G (100 % Imported from Europe) Size : (W) 2500 mm x (H) 3000 mm Technical Specifications : Operating speed : Opening: up to 1,2 m/s 2, closing: 0,5 m/s . The fast opening and closing speed improves your traffic flow, provides employee comfort and saves energy Wind load resistance : Class 1 (300 N/m2), maximum wind load while closing 50 N/m2 Other Specifications : a. The soft bottom edge has no rigid parts. It molds around any obstruction to prevent injury or damage. b. When an object hits the door, the fabric curtain absorbs the impact and releases itself from its side guides without causing damage or being damaged itself. c. Vision Window - One row of 400 mm height (Supply + Installation)	₹ 556,000.00	1	Nos	₹ 556,000.00
6.	Motorised Rolling Shutter Size : (W) 4000 mm x (H) 4000 mm Technical Specifications : M S Slat : 1 mm Thick, Curved Type Profile with Heavy duty Shaft, Guide, Hood Cover, Motor Indirect Drive with Painting (Supply + Installation)	₹ 147,000.00	1	Nos	₹ 147,000.00
7.	Motorised Rolling Shutter Size : (W) 6000 mm x (H) 4000 mm Technical Specifications : M S Slat : 1 mm Thick, Curved Type Profile with Heavy duty Shaft, Guide, Hood Cover, Motor Indirect Drive with Painting (Supply + Installation)	₹ 187,000.00	1	Nos	₹ 187,000.00

Sales Quote

An ISO 9001:2008 Certified Company

Quote No: SQT.18-19.1673					Date: 05/31/2019
Sl.No.	**Description**	**Price**	**Qty**	**Unit**	**Total**

Sub Total	₹ 5,886,000.00
Grand Total	**₹ 5,886,000.00**

GST Pune	27AAECN0437H1ZM

General Pre requisite at site

1 Finished Flooring after curing (Without Water)
2 Electrical Supply on the site single phase/three phase points at different places
3 Provide electrical cables near to the installation machinery
4 Fork lift/crane to be provided if required
5 Scaffolding require for Installation it is in client scope

Limit of Supply

1 Provide place to store the material to be installed
2 Be responsible for the safe custody of all material
3 Provide place to safely store all the tools of installation
4 Provide change & rest room for the workers

Quote/Supply is based on

1 BOM is calculated as per standard quantity measurement
2 In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account
3 Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1 Unloading from truck placement on site
2 Electrical connection for control panel

Client Scope

1 Once our project gets complete for any additional work to & fro loading & boarding of our service technicians is in client scope
2 Any civil / masonry/structural work required to support are in client scope
3 All structure support is in client scope
4 NIHVA Will provided structure drawing only if required
5 Existing/Repair/ Modification/ Refurbishment charges will be extra

Terms & Conditions

1 **Price** : Ex works Pune
2 **P & F Charges**: @3% of Total Supply Value
3 **Freight Notes**: Extra as applicable
4 **Payment**: 80% Advance along with confirm purchase order & Balance 20% before dispatch
5 **Taxes**: GST @ 18%
6 **Validity**: Validity of Offer is 15 days from the date of quotation.

Sales Quote

An ISO 9001:2008 Certified Company

Quote No: SQT.18-19.1673 **Date: 05/31/2019**

7 **Warranty**: 12 months from the date of supply
8 **Delivery** : 10-12 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval
9 **Insurance :**Extra As applicable

Please feel free to Contact **Mr. Arjun Patil on (855) 109-6333** for any further Clarification /Information in this Concern.

With Best Regards

Smita Khare
+91-9637991333
For Nihva Technologies Pvt Ltd