NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Huhtamaki PPL Ltd
Village Ransai, KM.16,
Khopoli - Pen Road,
Taluka : Khalapur, Dist - Raigad
402107

Date : 19.02.2020
Quote NO : SQT.19.20.2450
Kind Attn : Mr. Bapu Gawali
Email Id : bapu.gavali@huhtamaki.com
Contact No: 8879068207

Project Name & Location: Huhtamaki PPL Ltd

Subject : Phase 1 : Quotation for Sectional Door, High Speed Door, Dock Leveler, Dock Shelter, Rolling Shutter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1-2
B.	Technical Specification	3-5
C.	General Conditions	6
D.	Terms & Condtions	6

A) Commercial Offer

Sr No	Description	Location	Size		Qty	Supply Charges in INR		Installation Charges in INR	
			Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
	Phase 1 - Unit no 1 : Doors								
1	High Speed Doors - RR300+ Alu	Hall No. 1 Entry	3000	4000	1	6,49,000	6,49,000	15,000	15,000
2	High Speed Doors - RR300+ Alu	Intermediate Store Exist	3000	4000	1	6,49,000	6,49,000	15,000	15,000
3	High Speed Doors - RR300+ Alu	Daekang Entrance	3000	4000	1	6,49,000	6,49,000	15,000	15,000
4	High Speed Doors - RR300+ Alu	WNH Cofil Entry	3000	4000	1	6,49,000	6,49,000	15,000	15,000
5	High Speed Doors - RR300+ Alu	Packing Entrance	3000	4000	1	6,49,000	6,49,000	15,000	15,000
6	High Speed Doors - RR300+ Alu	Slitting Entrance	3000	4000	1	6,49,000	6,49,000	15,000	15,000
7	High Speed Doors - RR300+ Alu	Cylinder Loading / Unloading	3000	3000	1	6,32,000	6,32,000	15,000	15,000
8	High Speed Doors - RR392	Dispatch Loading	3000	3000	1	7,63,000	7,63,000	15,000	15,000
9	High Speed Doors - RR392	Raw material	3000	6000	1	8,39,000	8,39,000	15,000	15,000
10	High Speed Doors - RR392	Granuals RMS	3000	6000	1	8,39,000	8,39,000	15,000	15,000
11	Sectional Door	Cylinder Loading / Unloading	3000	3000	1	2,85,500	2,85,500	15,000	15,000
12	Dock Leveler - 6 Ton	Cylinder Loading / Unloading	2000	2500	1	3,35,500	3,35,500	15,000	15,000
13	Inflatable Dock Shelter	Cylinder Loading / Unloading	3600	3755	1	4,24,500	4,24,500	15,000	15,000

	Phase 1 - Unit no 2 : Doors								
1	High Speed Doors - RR300+ Alu	Dispatch	3000	4000	1	6,49,000	6,49,000	15,000	15,000
2	High Speed Doors - RR300+ Alu	RMS 2	3000	3000	1	6,32,000	6,32,000	15,000	15,000
3	High Speed Doors - RR300+ Alu	RMS Unloading - Tube FG Dispatch	3000	3000	1	6,32,000	6,32,000	15,000	15,000
4	High Speed Doors - RR300+ Alu	Cylinder receiving Area	3000	3000	1	6,32,000	6,32,000	15,000	15,000
5	Sectional Door	Dispatch	3200	2800	1	2,97,500	2,97,500	15,000	15,000
6	Sectional Door	RMS 2	3000	3000	1	2,85,500	2,85,500	15,000	15,000
7	Sectional Door	RMS Unloading - Tube FG Dispatch	3000	3000	1	2,85,500	2,85,500	15,000	15,000
8	Sectional Door	Cylinder receiving Area	3000	3000	1	2,85,500	2,85,500	15,000	15,000
9	Dock Leveler - 6 Ton	Dispatch	2000	2500	1	3,28,000	3,28,000	15,000	15,000
10	Dock Leveler - 6 Ton	RMS 2	2000	2500	1	3,28,000	3,28,000	15,000	15,000
11	Dock Leveler - 6 Ton	RMS Unloading - Tube FG Dispatch	2000	2500	1	3,28,000	3,28,000	15,000	15,000
12	Dock Leveler - 6 Ton	Cylinder receiving Area	2000	2500	1	3,28,000	3,28,000	15,000	15,000
13	Inflatable Dock Shelter	Dispatch	3600	3755	1	4,24,500	4,24,500	15,000	15,000
14	Inflatable Dock Shelter	RMS 2	3600	3755	1	4,24,500	4,24,500	15,000	15,000
15	Inflatable Dock Shelter	RMS Unloading - Tube FG Dispatch	3600	3755	1	4,24,500	4,24,500	15,000	15,000
16	Inflatable Dock Shelter	Cylinder receiving Area	3600	3755	1	4,24,500	4,24,500	15,000	15,000
17	Motorised Rolling Shutter	Pouching Scissor Lift Door	2500	2000	4	96,000	3,84,000	15,000	60,000
					Total		**1,51,05,500**		**4,95,000**
18				P&F Charges	3%		**4,53,165**		
				Total Without Taxes			**1,55,58,665**		**4,95,000**
				GST Extra @ 18%	18%		28,00,560		89,100
				Total With Taxes			**1,83,59,225**		**5,84,100**
19				Transportation Charges			**Extra at Actual**		
20				Unloading Charges @ Site			**Client Scope**		

NIHVA TECHNOLOGIES PVT. LTD.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

High Speed Door - ASSA ABLOY RR300+ Alu

Sr. No	Description	Specifications
1	Door panel:	Transparent PVC with Red (RAL 3002) reinforcement stripes.
2	Barrel:	Aluminium, anodized with shafts made of galvanized steel
3	Wind Reinforcement:	Door Panel wind tabs for improved wind resistance
4	Wind Speed	Class 1
5	Side Frames:	Aluminium profiles, anodised
6	Drive Unit:	Motor IP 55, either RH or LH as an option, with control cable (standard length = height of door)
7	Self-opening:	Standard - the door can be opened partially up to 1,8 m by releasing the brake manually.
8	Bottom beam:	Anodized extruded aluminium.
9	Control system:	MCC Vector Control - frequency converter control system for a dynamic, smooth door movement, located close to the drive unit Max. Opening Speed 2.2m/s Max. Closing Speed 0.9 m/s
10	Safety features:	Safety edge, safety photocell (Transmitter/Receiver) inside side columns
11	Loop Detector	Considered (Both Sides)
12	Push Button	Considered (Both Sides)
13	Motor Cover	Included
14	Hood Cover	Included

High Speed Door - ASSA ABLOY RR392

Sr. No	Description	Specifications
1	Door panel:	Transparent PVC with Red (RAL 3002) reinforcement stripes.
2	Barrel:	Aluminium, anodized with shafts made of galvanized steel
3	Wind Class	Class 2
4	Wind Reinforcement:	Curtain with Tension to the bottom
5	Side Frames:	Galvanised Steel Profile
6	Drive Unit:	Motor IP 55, either RH or LH as an option, with control cable (standard length = height of door)
7	Self-opening:	Standard - the door can be opened partially up to 1,8 m by releasing the brake manually.
8	Bottom beam:	Anodized extruded aluminium.
9	Control system:	MCC Vector Control - frequency converter control system for a dynamic, smooth door movement, located close to the drive unit Max. Opening Speed 2.2m/s Max. Closing Speed 0.9 m/s
10	Safety features:	Safety edge, safety photocell (Transmitter/Receiver) inside side columns
11	Loop Detector	Considered (Both Sides)
12	Push Button	Considered (Both Sides)
13	Motor Cover	Included
14	Hood Cover	Included

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

Sectional Door - ASSA ABLOY

Sr. No	Description	Specification
1	Vision Windows	2 Nos at central panel
2	Opening Direction & Mounting	Horizontal
3	Opening/Closing Speed	CDM9 0,28 m/s
4	Door Material	GI Steel
5	Panel Thickness	42 mm Square Grid, steel sheet
6	Filling	CFC-free polyurethane
7	Panel colour	RAL 9002 Grey White Powder coated
8	Door sealent	All door sealants made of EPDM rubber, temperature resistant
9	Panel Flame Retardent standrad	Flame retardant polyurethane foam according DIN4102-class B
10	Water Penetration	EN 12425 class 3
11	Air Permealibity	EN12426 class 3
12	Wind Load	EN21424 class 3
13	Thermal Transittance	EN 12428 1.10W /m2K
14	Bottom sealing	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber
15	Door saftey	Doors equiped with spring break device
16	Incase of Power failuer	Doors to be equiped with quick release fuction
17	Operator power conumption	Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W
18	Drive Unit & Mounting Type	Single phase 230V direct drive on shaft
19	Emergency Operation	by Disengagement rope manual
20	Operating Switch	Up/Down Keypad + stopbutton
21	Locks : Lock bolt	The Lock bolt locks the door from the inside, without the use of a key. The Lock bolt is not visible from the outside.
22	Environmental Green Product Declaration Certification	As per ISO 14025 and EN 15804

Dock Leveler - ASSA ABLOY

Sr. No	Description	Specification
1	Capacity	6 T
2	Control Unit Protection Class	IP54
3	European Standards	EN 1398
4	Coating	RAL 5010
5	Control unit	Supervision 105, 105A, i105, i305 Service & fault Indicator
6	Vertical working range	250 - 620 mm
7	Rise above dock	270 - 350 mm
8	Platform tear-plate thickness with platform reinforcements according to the load capacity	6/8, 8/10 mm
9	Lip material & length	Steel, 400 / 500 mm
10	Nominal voltage	400V 3-phase

NIHVA TECHNOLOGIES PVT. LTD.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

Inflatable Dock Shelter Door - ASSA ABLOY

Sr. No	Description	Specification
1	Door type	Dock Shelter DS6070B
3	Nominal Height	3755 mm
4	Nominal Width	3600 mm
5	Top bag extension	1000 mm
6	Side Bag Extension	650 mm
7	Fabric Quality	PVC Coated Polyster
8	Fan	230V, 1 Phase, 50Hz, 250W
9	Niose Level	65dBA in working position
11	Operating	by Switch Control
21	Temperature Range	-30 to + 60 Degree Celcuis

Motorised Rolling Shutter - NIHVA Make

Sr. No	Description	Specification
2	Mounting Location area	Inside area / Outside area
3	Mounting Surface	Side Brackets: Optional = On Concrete
4	Curtain Panel	The panel made of 1.0mm thick MS.
5	Curtain panel size	75mm wide
6	Curtain Profile	Curved
7	Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	Hood Cover	Made of GI Sheet Thickness 1 mm
11	Surface finish	Two Coats of Primer and two coast of Synthetic Enamel
12	Motor	Indirect Drive - Jielong Make Motor

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 10-12 weeks for Scissor lift from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Arjun Patil on 8551096333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd