ips mehtalia	IPS-MEHTALIA PVT. LTD.		Client	THERMAX
	Consulting Engineers • Construction Management • Commissioning & Qualification		Project No.	MBD22927
	Unit B 101-109, 1st Floor, Kailash Vaibhav Ind Complex, Park Site, Vikhroli (W), Mumbai - 79		Made / App	ASP / PDP
	Document Title	Datasheet for Scissor Lift	Rev	R0
	Document No.	IPS-MBD22927-ME-1432	Date	24-Jul-23

Sr. No.	Description	IPS- Mehtalia Specification	Vendor to Specify
A	General		
1	Tag No.	SL-101	Yes
2	Type	Hydraulic lifting platform and hydraulic power pack with requisite hose pipes / fixed piping.	Hose piping
3	Location	Near unloading bay of stores	In client scope
4	Quantity	1 no.	Yes
5	Capacity (Kgs)	1000	Yes
6	Safety Standard	EN 292 / EN 1570	Yes
7	Platform Size (mm)	Bidder to specify	4800 (L) x 3800 (W)
8	Pit Size (mm)	5000 (L) x 4000 (W)	Yes
9	Max. Travel (up/down) mm	4000 / Bidder to specify	4000
10	Travel		
i	Speed (m/min)	Bidder to specify	2-3m/min
11	Overall dimensions (l x w x d)	Bidder to specify	4800 x 3800 x 4000
12	Operating oil pressure (bar)	Bidder to specify	At the time of installation
13	Max. oil pressure (bar)	Bidder to specify	At the time of installation
14	Safety valve set pressure (bar)	Bidder to specify	At the time of installation
15	Platform Surface	Bidder to specify	Chequered plate
15	Thickness		
i	Platform (mm)	Bidder to specify	6mm to 8mm
iii	Scissors (mm)	Bidder to specify	3mm
16	Drive details		
i	Type	Squirrel cage induction type	Yes
ii	Enclosure	Squirrel cage induction motors, TEFC, IP- 55, Class 'F' insulation, IE3 efficiency class as per IS: 12615.Flame proof, Confirming to Zone 1 (IS 5572) Gr II A & II B Vapours (IS 2148)	Yes
17	Motor rating (kW/Poles)	Bidder to specify	5HP
18	Other details		
i	Oil grade	Bidder to specify	Ip 68
ii	Oil charge (ltr)	Bidder to specify	-
iii	Oil Life (Month)	Bidder to specify	-
B	MOC		
1	Platform	Bidder to specify	MS
2	Supporting structure	Bidder to specify	MS
3	Operating panel faceplate	Bidder to specify	MS
4	Indication	1. Up 2. Down 3. Overload 4. Emergency stop	Yes
5	Button	1. Up 2. Down 3. Overload 4. Emergency stop 5. Reset the systems	Yes
6	Safety features	1. Overload alarm 2. Bottom safety bar 3. Safety check valve	Yes
7	No. of limit switches provided	Bidder to specify	2

MAHA TECHNOLOGIES PVT. LTD. PUNE

ips mehtalia	IPS-MEHTALIA PVT. LTD.		Client	THERMAX
	Consulting Engineers • Construction Management • Commissioning & Qualification		Project No.	MBD22927
	Unit B 101-109, 1st Floor, Kailash Vaibhav Ind Complex, Park Site, Vikhroli (W), Mumbai - 79		Made / App	ASP / PDP
	Document Title	Datasheet for Scissor Lift	Rev	R0
	Document No.	IPS-MBD22927-ME-1432	Date	21 Jul 23

Sr. No.	Description	IPS- Mehtalia Specification	Vendor to specify
C	**Makes of bought out items**		
1	Pump	Bidder to specify	Rexroth
2	Motor	Bharat Bijlee / Crompton	CG 5HP
3	Hydraulic valves	Polyhydron / ATOS / Equivalent make	Vtech/Polyhydron
4	Strainer	Hydroline / Equivalent	Equivalent
5	Hydraulic fittings	Hylock / Equivalent	Equivalent
6	Hose pipes	Swastik / Equivalent make	Parker
7	Hydraulic cylinders	Bidder to specify	NIHVA make
8	Control panel	Bidder to specify	NIHVA make
9	Painting & colour	Enamel Spray Painted	Yes
10	Power cable	CCI / Polycab / Asain	Polycab
11	Control cables	Finolex	Polycab
D	**Other details**		
1	Quality Assurance Plan	Required	Yes
2	GAD	Required	Yes
3	Performance trial run at site including additional instruments required for performance trial	Required	At time of Installation & Commissioning
4	Commissioining spare	Required	Extra as applicable
5	First fill of oil and lubricant	Required	Extra as applicable
6	Delivery of equipment (Weeks)	Required	8-10 Weeks
7	Erection and commissioning (Weeks)	Required	10-12 Weeks
8	Recommended O&M spares for 2 years normal operation with their unit rates and quantities (if any required) - Vendor to provide list of spares offered indicating life of each spare item	Required	Extra as applicable (After Confirmed Purchase order, spare list with unit rates will be provided)
Notes :	"*"-Vendor to specify		

NIHVA TECHNOLOGIES PVT. LTD. PUNE