NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No. SQT/20-21/2619 **Date: 19/June/2020**

Unit-1- I- 39, GIDC,
Vitthal Udyog Nagar- 388121,
Dist. Anand, Gujarat, India

Kind Attention: Mr. Hasmukh Patel
Email:
hasmukhpatel@technodesignsindia.com

Contact No: + 91 -9582383391

Project Name and Location: Techno Designs, Gujarat

Subject: Quotation for Large Size Vertical Lifting Mega Door.

Dear sir,

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.

"NIHVA" is the Authorized Business partner of "Megadoor" in India. This has reference to your above-mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer for Mega Doors

Sr. No.	Description	Clear Size (mm) (W) X (H)	Qty. (no)	Supply + Installation Price Project site Gujarat in Rs/ each
1	**Single Bay:** ASSA ABLOY Megadoor	6768 X 22000	1	5,800,000

Note:

1. Above prices are excluding all other structural members / structural support /frame work/ Side structures to close the excessive opening.

HO. Off : 187/ G-Block, 1st Floor, Thermax Chowk, Above Renault Showroom, Chinchwad, Pune 411019.

A. Requirement

Mega Door purpose

The Mega Door will be used for the Large Openings like in Heavy industries, Aircraft Hanger, Shipyard, Crane Openings and West Handling. The Mega door must provide a tight seal to reduce energy loss and provide protection against ingress of dust, sand and water. A short opening and closing time of the door will contribute to the saving of energy.

Opening dimensions

The clear opening required is

- **Mega Door: Single bay: Clear Width – 6768 mm**

Note: Please refer attached load diagram for detailed dimensions.

Space limitations

The mega door especially design for industrial environments where doors are expose to moisture, dust and very high and low temperature or door opening is large therefore a vertically lifting door is suitable for the project.

Wind load

The doors must be designed to take into account the local environmental conditions i.e. high winds, high temperatures, high levels of dust and high humidity levels.

- **Door sections designed for a wind load of 0.7 kPa with safety factor 1.5.**

Quality Standards

The mega doors must contribute to a very clean working environment. The supplier of the mega doors must have a proven track record of similar installations and provide quality certifications on request.

Other vehicle traffic

Although the mega doors are designed for demanding conditions such as mud, dirt, dust, moisture, corrosive and abrasive materials, high wind loads and a wide range of temperatures, often extreme.

Door construction

The doors must be constructed from materials, which resist corrosion so as to minimize long term maintenance costs.

HO. Off : 187/ G-Block, 1st Floor, Thermax Chowk, Above Renault Showroom, Chinchwad, Pune 411019.

B. PROPOSAL:

Supply of Mega Doors from ASSA ABLOY Entrance Systems, offering Megadoor as product brand.

We manufacture these doors in Sweden and are certified with ISO 9001.

To suit the door opening requirement, we propose vertical lifting Mega door with the following configuration.

Specification	Vertical Lifting Door
Width	6768 mm
Height	22000 mm
Depth	160 mm
Differential Pressure	0.7 kpa (14, 6 psf)
Total Height	24887 mm
Total Width	7008 mm
Guide shoe load	2,2 kn
Leaf Fabric Outside	Standard Fabric colour TBC
Leaf Fabric Inside	Standard Fabric colour TBC
Hoist	1 * SK 73F-132S/4 OD440
Open Time	105 sec
Moving Weight	1260 kg
Total Weight	2272 kg
Bottom Seal	EPDM Grey 400 mm

Option Selected

Back – up power switch
Audible and visual alarm
Beam clamps

Door 1 options selected

Motor Cover
Metal trim both sides
Shop- built door leaf
Colored clamp strip on inside
Colored clamps strip on outside

HO. Off : 187/ G-Block, 1st Floor, Thermax Chowk, Above Renault Showroom, Chinchwad, Pune 411019.

The dividing of the door sections and the sizes may vary according to the final approved design. We refer to attached load diagram (separate load diagram is sent in PDF-format).

Door speed

- It will take 73 seconds for the tallest door to open and 87 seconds for the mullion to swing up fully. This means a clear opening in approximately 160 seconds in total.

Short specification

The door leaf consists of two sheets of PVC-coated polyester fabric that can withstand a load of 9700 kg/m door width and a temperature of –35 to +70 degrees C. Intermediate horizontal aluminum sections are fitted between the inner and outer fabric with a minimum depth of 160 mm.

The door leaf is opened by wire ropes, which are attached to the bottom section; these are wound up onto a wire rope hoist. The belts or ropes are tested and certified and are connected to patented safety arresters. The TUV Approved safety arrester will prevent the door from falling in the unlikely event of rope failure.

A wind lock system is also included to prevent the door from lifting under high wind load conditions. This locking action shall act to maintain a tight floor seal and intermediate stability even under conditions of heavy wind.

The vertical guides shall be an integral part of the door, made of extruded aluminum with a suitable depth and width dependent on the size of the intermediate beams. The guides shall be designed to provide weather sealing on the inside and the outside faces. The door is available in the following standard colours: Red (RAL 3001), Blue (RAL 5005), Grey (RAL 7004), White (RAL 9016), Tan (RAL 1001), Yellow (RAL 1003), Green (RAL 6009).

Final design

Please note that the final design of the doors is subject to the final design of the building structure; the final door configuration will be agreed after the contract is awarded.

General Pre-Requisites Required at Site

Prerequisites:

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide Cable tray.
4. 400V/50Hz 3 phase power supply to be hard wired directly to Megadoor main panel.

Limit of Supply

1. Provide place to store the material under proper care.
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation.
4. Provide change & rest room for the workers.

HO. Off : 187/ G-Block, 1st Floor, Thermax Chowk, Above Renault Showroom, Chinchwad, Pune 411019.

Quote/Supply is based on

1.BOM is calculated as per standard quantity measurement.
2. In Case of any changes in the layout as per site requirements after the shipment of material, the additional quantities and the wastage will be to customer account.
3.Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include .

1. Main Electrical connection to control panel nearest to the door

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service Technicians is in client scope
2.Any civil / masonry/structural work required to support are in client scope.
3. All structure support is in client scope
4. Lifting Equipment's like Crane, Telehandler, Boom Lift

General conditions of Mega Door:

1. Continuous uninterrupted access to any single door section or as agreed separately.

2. A clear floor area of 4 meters each side of the door centerline must be available during the door leaf fitting process. The floor should be finished or if this is not possible, adequate temporary protection be made available to prevent damage to the curtain material.

3. 380/400/415V 3 phase power supply to be hard wired directly to the Megadoor Main panel. If not available at the start of installation, a temporary supply is acceptable. Voltage/Hz as appropriate to country. Any return visits to commission the doors due to permanent power not being available will be charged as appropriate. Power must be available around the clock during the entire installation.

4. A wheel loader with forks, tele handler with forks or a forklift is to be supplied (by others) for offloading the goods upon delivery. The customer/main contractor are responsible for unloading the goods, if no other agreement has been arranged with ASSA ABLOY Entrance Systems (AAES)

5. A suitable door frame should be available designed in accordance with final approval drawings issued by AAES. Tolerances/deflections of the support structure to be in accordance with the drawings.

6. Provision of 110/220/230 Volt power supply (by others) for hand tools and battery charge of equipment as lifts etc. Voltage/Hz as appropriate to each country's regulations. Power must be available around the clock during the entire installation.

7. A dry and secure area, not in direct sunlight, is to be provided for storage of the door components.

8. Access to site between 7 am to 6 pm six days per week. If this is not possible the installation schedule may require amending.

9. Any storage costs for materials due to delays outside of AAES control will be charged to the main contractor.

HO. Off : 187/ G-Block, 1st Floor, Thermax Chowk, Above Renault Showroom, Chinchwad, Pune 411019.

10. The programme assumes fair weather working between the months of March and October and does not take into account adverse weather conditions that may prevent safe and efficient working practices. We reserve the opportunity to claim extensions of time and associated costs for exceptionally adverse weather.

Inclusions

1. Our proposal includes sea freight from Sweden to Gujarat and installation of the door leaf, guide rails, weather seals, motors, control panel and electrical wiring. (Please refer exclusions)

2. A pre-installation inspection will be carried out, by our Project Manager, before our installers travel to site, so as to verify that the structural steelwork and electrical installation are as per our requirements. Our Project Manager will also check that the installation equipment and facilities (as mentioned in Exclusions) are ready.
3. Please note that the control panels, motors and electrical wiring are in full compliance with Swedish regulations and specifications, any variations due to specific requirements for India must be notified to us at the time of ordering and may be subject to an increase in the price. Any variations notified to us, after material procurement, will be charged accordingly and may lead to production delays.

Exclusions

The following items are not within our scope of works and are to be provided by others at no cost to ASSAABLOY.

1. The structural support steel for the door head, jambs, motor plates and motors shall be furnished by others. Structural steel supports shall be installed in accordance with tolerances shown on Megadoor shop drawings. The installation will not commence until these items are fully installed and tested (by steelwork contractor). The installation must be approved by the Megadoor Project Manager.

2. A load test on all points in the door opening, as specified by our design department. A load test report is to be submitted to our Project Manager after the test is completed (by Client).

3. A compliance statement, with supporting documentation, which states that the building deflections are in accordance with the criteria, as agreed between our design department and the steelwork contractor (by main contractor).

4. Any passes required for the project, are the responsibility of the Contractor and must be available, before commencement of the installation. Any delays caused by the non-availability of passes, will be charged accordingly.

5. Power supply and isolators adjacent to the control panels (by Client).

6. Mullion pits, as per our design (to be done by civil contractor).

7. Conduits and Cable trays from the control panel locations to the door distribution boxes, mullion hoist units and door hoist units to be provided. (by electrical contractor). These are to be installed prior to the commencement of door installation.

HO. Off : 187/ G-Block, 1st Floor, Thermax Chowk, Above Renault Showroom, Chinchwad, Pune 411019.

8. A 400/230 power supply (permanent or temporary) must be provided (FOC) by the main Contractor during the installation of the door for power tools and testing of the door sections during erection.

9. A safe storage / pre-assembly area for the door materials (by Client).

10. Any additional tests or certification, which are not within our scope of works but maybe required by the Consultant or Client, these will be carried out or provided, subject to the actual requirements but will be at additional cost (by Client).

Terms &Conditions:

Payment	:	**Supply + Installation = 100% against Irrevocable L/c .** • 70% Advance along with purchase Order • 30% before dispatch of material against bill of lading.
P & F Charges	:	3% on supply price
Taxes	:	Exempted (To required Government forms to get exemption at all level is the responsibility of Client)
Transport	:	included.
Service Tax	:	@15% extra on installation (if not applicable need to submit exemption form)
Validity	:	15 days from the date of offer
Delivery	:	Within 14 -16 weeks from the date of receipt of confirmed order, drawing approval & Final Irrevocable L.C.
Insurance	:	Included
Warranty	:	12 months from date of Supply
Client scope	:	1. Once our project gets completed; for any additional work to & fro, lodging & Boarding of our service technicians is in client scope. 2. Any masonry / structural work required to support are in client scope.

Please feel free to contact **Mr. Vijay Tarak (8551093333)** for any further clarification / information in this concern.

Thanks & Regards,
For NIHVA Technologies Pvt. Ltd.,

Ms Ulka Auti
Mob- 7219206333
Email- informatiom@nihva.com

HO. Off : 187/ G-Block, 1st Floor, Thermax Chowk, Above Renault Showroom, Chinchwad, Pune 411019.