NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Central Public Works
GOA CENTRAL SUB DIVISION –IV
CENTRAL PUBLIC WORKS DEPARTMENT
NEAR HOLY CROSS CHURCH ,BAMBOLIM GOA- 403202

Date : 11.02.2021
Quote NO : SQT.20.21.2757R
Kind Attn : Varad Salake
Email Id : varadsalke@gmail.com
Contact No: 8130114549

Subject : Revised Quotation for Double Skin Aluminium & Steel Curtain Rolling Shutter.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer — **Option-1 _Steel Curtain**

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Thermo Tack Double Skin Steel Curtain Rolling Shutter**	2600	3000	8	520,000	4,160,000	Inclusive	
				Total		**4,160,000**		-
				P&F Charges	3%	124,800		
				Total Without Taxes		**4,284,800**		-
				GST Extra @ 18%	18%	771,264.00		-
				Total With Taxes		**5,056,064**		-
				Transportation Charges		**Inclusive**		
				Unloading Charges @ Site		**In Client Scope**		

A-1) Commercial Offer — **Option-2 _Aluminium Curtain**

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Thermo Tack Double Skin Aluminium Curtain Rolling Shutter**	2600	3000	8	575,000	4,600,000	Inclusive	
				Total		**4,600,000**		-
				P&F Charges	3%	138,000		
				Total Without Taxes		**4,738,000**		-
				GST Extra @ 18%	18%	852,840.00		-
				Total With Taxes		**5,590,840**		-
				Transportation Charges		**Inclusive**		
				Unloading Charges @ Site		**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Double-skinned Profile Teckentrup roller shutter _ Steel Curtain

Sr .No.	Specification	Double-skinned Profile Teckentrup roller shutter
1	Description	double-skinned Teckentrup roller shutter made from PU-foamed steel profiles. outside of profiles micro-profiled, inner surface "smooth" w groove (curve). For outer rollers the actual inside is visible on the outside! Micro-profiling then inside.
2	Sizes	2600 x 3000 mm
3	Roller door curtain profile type	ThermoTeck steel filled with PU-foam
4	Roller shutter door curtain material	steel
5	Roller door surface outside	galvanised with protective fil
6	door color inside / outside	uniformly
7	roller shutter type	inside roller
8	buffer drive side min./exist.	300 mm / 300 mm
9	buffer bear. side min./exist.	175 mm / 175 mm
10	lintel height min./existing	497 mm / 497 mm
11	insertion depth	725 mm
12	building structure	concrete
13	bottom profile	ET-1 for Teckentrup ThermoTeck
14	welding shaft	octagonal tube galvanised
15	guideee rail	FS 85 (steel)
16	heat transmission value[W/m²K]	3,72
17	wind load class	wind class 2
18	lintel sealing	yes
19	brush sealing type	BH - 70
20	drive type / -edition	direct mount drive TAR 1.14 KU 400V/3Ph AWG 12 U/min; IP54; 60% ED
21	drive mounted	inside left, standing
22	console drive/bearing side	console type 1 / console type 1
23	emergency drive operation	emergency hand crank
24	control unit	CS 310 (dead man) with built-in triple button CEE-plug with wire
25	length of control cable	5.000 mm

Double-skinned Profile Teckentrup roller shutter _ Aluminium Curtain

Sr .No.	Specification	Double-skinned Profile Teckentrup roller shutter
1	Description	Double-skinned Teckentrup roller shutter from aluminium profiles
2	Sizes	2600 x 3000 mm
3	Roller door curtain profile type	4020 alu polystyrene
4	Roller shutter door curtain material	Aluminium
6	door color inside / outside	uniformly
7	roller shutter type	inside roller
8	buffer drive side min./exist.	300 mm / 300 mm
9	buffer bear. side min./exist.	175 mm / 175 mm
10	lintel height min./existing	520 mm / 520 mm
11	insertion depth	743 mm
12	building structure	concrete
13	bottom profile	4013 for Teckentrup 4020
14	welding shaft	steel tube ø 159mm primed
15	guideee rail	FS 85 (steel)
16	heat transmission value[W/m²K]	3,72
17	wind load class	wind load resistance class 2
18	lintel sealing	yes
19	brush sealing type	BH - 70
20	drive type / -edition	direct mount drive TAR 1.14 KU 400V/3Ph AWG 12 U/min; IP54; 60% ED
21	drive mounted	inside left, standing
22	console drive/bearing side	console type 1 / console type 1
23	emergency drive operation	emergency hand crank
24	control unit	CS 310 (dead man) with built-in triple button CEE-plug with wire
25	length of control cable	5.000 mm

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 10 - 12 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Transportation : 4000/- / Unit (Shutter) is consider on as per todays. Calculation at Actual varies depend on quantity and order place date.

Please feel free to Contact **Mr. Ravindra Kharat on 7410169333** For any further Clarification /Information in this Concern.

With Best Regards
Pradeep Shinde
8551096333
For NIHVA Technologies Pvt Ltd