NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

JSW Steel Coated Products Ltd.
Kalmeshwar,
Maharashtra
India

Date : 15.11.2019
Quote NO : SQT/19-20/2099R
Kind Attn : Mr. Rajesh Dhote
Email Id : dhote.rajesh@jsw.in
Contact No: 9860269737

Subject : Revised Quotation for Sectional Door, Rolling Shutter and Sliding Door. (Project - JSW Kalmeshwar ,New Shed of CCL-3.)

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2,3
C.	General Conditions	4
D.	Terms & Condtions	4

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	MS Motorized Rolling Shutter	7000	4500	1	445,000	445,000	20,000	20,000
2	MS Motorized Rolling Shutter	4000	4000	1	318,000	318,000	20,000	20,000
3	MS Motorized Rolling Shutter	4000	6000	2	407,000	814,000	20,000	40,000
4	MS Motorized Rolling Shutter	4000	4500	1	382,000	382,000	20,000	20,000
5	Grill Motorized Rolling Shutter	5000	4500	3	400,000	1,200,000	20,000	60,000
6	Sectional Door	7000	6000	4	856,000	3,424,000	20,000	80,000
7	Sectional Door	6000	5000	2	567,000	1,134,000	20,000	40,000
8	Sectional Door (Auto Open)	4000	4000	1	475,000	475,000	20,000	20,000
9	Sectional Door	4000	4000	1	369,000	369,000	20,000	20,000
10	Sliding Door	3000	3000	1	293,000	293,000	20,000	20,000
11	Sliding Door	7000	6000	4	430,000	1,720,000	20,000	80,000
			Total			**8,854,000**		**340,000**
12	P&F Charges			3%		265,620		
	Total Without Taxes					9,119,620		340,000
	GST Extra @ 18%			18%		1,641,531.60		61,200
	Total With Taxes					**10,761,152**		**401,200**
13	Transportation Charges					In Client Scope		
14	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Sectional Door

Sr .No.	Specification	Description	
1	Door type	Sectional Door -Crawford - NIHVA Assaabloy 1042P	
2	Opening Direction	Vertical Lift	
3	Opening Direction	High Lift (Only for Product No. 8)	
4	Door produced Based on which certificatio	Doors produced according to ISO 9000 or ISO 14000 certified processes	
5	Opening/Closing Speed	0.25 m/s	
6	Door Material	GI Steel with PUF inside	
7	Panel Thickness	42mm	
8	External surface of the panel	diamond grid design with a glossy finish at the section joints.	
9	Inside surface of the panel	Monolithic surface on the inside of the door	
10	Broken cold bridge	Section joints with broken cold bridges	
11	Door sealent	All door sealants made of EPDM rubber.	
12	All Panel height	All panels should be 545mm high	
13	Panel Inside insulation metrial	Insulation material to be CFC free polyuretane foam.	
14	Panel Flame Retardent standrad	Flame retardant polyurethane foam according DIN4102-class B2.	
15	Steel component Material	All steel components to be electro galvanized	
16	Hinge Material	Glass fibre reinforced Polyamide	
17	Spring Material surface finish	Powder coated	
18	Water Penetration	EN 12425	class 3
19	Air Permealibity	EN12426	class 2
20	Wind Load	EN21424	class 3
21	Thermal Transittance	EN 12428 1.10W /m2K	
22	Bottom sealing	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber	
23	Door saftey device 1	Doors equiped with spring break device	
24	Incase of Power failuer	One can operate the Door manually	
25	Operator power conumption	Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W	
26	Drive Unit & Mounting Type	Single phase 230V direct drive on shaft	
27	Emergency Operation	By Disengagement rope manual	
28	Operating Switch	Up/Down Keypad + stopbutton	
29	Environmental Green Product Declaration Certification	As per ISO 14025 and EN 15804	
30	Included Accessories	Photocell Opticall wireless edge sensor 2 Control Box & Push Button for each door 4 Wheel Roller Vision Pannel Wicket door 4 Bollards for each door Key switch Alaram & flashing Light Radar Sensor on both side(Product no.8 4000 X 4000 Size)	

MS Rolling Shutter		
Sr .No.	**Specification**	**Description**
1	GI Motorised Rolling Shutter	Motorised Rolling Shutter with GI Laths with thickness of 1 mm.
2	Mounting Location area	Inside area / Outside area
3	Mounting Surface	Side Brackets: Optional = On Concrete /Steel & Side
4	Curtain Panel	The panel made of 1.0mm thick GI
5	Curtain panel size	75mm wide
6	Curtain Profile	Curved
7	Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	Side Brackets	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	Hood Cover	Made of GI Sheet Thickness 1.2 mm GF mm with 25x25x3mm angle stiffener
12	Surface finish	PU paint or Powder coated
13	Drive Unit & Mounting Type	Electric Motor - Direct Mounting - Sprocket chain arrangement – IP54 Protection
14	Included Accessories	Refelective strips on Guide 2 Control Box & Push Button for each Shutter 4 Wheel Roller Vision Pannel Wicket door (For Product no. 2 & 4) 4 Bollards for each Shutter Key switch Alarm & flashing Light Grill (Only Product No. 5)

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 9 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Swapnil Kulat on 7219207333** For any further Clarification /Information in this Concern.

With Best Regards
Vivek
8530370333
For NIHVA Technologies Pvt Ltd