NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

HEHONG PAPER INDIA TECHNOLOGY PRIVATE LIMITED
MUNDRA, GUJARAT

Date : 27.10.2020
Quote NO : SQT.20.21.2771
Kind Attn : Eric Fang
Email Id : hhpitpl@163.com
Contact No:

Project, Location : MUNDRA, GUJARAT

Subject : Quotation for Rolling Shutter, Boom Barrier and Motorized Sliding Gates

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Motorized Rolling Shutter**	4500	5000	10	179,000	1,790,000	20,000	200,000
2	**Motorized Rolling Shutter**	6000	5000	3	223,000	669,000	20,000	60,000
3	**Motorized Rolling Shutter**	3000	3000	1	104,000	104,000	20,000	20,000
4	**Boom Barrier**	7500		3	142,000	426,000	15,000	45,000
5	**Boom Barrier**	5000		1	129,000	129,000	15,000	15,000
6	**Motorized Single Leaf Sliding Gate**	7500	1550	1	387,000	387,000	20,000	20,000
7	**Motorized Single Leaf Sliding Gate**	4925	1550	1	342,000	342,000	20,000	20,000
8	**Automatic Telescopic Sliding Gate**	14925	1550	1	796,000	796,000	20,000	20,000
	Total			**21**		**4,643,000**		**400,000**
9	P&F Charges			3%		139,290		
	Total Without Taxes					**4,782,290**		**400,000**
	GST Extra @ 18%			18%		860,812.20		72,000
	Total With Taxes					**5,643,102**		**472,000**
10	Transportation Charges					Extra at atcual		
11	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Motorized Rolling Shutter

Sr .No.	Specification	MS Motorized Rolling Shutter
1	**Description:**	Motorised Rolling Shutter with MS Laths with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete /Steel & Side
4	**Curtain Panel**	The panel made of 1.0mm thick MS.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of MS Sheet Thickness 0.9 mm GF mm with 25x25x3mm angle stiffener
12	**Surface finish**	PU paint
13	**Drive Unit & Mounting Type**	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection

Boom Barrier

Sr .No.	Description	Specifications
1	**Size**	7.5 / 5 meter
3	**Opening time**	3S
4	**Motor Power Supply**	24V
5	**Type of limit Switch**	Electronic
6	**Safety**	Photocell sensor, Flashing Light With Buzzer
7	**Operated**	Push Button Pedant

Motorized Sliding Gate

Sr .No.	Specification	Motorized Sliding Gate
1	**Door type**	Motorized Sliding Gate
2	**Opening Direction**	Horizontal - from left to right or reverse
3	**Mounting Location area**	Inside area
4	**Design Pattern**	Standard Tubular Design Pattern
5	**Outer Tube**	80 x 80 x 3.6 mm THK SQ. TUBE
6	**For Post**	80 x 80 x 3.6 mm THK SQ. TUBE
7	**Innear Tube**	32 x 32 x 2.6 mm THK SQ. TUBE
8	**Gap Between Tubes**	125mm
9	**Bottom Rail on ground**	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
10	**Bottom Rollers**	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
11	**Guide Rollers supporter during Gate movement**	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
12	**Painting**	2 Coats of EPOXY polyamide based enamel finish of approved colour
13	**El motor make**	100% Imported from Europe
14	**Emergency Operation**	Manual after turn the switch
15	**Operating Switch**	Push Button from inside
16	**Safety**	Photocells, Flashing Light

Automatic Telescopic Sliding Gate

Sr .No.	Specification	Telescopic Sliding Gate
1	**Door type**	Motorised Three Leaf Telescopic Sliding Gate
2	**Clear Opening gate dimension**	(W) 14925 mm X (H) 1550 mm
3	**Opening Direction**	Horizontal - from left to right or reverse
4	**Mounting Location area**	Inside area
5	**Design Pattern**	Standard Tubular Design Pattern
6	**Outer Frame Tube Sizes**	80 x 80 x 3.6 mm THK SQ. TUBE
7	**Internal Vertical Tube Sizes**	32 x 32 x 2.6 mm THK SQ. TUBE
8	**For Post**	80 x 80 x 3.6 mm THK SQ. TUBE
9	**Bottom Rail on ground**	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
10	**Bottom Rollers**	Heavy Duty Bottom Wheel With both side Bearings
11	**Guide Rollers supporter during Gate movement**	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
12	**Painting**	Two Coats of Primer and Two Coats of Synthetic Enamel Paint
13	**Motor**	100% Imported from Europe
14	**Operation**	By Telescopic Mechanism

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Bhavin Jain on 8551092333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
7219206333
For NIHVA Technologies Pvt Ltd