WORK ORDER

Client
Sandvik Asia Pvt. Ltd.

PO Number:	J-483468	W. O. no-	SO/20-21/034
PO Dated :	24-09-2020	W. O. Date	24.06.2020
PO Received Date:	24-09-2020	Sales Co ordinator	Smita Khare
Ref. Quotation:	SQT.19-20_2704 R	Front Sales Person	Ravindra Kharat

Dispatch Address:

Sandvik Asia Pvt Ltd (EOUIII)
Recycling centre ,
D27/1,MIDC Lote parshuram ,Tal -
Maharastra

Sr. No	Description of Goods	Technical Details	UOM	Qty.	Rate	Amount	Dwg. Approval
1	NIHVA Make Rapid Roll Up Door	**Size : (W) 3000 x (L) 4000 mm** Use : Internal Door Opening Speed : 3 m/s Closing Speed : 0.8 m/s Control Panel : 4 Push Button Operated Security Features : EN 13241-1 Standard Resistance to wind load : EN12424 upto class 2 Curtain : Fabric Transparent PVC section Guide Material : Aluminium Hood Cover : GI Motor Cover : GI Operator & Control : German Make Motor Connecting Voltage : 220V , 1Ph , N Open-Stop-Close Button : Standard Protection Category : IP 54 / IP 65 Power Consumption : 0.75 kw Motor Emergency Off Button : Standard Closing Zone Monitoring : Optical Safety edge External Route Monitoring : Photocell Emergency Opening : Crank Handle	No.	1		-	
2		**Installation for above Door**	No.	1		-	

A) Commerical Terms

1)	**Payment Terms:**	1. 50 % Advance Payment against PO 2. 40 % Immediately after delivery of material at Site 3. Balance Immediately after Installation at site
2)	**Delivery Date as per PO:**	30-10-2020
3)	**Transportation:**	Inclusive
4)	**P&F Charges:**	Inclusive
5)	**Loading:**	Nihva Scope
6)	**Unloading:**	In Client Scope
7)	**Lifting Equipments:**	In Client Scope
8)	**Warranty:**	12 months from the date of supply
9)	**Height arrangement:**	NA
10)	**Electricity Supply:**	In Client Scope
11)	**GST:**	Extra@18%
12)	**Installation Scope:**	Nihva Scope
13)	**Mode of import:**	NA
14)	**HSS:**	NA
15)	**Documentation Required:**	Standard Handover Documents

Certified that the above work order finalised in presence of:

AGM	SALES	PROJECT	PPC	DESIGN	Date & Time
A. K.	V.T.	S. P.	S.B.	P. A.	