**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

## NIHVA Sales Quotation

**Padmawati Engineering**
Plot No. G-20/1/1, MIDC
Chakan Industrial Area, Phase-3
A/P-ighoje, Tal.Khed, Dist Pune -410501

**Date : 01.10.2020**
Quote NO : SQT.20.21.2732
**Kind Attn :** Mr.Deepak Patil
Email Id : padmawati.engineering@gmail.com
Contact No: 9923092376

**Project Name & Location: PUNE**

**Subject : Quotation for Pit Mounted ELECTRO HYDRAULIC Scissor Lift**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.**

| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 3 |

**A) Commercial Offer**

| Sr No | Description | Size | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|
| | | Working Platform (in mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **Pit Mounted ELECTRO HYDRAULIC Scissor Lift** | (W) 1200 mm X (L) 2000 mm | 1 | 319,500 | 319,500 | 15,000 | 15,000 |
| | | | | | | | |
| | | | **Total** | | **319,500** | | **15,000** |
| 2 | | P&F Charges on Total Supply Value | 3% | | **9,585** | | |
| | | **Total Without Taxes** | | | **329,085** | | **15,000** |
| | | GST Extra @ 18% | 18% | | 59,235 | | 2,700 |
| | | **Total With Taxes** | | | **388,320** | | **17,700** |
| 3 | | Transportation Charges | | | **In Client Scope** | | |
| 4 | | Unloading Charges @ Site | | | **In Client Scope** | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification -**

**Pit Mounted ELECTRO HYDRAULIC Scissor Lift**



| Sr. No | Description | Specifications |
|---|---|---|
| 1 | Capacity | 1500 Kgs |
| 2 | Platform size | (W) 1200 mm X (L) 2000 mm |
| 3 | Shut ht | 450 mm |
| 4 | Max ht | 1950 mm |
| 5 | Lift ht | 1500 mm |
| 6 | Power pack | 3PH 3Phase |
| 7 | Safety Railing | on 2 side (900 mm height) |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description | Remark |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | In Client Scope |
| 2 | Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site | In Client Scope |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | In Client Scope |
| 4 | Any civil / masonry/structural work required | In Client Scope |
| 5 | All structure support required | In Client Scope |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | In Client Scope |
| 7 | Conduits, Cables required | In Client Scope |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 4 -5 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** :80% Advance along with Confirmed Purchase Order & Balance before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Amol Gaware on 7758820333.**

With Best Regards
Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd