## PO NO: - NVA – 721 Annexure – A For Terms and Conditions

| Sr. No | Item Description | Profile | | Cladding | Main Size | | Qty | | Unit Price | Total Price |
|---|---|---|---|---|---|---|---|---|---|---|
| | | Model | Colour Oprtions | Material | Length In mm | Width In mm | | Currency | Per Unit | |
| 1 | Aluminium Polycarbonate Retractable Enclouser | 6063-T5 Aluminum Commercial system Main profile 66*95(3.0-4.0mm) | 1)Coffee brown 2) Black 3) Flat Grey | 1)100% German raw material 2)LED light Included | 31950 | 5412 | 1 | USD | 28491 | $ 8,491.00 |
| 2 | Aluminium Polycarbonate Retractable Enclouser | 6063-T5 Aluminum Commercial system Main profile 66*95(3.0-4.0mm) | 1)Coffee brown 2) Black 3) Flat Grey | 1)100% German raw material 2)LED light Included | 31950 | 5412 | 1 | USD | 28491 | $28,491.00 |
| 3 | Aluminium Polycarbonate Retractable Enclouser | 6063-T5 Aluminum Commercial system Main profile 66*95(3.0-4.0mm) | 1)Coffee brown 2) Black 3) Flat Grey | 1)100% German raw material 2)LED light Included | 5812 | 29260 | 1 | USD | 28018 | $28,018.00 |
| | | Total | | | | | 3 | | | $85,000.00 |

21/08/24

21/8/24

P.T.O.

**Technical Conditions:**

1) Need to consider and supply all material require for installation except polycarbonate sheet.
2) All necessary drawings (Civil Drawing, MS structure drawing, Water drainage drawing, shop drawings, GA layout, rendering drawing, Electrical drawings, etc) should be submitted within 7 days from receipt of PO.
3) MS structural frame drawings needed to mount the retractable roof rightly.
4) All necessary spare part drawing and list with price require.
5) Polycarbonate sheet, EPDM rubber fitting arrangement and fitting process should be defined through video and installation manual should be provided for the same along with drawings mention in point no 2.
6) All working manuals (Installation manual, Assembly manual, Electrical manual) should be submitted for study and ask doubts if any to us.
7) All working manuals (Installation manual, Maintenance manual, Assembly manual, Electrical manual, daily check list of roof) should be submitted along with the dispatch.
8) EPDM rubber must be of Chinese brand "Haida" EPDM rubber seal.
9) Test Certificates for all supplied material are mandatory. (AL 6063-T5, EPDM Rubber, SS-304, Motor, Remote, LED, Bus bar, Roller, etc)
10) Powder Certificate and Powder coating test report must be submitted with stamp and seal of the supplier/Manufacturer).
11) All Hardware should be of SS-304 grade.
12) Internal quality and inspection report require with Photos and Videos.
13) Assembly and Trail of Roof video requirement is mandatory.
14) All manual should be in English language only.

**Warranty Conditions (Certificates Mandatory):**

1) AL profile 6063- T5, 30 years warranty
2) EPDM rubber Chinese Top brand "Haida" EPDM rubber seal with 10 years warranty
3) Motor, Remote, Receiver Nice make (RUN 2500) warranty 2 years.
4) Bus bar, current collector etc accessories warranty certificate with detailed specification require.

**Delivery Conditions:**

1) All material should be packing as per sea shipment norms. Plywood case+plastic belts+protective film+PE foam and should not be damaged.
2) Delivery- 30-35 days.

2/8/24

2/08/24