NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Archean Chemical Industries Pvt Ltd
"ANANDAM" D/4,Shaktinagar,Opp.Lions Club
Gandhidham - 370 201.(kutch)

Date : 18.03.2021
Quote NO : SQT.20-21.3082R
Kind Attn : Mr. Prakash Gohil
Email Id : prakash.gohil@jakhausalt.com
Contact No: 6353433393

Subject : Quotation for D-typeTripod Trunstile

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**D-Type Half Turnstile Gate: SS 304** • It has zero position of self -checking • There is alarm notice funtion when illegal access. • Avoid bump funtion • IR/mechanical dual anti-lined funtion • Reseng automatically • Standard wiring connectio • Mounting Pole • The whole system works steadily, and the noise is very low. • Unlock time: 0.2s • Pass rate: 35 person/min each from both gates • Pass Width: 550mm • Input: 100V~240V • Driving Voltage: 24v • Environment: -20~60°c • Power Consumption: 35w	3	95,000	2,85,000	20,000	60,000
2	**Face Reader with inbuilt Access Controller**	6	28,950	1,73,700		
3	**Basic Software for IN_OUT Entry**	1	10,000	10,000		
		Total		4,68,700		60,000
4	P&F Charges @ 3%	3%		14,061		
	Total without Tax			**4,68,700**		**60,000**
	GST Extra @ 18%	18%		84,366.00		10,800.00
	Total with Tax			**5,53,066.00**		**70,800.00**
5	Transportation Charges					Extra At Actual
6	Unloading Charges @ Site					In Client Scope

B) Technical Specification

D-type Half Height Turnstile

Sr .No.	Description	Specifications
1	Framework	304 SS
2	Unlock Time	0.2 Sec
3	Size (L x B x H)	1630 x 1500 x 2310 mm
4	Pass Width	650 mm
5	Pass Rate	35 persons/min
6	Operation	Single/Bi-directional
7	Rotor Type	3 arm x 120°
8	Mechanism	Electro-Mechanical
9	Power Voltage	AC 220V +/- 10% 50-60Hz
10	Mode	Fail Safe
11	Driving Voltage	24 V
12	Integration	Any Access control system

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad. Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 5 - 6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Ravindra Kharat on 7410169333** For any further Clarification /Information in this Concern.

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd