NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Grasim Industries Ltd.
SFD Nagda MP

Date : 05.04.2022
Quote NO : **MHE_21.22.0054R1**
Kind Attn : Mr. Hukum Singh Tomar
Email Id : hukum.tomar@adityabirla.com
Contact No: 8319193227

Project Name & Location: Grasim Industries Ltd. SFD Nagda MP

Subject : Quotation for Screw Conveyor

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Screw Conveyor** Total Length- 4.25mtr	**1**	**2,55,000**	**2,55,000**	**35,000**	**35,000**
		Total		**2,55,000**		**35,000**
	P&F Charges	3%		**7,650**		**35,000**
	Insurance Charges					**2,000**
	Total Without Taxes					**2,99,650**
2	GST Extra @ 18%	18%				**Extra At Actual**
3	Transportation Charges (It may vary by the time)					**Approx. 60,000**
4	Insurance Charges					**Included**
5	Unloading Charges @ Site					**In Client Scope**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Screw Conveyor

Sr. No.	Parameters	Specification
1	Material to be conveyed	Sodium Sulphate Powder (Particle less than 0.3mm)
2	Total Screw transfer Length	4250 mm
3	Moisture	Less than 0.1 %
4	MOC	SS316L
5	Screw inclination	45 degree
6	In feed Hopper size	50 Kg, Dia 16 inch, 600 mm Height
7	Transfer rate	500 kg ++ / hr
8	Screw Dia	4 Inch
9	RPM	72-90 RPM, VFD adjustable
10	Screw Pitch	100 mm
11	Motor	FLP motor , 1 hp / CG, BBL, HM, [IE2 class]
12	Gearbox	Bonfiglioli

C) General Conditions

1 Installation will start after receiving of Site Readiness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation.

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 After 1 year warranty, Non comprehensive AMC will be provided by NIHVA at an additional cost.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : Min. 8 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance 20% against readiness of material before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation subject to change in raw material price.

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Vijay Tarak on 85510 93333.**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd