NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/16-17/0458R2 **Date : 02-03-2017**

Tenneco Automotive India Pvt. Ltd
Plot No.G-6, Phase - III ,MIDC Chakan
A/P- Kuruli,Tal - Khed,Pune,
Maharashtra,India

Kind Attn : Girija Jena
Email : gjena@tenneco.com
Contact No : 9922031500

Subject : Quotation for Manipulator

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.

This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr.No	Description	Qty	Unit	Rate In INR	Net Amount INR
	Manipulator : 1. Manipulator enables the safe and efficient handling of many products up to a maximum weight of 150 kg. 2. Manipulator incorporates a pneumatic cylinder to achieve the lifting action, and is normally custom built to suit the relevant working environment 3. Low noise levels and low maintenance make manipulator the ideal solution for your material handling problems 4. Three control styles ensure maximum flexibility. Auto balance, powered lift/lower, and pre-set loaded/unloaded options allow the most suitable control style to be used for each handling application **Types** : 1. Railing roof mounted				
					
	Railing roof mounted				
A	**6 x 4m Roof Mounted Railing**				
1	Roof Mounted 6 x 4m Rail	1	No.	2,76,000	2,76,000
	Installation charges for above Railing	1	No.	25,000	25,000
	Manipulator 6 Bar : Capacity-150kg	1	No.	6,84,000	6,84,000
	Installation charges for above Manipulator	1	No.	35,000	35,000
	4 Piller Mounting Structure	1	No.	48,000	48,000
	Belt	2	Set	13,500	27,000
	Air Booster/Receiver	1	No.	1,30,000	1,30,000
2	Transportation charges for above set	1	Set	30,000	30,000
	Total (A)				**12,55,000**
B	**Gripper**				
1	**Clamper Expansion** Max. : 450mm Min. : 100mm Min Height : 350mm Max. Height : 1650mm **Rotation** : 180 Degree **Tilter** : 40 Degree	1	No.	4,75,000.00	4,75,000.00
	Total (B)				**4,75,000.00**

General Prerequisites Required at Site

1 Finished Flooring after curing (Without Water)
2 Electrical Supply on the site single phase/three phase points at different places.
3 Provide electrical cables near to the installation machinery
4 Fork lift/crane to be provided if required .
5 Scaffolding require for Installation it is in client scope.

Limit of Supply

1 Provide place to store the material to be installed .
2 Be responsible for the safe custody of all material
3 Provide place to safely store all the tools of installation
4 Provide change & rest room for the workers.

The supply included only those mentioned in the quote & does not include

1 Unloading from truck placement on site
2 Electrical connection for control panel.

Client Scope

1 Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope

2 Any civil / masonry/structural work required to support are in client scope
3 All structure support is in client scope
4 NIHVA Will provided structure drawing only if required
5 Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	Considered in above prices
3	**Freight Notes**	:	Considered in above prices
4	**Delivery**	:	8-10 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	**80% advance along with confirm Purchase Order & balance before dispatch**
6	**Insurance**	:	Considered in above prices
7	**Sales Tax**	:	Extra as applicable at the time of dispatch. Presently @13.5% VAT (supply within Maharshtra OR @2% CST against Form C (Outside Maharashtra)
8	**Service Tax**	:	Extra @ 15%
9	**Validity**	:	Validity of Offer is 15 days from the of quotation
10	**Warranty**	:	12 Months from the date of supply

Please feel free to Contact **Mr. Mayur Derle** on **7709209333** For any further Clarification /Information in this Concern.

With Best Regards

Monika Kidgaonkar
8551091333
For Nihva Technologies Pvt Ltd