Sales Quotation

Quotation No - SQT/19-20/1444 **Date : 10.04.2019**

SUROJ BUILDCON PVT. LTD.
Bungalow No. 3, Liberty Society Phase-I, North Main Road,
Koregaon Park, Pune 411 001, Maharashtra, India.

Kind Attn : Nikhil Bakane
Email ID : nbakane@suroj.in
Contact No : 020 4135 5926

Project Name And Location : A Raymond

Subject : Quotation for High Speed Doors, Fire Rated Rolling Shutter, Rolling Shutter, Fire Door,Sliding Door and Tripod Turnstile.

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Sr. No	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**ASSA ABLOY (Albany) Rapid Roll Up Door RR300+AL** **(100% Imported – made in Germany)** **(Supply + Installation)**				
Door panel:	Transparent PVC with Red (RAL 3002) reinforcement stripes.				
Barrel:	Aluminium, anodized with shafts made of galvanized steel				
Wind Reinforcement:	Door Panel wind tabs for improved wind resistance				
Vision Window	Vertical Transparent Vision panel				
Side Frames:	Aluminium profiles, anodised				
Drive Unit:	Motor IP 55, either RH or LH as an option, with control cable (standard length = height of door)				
Self-opening:	Standard - the door can be opened partially up to 1,8 m by releasing the brake manually.				
Bottom beam:	Anodized extruded aluminium.				
Control system:	MCC Vector Control - frequency converter control system for a dynamic, smooth door movement, located close to the drive unit Max. Opening Speed 2.2m/s Max. Closing Speed 0.9 m/s				
Safety features:	Safety edge, safety photocell (Transmitter/Receiver) inside side columns				
1	Size (W) 2400 mm x (H) 3000 mm	4	No	639,000	2,556,000
2	Size (W) 1800 mm x (H) 3000 mm	2	No	625,000	1,250,000
3	Size (W) 3000 mm x (H) 3000 mm	1	No	653,000	653,000
				Total	4,459,000
B	**Motorized Rolling Shutter** **Technical Specifications:** **• MS Slat : 1.0 mm Thick** **• Profile : Curved Type Profile with heavy duty Shaft** **• Guide : 2.5 mm Thick MS Guide** **• Hood Cover & Motor Cover : 0.9 mm Thick GI material** **• Indirect Drive** **• With Painting** **(Supply + Installation)**				
1	Size (W) 5000 mm x (H) 7000 mm	2	No	244,000	488,000
2	Size (W) 3000 mm x (H) 3000 mm	3	No	103,000	309,000
3	Size (W) 5000 mm x (H) 3000 mm	2	No	134,000	268,000
				Total	1,065,000
C	**ASSA ABLOY-BESAM-Automatic Sliding Door SL 500** **100% imported from Sweden** **Specifications :** 1. Main power supply 2. Operator type- Bi part operator/single slide 3. User interface- Auto Partial/Auto/one way/closed including LED status 4. Battery- Battery 12 V power fail open 5. open Operator lock- Electric lock (fail safe) 6. Glass : 10mm thick 7. Sensor for both side application				
1	**Size** : (W) 1220 mm x (H) 2800 mm Supply + Installation	1	No	190,000	190,000
D	**Tripod Turnstile:** **(Supply + Installation)**				
	• It has fault self-test and alarm prompt function, which is convenient for users to maintain and use. **• Can be connected to any control device output control signal or button or remote control, to achieve single bidirectional control pass.** **• The Tripod may be programmed for uni-direction access & bi-directional access as well.** **• Hold Open Time: On flashing a card the Tripod arm must be moved to initiate action. If there is no action initiated the arm locks itself after a 10 second hold open time.** **• Light indication: High-brightness traffic light status indication, guide the passage.** **• Anti-tailing function: The design is such that tailgating is negated. However, if there is an attempt to pass through after an operation is completed the arm locks and initiates an alarm condition if the thrust continues.** **• Fire input: Fire input connection may be terminated for initiation of fail-safe operation during emergency.** **• Input Memory function: In case of heavy traffic, the system can accept more than one card for quick processing of traffic. • Anti-reverse function: When the reversal occurs during the passage, the brake lever will automatically start the reverse thrust blocking and issue an alarm. After the external force disappears, the passage will automatically resume. • Drop Arm Function: The Tripod Arm drops automatically during emergency and when power is cut. On resumption of power/normalcy the Tripod arm is deployed in blocking position and is then ready for normal operation. • Dynamic reminder: On receiving a signal for access the arm moves about 5 degrees, and thereafter a soft touch rotates the arm to complete an access and stops.**				
1	Turnstile	1	No	155,000	155,000

E	**2 Hrs. Fire Rated Rolling Shutters** **•Shutter Slats: Zinc coated steel solid slats** **•Slat Thickness: 1.0mm thick** **•Shutter Guide: Galvanize Steel, 3mm thick** **•Operated by: Motor with one unit push button switch & manual override**				
1	Size : (W)3000 mm x (H)3000 mm **(Supply + Installation)**	1	No	275,000	275,000
	Total				**275,000**

GST Pune	**27AAECN0437H1ZM**	**Grand Total**	**6,144,000**

General Prerequisites Required at Site

1 Finished Flooring after curing (Without Water)
2 Electrical Supply on the site single phase/three phase points at different places.
3 Provide electrical cables near to the installation machinery
4 Fork lift/crane to be provided if required .
5 Scaffolding require for Installation it is in client scope.

Limit of Supply

1 Provide place to store the material to be installed .
2 Be responsible for the safe custody of all material.
3 Provide place to safely store all the tools of installation
4 Provide change & rest room for the workers.

Quote/Supply is based on

1 BOM is calculated as per standard quantity measurement
2 In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3 Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1 Unloading from truck placement on site
2 Electrical connection for control panel.

Client Scope

1 Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2 Any civil / masonry/structural work required to support are in client scope
3 All structure support is in client scope
4 NIHVA Will provided structure drawing only if required
5 Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	@ 3% of Total supply value
3	**Freight Notes**	:	Extra as applicable + Taxes
4	**Delivery**	:	11-12 weeks for High Speed Door, Sectional Door and 4 -5 weeks for Steel Door and Telescopic Gate from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% Advance along with Confirmed Purchase Order & Balance before dispatch.
6	**Insurance**	:	Extra As applicable
7	**Insurance**	:	Extra As applicable
8	**Tax**	:	GST Extra @ actual
9	**Validity**	:	Validity of Offer is 15 days from the date of quotation
10	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact **Mr. Swapnil Kulat** on **7210207333** For any further Clarification /Information in this Concern.

With Best Regards
Ulka
7219206333
For NIHVA Technologies Pvt Ltd