TECHNOLOGY NUCLEUS
1, Pranav Apartments, Guru Ganesh Society
613/1+2, Bibwewadi-Kondhwa Road, Pune 411037, MH, India.
E-mail: rahul.bhalgat@technologynucleus.com
GSTIN: 27ABEPB4431D1ZB

**Purchase Order**

| P O number: 1076DM R2 | P O Date: 05 February 2021 | Revision date: 10 March 2021 |
|---|---|---|
| Design approval:<br>11 March 2021 | Inspection:<br>31 March 2021 | Delivery:<br>Upon inspection |

| Supplier: | GST No. | Kind Attention: |
|---|---|---|
| NIHVA Technologies Pvt. Ltd.<br>187, G-Block, 1st Floor,<br>Above Renault Showroom,<br>Thermax chowk, MIDC, Chinchwad,<br>Pune – 411019<br><br>Phone: +91 85510 91333<br>Email: sales@nihva.com | 27 AAECN 0437H1 ZM | Mr. Vijay Tarak (MD)<br>Email: sales@nihva.com<br><br>Mr. Rohit Kadgave (Project Manager)<br>Mobile: 89566 14106<br>E-mail: automation@nihva.com |

**Deliverables and price (Cage welding machine):**

| Sl. No. | Description | HSN | Quantity | Rate (Rs.) | Total (Rs.) |
|---|---|---|---|---|---|
| 1 | Pivoted translating conveyor for concrete, with hopper. Scope and specifications as per Annexure A. | 84 | 01 no. | 5,53,300/- | 5,53,300/- |
| | In words: Rs. Five lakhs fifty-three thousand three hundred only. GST 18% extra, Transport extra. | | | | |

Payment terms:


a) 10% advance payment against the acceptance of this order.
b) 40% advance payment against the design approval.
c) Balance against proforma invoice before dispatch, after inspection.

Delivery:
The equipment shall be presented to us for inspection in assembled condition at your factory by 31 March 2021. The equipment shall be dispatched upon inspection for scope, specifications and performance.

The delivery date has been specified only after taking concurrence from the supplier. Timely delivery is the essence of this P O and the supplier must adhere to the specified delivery date. The possible delay because of factors beyond your control shall be communicated in advance, stating the reasons and the likely period of delay. In the event of delay in delivery, we have right to cancel the P O, with all the repercussions to the account of the supplier. In such a case no payment will be due to the supplier and the advance payments made in connection with this P O shall be returned by the supplier within 4 days of cancellation of the PO.

Prices: Prices are fixed till delivery and there is no price escalation clause.

For Technology Nucleus



Rahul Bhalgat

TECHNOLOGY NUCLEUS
1, Pranav Apartments, Guru Ganesh Society
613/1+2, Bibwewadi-Kondhwa Road, Pune 411037, MH, India.
E-mail: rahul.bhalgat@technologynucleus.com
GSTIN: 27ABEPB4431D1ZB

Annexure A to the Purchase Order 1056DM dated 28th December 2018
Scope and specifications for the Automatic Cage Welding Machine, model CWC2730-24CNC.

| Parameter | | Value / details |
|---|---|---|
| 1 | Material to be conveyed | Freshly mixed non-flowing concrete, which is a mixture of crushed sand (particle size 0 to 6 mm), 10 mm gravel, 20 mm gravel, cement and water. Photograph of concrete on a conveyor belt is enclosed with this PO. |
| 2 | Material weight | Material in the hopper: 1350 kg<br>Material on the belt: 350 kg, in the form of 450 mm wide x 50 mm thick layer on the belt.<br>~~Total 1350 + 350 kg = 1600 kg weight is born by the skid plate below the belt.~~ |
| 3 | Hopper dimensions | As per the drawing 2103 199 101 enclosed with this PO. The material (concrete) loaded into the hopper shall directly fall onto the conveyor belt, supported by ~~a skid plate~~ rollers. The hopper shall have an opening, 450 mm wide x ~~50~~ ***60 to 75*** mm high. When the conveyor runs, the material (concrete) shall come out of this opening to form a 450 mm wide x ~~50~~ ***60 to 75 mm*** high layer on the belt. |
| 4 | Belt | 600 mm wide belt, running on a ~~skid plate~~ rollers at a speed of 20 m/min (or less through VFD). Shall have appropriate material, construction and thickness for the application. ~~The side plates, 455 mm apart, shall run on both sides of 450 mm wide material (concrete) layer on the belt. Flexible lips to be provided below the side plates to prevent material / slurry from escaping~~. ***The belt shall be running on the troughing rollers.*** |
| 5 | Conveyor length | 5900 mm drum center to drum center. |
| 6 | Drive and drum | Drum diameter 240 mm, driven by ~~5 HP or 7.5 HP~~ 4 HP geared motor at around 25 rpm. ~~Motor and gearbox rating to be confirmed at design stage. Motor make: ABB / Siemens / Bharat Bijlee. Gearbox: Bonfigloli / Nord / SEW / Elecon.~~ ***Geared motor make: Transtech, Bangalore.*** |
| 7 | Conveyor translation and pivoting motions | The conveyor shall move to-and-fro by 3275 mm on the base frame. This motion shall be motorized, on wheels inside the guides. Translation speed: 6 – 12 m/min. The end positions of the 3275 mm stroke shall be as shown in the drawing 2103 199 101 enclosed with this PO. ***The actual end positions shall be set as specified in our comments (dated 02nd March 2021) on your draft design. Geared motor for this shall be 1.5 kW, 12.7 rpm, 1096 Nm. Geared motor make: Transtech, Bangalore.***<br>The base frame itself shall move by + /- 20° around the pivot point shown in the drawing 2103 199 101 enclosed with this PO. This motion shall be executed manually. The base frame shall have 3 rollers (running on spherical plain bearings) on a |

TECHNOLOGY NUCLEUS
1, Pranav Apartments, Guru Ganesh Society
613/1+2, Bibwewadi-Kondhwa Road, Pune 411037, MH, India.
E-mail: rahul.bhalgat@technologynucleus.com
GSTIN: 27ABEPB4431D1ZB

| Parameter | | Value / details |
|---|---|---|
| | | PCD at a height of around 1 m. These rollers shall run around a circular guide-plate anchored on the floor through a pillar.<br>The positions of the legs of the base frame also shall be as per the drawing 2103 199 101 enclosed with this PO. |
| 8 | Material of construction | Mild steel |
| 9 | Electrical supply and panel details | 3-phase 400V, 50 Hz electrical supply will be given at single point. The supplier to confirm the incoming cable size at the design approval stage.<br>Panel shall be dust proof. There shall be adequate inside volume for air circulation for the VFD.<br>Contactor / MCB / Overload relay: Telemechanique / Siemens<br>Relay: Omron, coil voltage 24V DC<br>Limit switch: BCH<br>Push buttons: Telemechanique with transparent rubber caps.<br>Wires: Polycab / Finolex, with numbered ferrules.<br>VFD: Yaskawa, operating on 0-10V input via a pot on the panel. VFD bypass switch (with star delta circuit for direct operation) shall be given on the panel.<br>Operating elements like push buttons, selector switches, pot etc. shall not be selected merely on electrical rating, these shall be big and sturdy physically. |
| 10 | Documents to be supplied | Electrical circuit diagram with components list and panel layout.<br>Operation and maintenance manuals of all bought-outs like gearbox, VFD etc. |
| 11 | Warrantee | 1 year from the date of commissioning or 15 months from the date of dispatch, whichever is earlier. |
| 12 | Color | Epoxy primer + PU paint in 2 shades. The shades to be confirmed at the design approval stage. |

- - - - - - - - - - - - - - - - - - - - - - - - - - - - End of the document - - - - - - - - - - - - - - - - - - - - - - - - - - - -