NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Xrbia
Pune

Date : 5.12.2020
Quote NO : SQT.20.21.2866
Kind Attn : Lopamudra Priyadarshinee
Email Id : lopamudra.p@xrbia.com
Contact No: 7391051880

Project Name & Location:

Subject : Quotation for Motorized Rolling Shutter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	MS Motorized Rolling Shutter	8460	2930	1	198,000	198,000	20,000	20,000
2	MS Motorized Rolling Shutter	5000	2930	1	133,000	133,000	20,000	20,000
3	MS Motorized Rolling Shutter	5710	2930	1	157,000	157,000	20,000	20,000
4	MS Motorized Rolling Shutter	7990	2930	1	191,000	191,000	20,000	20,000
5	MS Motorized Rolling Shutter	7600	2930	1	185,000	185,000	20,000	20,000
6	MS Motorized Rolling Shutter	5430	2930	1	139,000	139,000	20,000	20,000
7	MS Motorized Rolling Shutter	5100	2930	1	134,000	134,000	20,000	20,000
8	MS Motorized Rolling Shutter	7920	2930	1	190,000	190,000	20,000	20,000
9	GI Motorized Rolling Shutter	8460	2930	1	215,000	215,000	20,000	20,000
10	GI Motorized Rolling Shutter	5000	2930	1	144,000	144,000	20,000	20,000
11	GI Motorized Rolling Shutter	5710	2930	1	170,000	170,000	20,000	20,000
12	GI Motorized Rolling Shutter	7990	2930	1	207,000	207,000	20,000	20,000
13	GI Motorized Rolling Shutter	7600	2930	1	201,000	201,000	20,000	20,000
14	GI Motorized Rolling Shutter	5430	2930	1	151,000	151,000	20,000	20,000
15	GI Motorized Rolling Shutter	5100	2930	1	146,000	146,000	20,000	20,000
16	GI Motorized Rolling Shutter	7920	2930	1	206,000	206,000	20,000	20,000
				Total		**2,767,000**		**320,000**
17	P&F Charges			3%		**83,010**		
	Total Without Taxes					**2,850,010**		**320,000**
	GST Extra @ 18%			18%		513,002		57,600
	Total With Taxes					**3,363,012**		**377,600**
18	Transportation Charges					**Client Scope**		
19	Unloading Charges @ Site					**Client Scope**		

NIHVA TECHNOLOGIES PVT. LTD.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Motorized Rolling Shutter

Sr .No.	Specification	MS Motorized Rolling Shutter
1	**Description:**	Motorised Rolling Shutter with MS Slats with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete /Steel & Side
4	**Curtain Panel**	The panel made of 1.0mm thick MS.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." T" Shaped profile 65 mm -150 mm x 3 mm thick.
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm GF mm
12	**Surface finish**	Powder coated
13	**Drive Unit & Mounting Type**	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection
14	**Control Type**	Dead man / Pulse Control

Motorized Rolling Shutter

Sr .No.	Specification	GI Motorized Rolling Shutter
1	**Description:**	Motorised Rolling Shutter with GI Slats with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete /Steel & Side
4	**Curtain Panel**	The panel made of 1.0mm thick GI.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." T" Shaped profile 65 mm -150 mm x 3 mm thick.
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm GF mm
12	**Surface finish**	Powder coated
13	**Drive Unit & Mounting Type**	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection
14	**Control Type**	Dead man / Pulse Control

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 4-5 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% along with confirmed purchase order & Balance before dispatch

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Amol Gaware on 7758820333**

With Best Regards
Shailesh Bhoir
7219206333
For NIHVA Technologies Pvt Ltd