NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Pyome Infra Solutions
08, 1st Floor, Sai Prabhu Building, Near Mantri Mall,
Seshadripuram, Bengaluru - 560 020

Project, Location : Bosch Power Tools - Oragadam

Date : 10.03.2021
Quote NO : SQT.20.21.3092
Kind Attn : Dileep SK
Email Id : dileep@pyome.com
Contact No: 9538893335

Subject : Quotation for Vertical Fold-up Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Vertical Fold Up Door**	3600	5000	1	314,000	314,000	20,000	20,000
	Total			**1**		**314,000**		**20,000**
2	P&F Charges			3%		9,420		
	Total Without Taxes					323,420		20,000
	GST Extra @ 18%			18%		58,215.60		3,600
	Total With Taxes					**381,636**		**23,600**
3	Transportation Charges					Extra at atcual		
4	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

HIGH SPEED FOLD UP DOOR



Sr. No.	Description	Specification
1	PVC CURTAIN	B6000 (900 gr) DIN EN ISO 2286-2 1.ST CLASS EUROPEAN
2	MECHANISM	ISO 9001 : 2000 – ISO 14001
3	CARRIER SYSTEM	GALVANIED STEEL /STAINLESS STEEL
4	AUTOMATION	MR220 Control Unit
5	OPENING-CLOSING SPEED	0.7 MT/SN
6	WIND RESISTANCE	CLASS 4 (IT DEPENDS OM THE SIZE)
7	VOLTAGE	400 VAC 50 HZ
8	REMOTE	INDUSTRIAL TYPE BUTTON CONTROL
9	SAFETY	PHOTOCELL
10	PVC COLOUR	WHITE/BLUE/GREEN / ORANGE / RED / GREY / YELLOW
11	WINDOW	IF YOU NEED

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Ravindra Kharat on 7410169333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd