NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/19-20/1669R1 **Date:- 30.05.2019**

ATS Conveyors India Pvt. Ltd.
Plot No. E3 /3/A,
MIDC Chakan, Phase 3 ,
Kurli Khed ,
Pune- 410501 , India

Kind Attn : Mr.Devdatta Danve
Email ID : devdattadanve@atsconveyors.com
Contact No : 77966 59511

Project Name And Location :ATS Conveyors India Pvt. Ltd, Pune .

Subject : Quotation for Nihva Make High Speed Door

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication. please find below our best offer.

Commercial Offer

Sr. No	Description	Qty	Unit	Rate In INR	Net Amount INR
A	NIHVA Make High Speed Door (Suplly + Installation)				
	Construction:High-Speed Roller Door with PVC curtain according to the following RAL colours: blue (RAL 5002) or red (RAL 3002).				
	Side frames: Side frames galvanized				
	Drive Unit: Motor IP 55, either RH or LH as an option, with control cable				
	Control system : Standard Control IP 55 for opening / closing speed approx. 0.8 m/s. Control box with Up-Stop-Down button.				
	Power supply: 3/(N)/PE/230/400/415 V, 50 Hz.				
	Safety features:Safety edge, safety photocell Transmitter / Receiver inside side frames, emergency crank and				
1	**Size: (W) 2000 mm X (H) 2000 mm**	2	No	175,000.00	350,000.00
	Total				**350,000.00**

GST Pune	27AAECN0437H1ZM

TOTAL BASIC AMOUNT	**350,000.00**

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed
2. Be responsible for the safe custody of all material
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading & boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	@ 3 % of total supply value
3	**Freight Notes**	:	Extra As applicable
4	**Delivery**	:	8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval
5	**Payment**	:	80% advance along with confirm purchase order and balance before dispatch
6	**Insurance**	:	Extra As applicable
7	**Tax**	:	GST @ 18%
8	**Validity**	:	Validity of Offer is 15 days from the date of quotation
9	**Warranty**	:	12 months from the date of supply

Please feel free to Contact Mr. Arjun Patil on 8551096333 for any further Clarification /Information in this Concern.

With Best Regards

Ulka Auti

7219206333

For Nihva Technologies Pvt Ltd