Chakan 38 Acre

ROHAN CITYSCAPE PVT LTD
Building B100
Rolling shutter Motorization

Quote No. **SQT19_20.2393**
Date **03.02.2020**

BOQ Abstract

Sr. No.	BOQ ID	BOQ Name	BOQ Description	Note	Unit	Rate	Quantity	Amount	Remark
1									
1.1			**Motorization of Gear operating Rolling shutter .**						
1.1.1			Motorization of Existing gear operated rolling shutter-Supply and Installation of Jielong motor with shaft , Single phase , all modifications to be carried out properly for motorization , all fitting modifcation for motorization to be covered ,all necessary fitting,setting , greasing along with all labor charges and with cleaning and enamel paint one coat (RAL-7001)etc. complete. (I.S. 6248 - 1979) etc. Vendor to make own arrangements for power,store & security etc as required at site .						
			Size 2451 (W) x 3033 (H) mm		Nos	52000	6	3,12,000.00	
			Total Amount in Rs.					**3,12,000.00**	