2-6.9 Warehouse

Refer Tender concept drawing no. RA1202-P4-3201

The warehouse for the MCMV facility is to be located inside the existing Steel Preparation Shop and this existing workshop shall be refurbished to accommodate warehouse area.

Any damaged areas of the existing flooring shall be repaired to suit stacking requirement of warehouse.

The warehouse shall be segregated from the other parts of the Steel Preparation Shop by a new concrete block wall up to 3m level with fibre cement board partition wall construction above this up to 7m level.

The warehouse shall include a mezzanine floor. Since as-built drawings of the existing columns and foundation are not available, it is proposed that the supporting columns for the mezzanine floor shall be independent of the existing structure with new pad foundations.

The existing workshop floor shall be provided with a new Hardcrete floor with 6kg/sqm monolithic floor hardener. Proper access to mezzanine floor shall be provided by steel staircase. The warehouse shall also have small office block.

The existing sliding door of the steel preparation workshop shall remain as the access door for warehouse. Refurbishment of the external cladding of existing steel preparation building shall be carried out under another Contract.

The warehouse shall be provided with a 2 ton monorail for storage handling. Contractor shall procure and install all racking systems as per Employer's Requirement from reputed manufacturers such as Godrej or equivalent.

2-6.10 Movable Shelters

Refer Tender concept drawing no. RA1202-P4-3701

The purpose of the moveable shelters is to provide covers over GRP ships when they are parked outside the GRP workshop. In order for the ships to be transferred sideways on the transfer rails, it is necessary for the shelters to be moved out of the way.

The moveable steel shelters are of three slightly different sizes so they can nest inside each other. The shelters move on rails.

The moveable shelters shall have electrical power sockets, lighting and compressed air outlets mounted on the inside walls of the shelters. The shelters will be provided with electric motors to drive the wheels. The wheels shall be equipped with fail safe brakes to prevent the shelters moving due to wind or other forces.

Any fixings to the concrete deck shall be proposed to the Engineer for consideration. No permanent obstruction above concrete surface level will be permitted and all works involved in retrofitting any fixings to the existing deck shall be solely the responsibility of the Contractor.

A method of connecting power to the shelters shall be proposed in which there shall be no danger of the power cable being damaged by vehicles or other equipment in the vicinity.

Similarly, a method of connecting a compressed line to the shelters shall be proposed in which there is no danger of the hose being cable being damaged by vehicles or other equipment in the vicinity.

2-6.11 De-perming Facility

The De-perming facility shall mainly be utilised to Demagnetize hand tools. The 6m x 7m wide structure shall have height of 4m.

The material used for entire building construction shall possess nonmagnetic characteristics.

Preferable material for construction shall be as follows

Load bearing CC block walls

Aluminium truss made of heavy duty aluminium box sections covered with Polycarbonate roof sheets anchoring of truss shall be made with aluminium or SS anchors. The roof shall withstand wind load described in clause 2-9.5

The building shall have aluminium access doors and windows with non-steel anchorages such as Stainless steel of Aluminium.

2-6.12 Office Buildings

There shall be two office strips along MCMV hall mainly East side service strip and West side service strip as shown in Tender concept drawing RA1202-P4- 3131

West side building shall be of 4 (ground + 3) storeyed and shall have clear width of Maximum 7m. Floor height should be 5m for ground floor and minimum 3.5m for rest of the floor above. Ground floor is mainly caters to ancillary workshops and labs etc. first floor shall have provision for workers facility such as locker room (including lockers and benches as per employer's requirement) , change rooms toilets etc. All above floors shall cater office areas.

East Side building shall be of 3 (ground + 2) storeyed and shall have clear width of maximum 4.6m. East side building shall mainly be used for Office facilities however shall also cater space for service rooms such as AHU's, server rooms, panel rooms etc.

Terraces for both strip shall provide space for overhead water tanks, booster pumps etc. both terraces shall have access for maintenance. Terraces shall have waterproofing treatment as described in Vol 3 part3 of employer's requirement.

The office buildings shall be provided with the following services

- Fresh water
- Foul water drainage
- HVAC
- Electrical power & Lighting