# Sales Quotation

**Quotation No - SQT/19-20/1706** **Date : 13.06.2019**

**FABLAB Engineering India Pvt Ltd.**
Unit No 303, Bhoomi Velocity, Road No 23.
Waghale Estate
Thane, Mumbai 400604

**Kind Attn** : **Mr. Sachin Kumar**
**Email** : enquiry@fablabindia.com
**Contact No** : 8424049181

**Subject: Quotation for High Speed Door HS9020G & RR300+ Al**

Dear Sir,
Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

**Commercial Offer**

| Sr. No. | Description | Qty | Unit | Rate In INR | Net Amount INR |
|---|---|---|---|---|---|
| | **Option 1 : HS9020G _Self Repairable** | | | | |
| **1** | **ASSA ABLOY Make Rapid Roll Up Door HS9020G**<br>**(Supply + Installation + Interlocking between two doors)** | | | | |
| | • The HS9020G high speed door is designed for interior applications. | | | | |
| | • Gravity drive system | | | | |
| | • Unique side column technology provides excellent seal on all 4 sides thereby reducing heat loss. | | | | |
| | • The speed of opening is up to up to 1,2 m/s depending on size of door. | | | | |
| | • The speed of closing is 0,5 m/s | | | | |
| | • The door design withstands overpressure or underpressure in specific areas | | | | |
| | • Photocells in side columns. | | | | |
| | • Wind load resistance: (EN 12424) Class 1 (300 Pa (N/m²)). Maximum wind load while closing 50 Pa (N/m²) | | | | |
| | • Water penetration (EN 12425) Class 2 (50 Pa (N/m²)) 20 minutes water spray | | | | |
| | • Air permeability (EN 12426) Class 1 (24 m³/m²/h at 50 Pa) | | | | |
| | • Thermal transmittance (EN 12428) 6,02 W/(m²K) | | | | |
| | • Temperature working range: 5 °C to +40 °C | | | | |
| | • Door curtain 900 g/m² colored PVC, material thickness: 0,8 mm | | | | |
| | • Flexible door curtain without ridged parts. | | | | |
| | • Flexible soft bottom edge including wireless edge activator. | | | | |
| | • Break-away and self-repair function. | | | | |
| | • The door curtain is available in 8 standard colors. | | | | |
| | • Various window - 400 mm height single row. | | | | |
| | • The motor with frequency converter guarantees smooth and reliable operation. | | | | |
| | • Soft start/stop significantly prolongs motor lifespan. | | | | |
| | • Operator 220V - 240V 1-phase 0,75 kW 16A | | | | |
| | • Operator protection: IP65 | | | | |
| | • Control unit with display, impulse Up and Down buttons, an emergency stop mushroom button and a mechanical main switch. | | | | |
| | • Control unit protection: IP54 | | | | |
| | • Lifetime expectations: 1.000.000 cycles | | | | |
| 1 | **Size:(W) 2000 mm x (H) 2100 mm** | 36 | No | 463,000 | 16,668,000 |
| | | | | | |
| | **Option 2 : RR300+ Al _ With Rigid Bottom Edge** | | | | |
| **1** | **ASSA ABLOY Make Rapid Roll Up Door RR300+ Al**<br>**(Supply + Installation + Interlocking between two doors)** | | | | |
| **Door panel:** | Transparent PVC with Blue (RAL 5002) reinforcement stripes. | | | | |
| **Barrel:** | Aluminium, anodized with shafts made of galvanized steel | | | | |
| **Wind Reinforcement:** | Door Panel wind tabs for improved wind resistance | | | | |
| **Side Frames:** | Aluminium profiles, anodised | | | | |
| **Drive Unit:** | Motor IP 55, either RH or LH as an option, with control cable (standard length = height of door) | | | | |
| **Self-opening:** | Standard - the door can be opened partially up to 1,8 m by releasing the brake manually. | | | | |
| **Bottom beam:** | Anodized extruded aluminium. | | | | |
| **Control system:** | MCC Vector Control - frequency converter control system for a dynamic, smooth door movement, located close to the drive unit Max. Opening Speed 2.2m/s Max. Closing Speed 0.9 m/s | | | | |
| **Safety features:** | Safety edge, safety photocell (Transmitter/Receiver) inside side columns | | | | |
| 1 | **Size:(W) 2000 mm x (H) 2100 mm** | 36 | No | 589,000 | 21,204,000 |



| GST Pune : | 27AAECN0437H1ZM |
|---|---|

**General Prerequisites Required at Site**

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

**Limit of Supply**

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

**Quote/Supply is based on**

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

**The supply included only those mentioned in the quote & does not include**

1. Unloading from truck placement on site
2. Electrical connection for control panel.

**Client Scope**

1. Once our project gets complete for any additional work to & fro loading & boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

**Terms and Conditions :**

| | | | |
|---|---|---|---|
| 1 | **Price** | : | Ex Works Pune |
| 2 | **P & F Charges** | : | @3 % of total supply value |
| 3 | **Freignt Charges** | : | Extra As applicable |
| 4 | **Delivery** | : | 10-12 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval |
| 5 | **Payment** | : | 80% Advance along with Confirmed Purchase Order & Balance before dispatch |
| 6 | **Insurance** | : | Extra As applicable |
| 7 | **Validity** | : | Validity of Offer is 15 days from the date of quotation |
| 8 | **Warranty** | : | 12 months from the date of supply |

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd