NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Sahyadri Farmers Producer Co.Ltd.
Sr. No. 1102/8, zbehind Police Head Quarter,
A/P adgaon, Nashik 422003

Date : 08.02.2021
Quote NO : **SQT.20-21.2444**
Kind Attn : Mr. Janardan Shelke
Email Id : janardan.shelke@sahyadrifarms.com
Contact No: 8411961929

Project Name & Location: Salt Chain Conveyor, Nashik

Subject : Quotation for Salt Chain Conveyor System

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	1
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Slat Chain Conveyor System for 5Mtr	1	2,07,000	**2,07,000**	**15,000**	**15,000**
	Total			**2,07,000**		**15,000**
2	P&F Charges	3%		**6,210**		
Total Without Taxes				**2,13,210**		**15,000**
GST Extra @ 18%		18%		**38,378**		**2,700**
Total Without Taxes				**2,51,588**		**17,700**
3	Transportation Charges					**Extra at Actual**
4	Unloading Charges @ Site					**Extra at Actual**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Slat Chain Conveyor System

Parameters	Specification
Dimensions	5000 x 130 x 800 mm LBH
Conveyor Frame	SS304 Sheet 1.6 mm Thick & Tubular Legs
Return Idler	Ø 50 mm
Slat Chain	Width 114 mm, SS
Bear Make	NTN or Reliable Make
Drive Unit	Sprocket and Idler
Side Guide	Both Side 50 mm, Adjustable
Geared Motor	1 HPBonvario/ Bonfliglioly Make
Conveyors Speed	20 mtr/Min, Fixed Speed
Power Supply	440VAC, 50 Hz
Adjustable slde Guide	50 mm Both Side
Adjuster Pad	M16 x 100 mm

C) General Conditions

1. Installation will start after receiving of Site Readyness Photographs or written Email communication.
2. We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation
3. For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.
4. If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 5 - 6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 50% Advance along with Confirmed Purchase Order & Balance 50 % against readyness of material before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation.

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Rohit on 7410175333.**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd