NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No -SQT/19-20/1887R **Date 03.08.2019**

Pragati Engineering
Pune

Kind Attn : Mr. Laxman Kale
Email ID : pragati_engineering@yahoo.co.in
Contact No : 9922008250

Project Name And Location : Dies & Moulds (Bhosari) Project .

Subject : Quotation for Motorized Rolling Shutter and Sliding Gate.

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Sr. No	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**Motorized Rolling Shutter** **Technical Specifications:** • **MS Slat : 1.0 mm Thick** • **Profile : Curved Type Profile with heavy duty Shaft** • **Guide : 2.5 mm Thick MS Guide** • **Hood Cover & Motor Cover : 0.9 mm Thick GI material** • **Indirect Drive** • **With Painting** **(Supply + Installation)**				
1	Size (W) 6000 mm x (H) 8000 mm	1	Nos.	350,000	350,000
				Total	**350,000**
B	**Single Leaf Motorised Sliding Gate** • **Only Automation** • **Motor** • **Photocell** • **Rack & Pinion** • **Control Panel** • **Electrical wire & accesories** **(Supply + Installation)**				
1	**Size : (W) 6500 mm x (H) 2500 mm**	1	No	338,000	338,000
				Total	**338,000**

GST Pune	**27AAECN0437H1ZM**	**Grand Total**	**688,000**

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	@ 3% of Total supply value
3	**Freight Notes**	:	Extra as applicable + Taxes
4	**Delivery**	:	5-6 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval
5	**Payment**	:	80% Advance along with Confirmed Purchase Order & Balance before dispatch.
6	**Insurance**	:	Extra As applicable
7	**Insurance**	:	Extra As applicable
8	**Tax**	:	GST@18% Extra
9	**Validity**	:	Validity of Offer is 15 days from the date of quotation
10	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact **Mr. Swapnil Kulat** on **7219207333** For any further Clarification /Information in this Concern.

With Best Regards

Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd