Sales Quotation

Quotation No - SQT/19-20/1846 **Date : 23-07-2019**

John Deere India Pvt Ltd.
Pune, Maharashtra 411013.

Kind Attn: Mr.Narayan Pawashe.
Email: PawasheNarayan@JohnDeere.com
Contact No :

Project Name And Location :

Subject : Quotation for Sectional Door and Double wall Rolling Shutter.

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr. No	Description	Qty	Unit	Unit Rate In INR	Total In INR
A	**ASSA ABLOY - Sectional door (100% Imported products from Europe) OH 1042P** **• Sectional door with Standard Lift,** **• Vision Windows,** **• motor & control Panel,** **• bottom safety edge and with all safety features** **(Supply + Installation)**				
1	Size (W) 4500 mm x (H) 3000 mm	1	No	289,400	289,400
Total					289,400
B	**Double Wall Motorized Rolling Shutter** **Technical Specifications:** **• Indirect Drive** **• PCGI Slat : 20 mm Thick** **• Profile : Curved Type Profile with heavy duty Shaft** **• Guide : 165 mm Thick AL Guide** **• Hood Cover & Motor Cover : GI Powder Coated** **(Supply + Installation)**				
1	Size (W) 4500 mm x (H) 3000 mm	1	No	204,000	204,000
Total					204,000

GST Pune	27AAECN0437H1ZM

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	@3% of Total Supply Value
3	**Freight Notes**	:	Extra as applicable
4	**Delivery**	:	13-15 weeks for Sectional Door and 5-6 weeks for Rolling shutter from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% Advance along with Confirmed Purchase Order & Balance before dispatch.
6	**Insurance**	:	Extra As applicable
7	**Taxes**	:	GST Extra @ 18%
8	**Validity**	:	Validity of Offer is 15 days from the date of quotation
9	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil** on **8551096333** For any further Clarification /Information in this Concern.

With Best Regards

Ulka Auti.

7219206333

For NIHVA Technologies Pvt Ltd