NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Ashok Construction
B-601, Sukhwani Glory
Dapodi, Pune- 411012

Date : 29.03.2021
Quote NO : SQT.20.21.3126
Kind Attn : Ashok Pilgonde
Email Id : ashokpilgonde@gmail.com
Contact No: 9552567922

Project, Location : Pimpalgaon Baswant Taluka, Niphad, Nashik

Subject : Quotation for Rolling Shutters ,Sliding Gate and Dock Shelter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Rectratable Dock Shelter**	3500	3500	1	80,000	80,000	10,000	10,000
2	**Gear Operated Rolling Shutter**	2400	3000	1	55,000	55,000	15,000	15,000
3	**Double wall PUF Insulated Rolling Shutter**	2400	3000	1	130,000	130,000	20,000	20,000
4	**Automatic Sliding Gate**	9000	1800	1	280,000	280,000	20,000	20,000
5	**Automatic Sliding Gate**	6000	1800	1	250,000	250,000	20,000	20,000
	Total			**5**		**795,000**		**85,000**
6	P&F Charges			3%		23,850		
	Total Without Taxes					818,850		85,000
	GST Extra @ 18%			18%		147,393.00		15,300
	Total With Taxes					**966,243**		**100,300**
7	Transportation Charges					**Extra at atcual**		
8	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Rectratable Dock Shelter



Sr. No	Description	Specification
1	Size	(W) 3500 mm x (H) 3500 mm
2	Top Curtain	1000 mm
3	Side Curtain	600 mm
5	Curtain colour	Black
6	Parking Guides	White, Yellow
7	Wall Fixings	Concrete, Sandwich light Concrete, Load house cavity, insulated panel
8	Top & Side Curtaiins	Double Layer High Quality Polyester
9	Thickness	3.0 mm
10	Weight	Approx 3400 g/m2

Gear Operated Rolling Shutter

Sr .No.	Specification	GI Gear Operated Rolling Shutter
1	**Description:**	Gear Operated Rolling Shutter with GI Laths with thickness of 1.2 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete /Steel & Side
4	**Curtain Panel**	The panel made of 1.2 mm thick.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -As per the opening width dimension
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm GF mm with 25x25x3mm angle stiffener
12	**Surface finish**	PU paint or Powder coated
13	**Drive Unit & Mounting Type**	Gear Assembly

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Double Wall PUF insulated Rolling Shutter



Sr No	Technical Specification for Double Wall Rolling Shutter
1	Thermal Insulation : Shutter infill of 20 mm PU rigid foam ensuring excellent thermal insulation
2	Side guide Protection : Black plastic strips on the edge of the side guides protect against abrasion and ensure longevity of shutters
3	Closing edge Safety device (only for Motorized) : Sensor controlled safety devices to monitor the bottom edge of the door. Instant stoppage and reversing on encountering any obstruction while closing .
4	• Fixing Material : Screw and Acncor Fastrener, GI Box Guide
5	• Sealing : Rubber seals are provided to reduce friction and sound, thereby ensuring a smooth door travel
6	• Door Curtain : GI PKP
7	• Support Brackets : MS
8	• Space Requirement (in mm) : Head room (S) = 500mm, 350 Motor INS. Hood Cover Bearing 150mm.
9	• Minimum requirement for Building Structure : Concrete = 140 mm (Min strength M10) , Steel = 5 mm, Brick work = 240 mm (Min strength 100 kg/cm2
10	• Side Guides : GI Guide with Rubber Brush
11	• Bottom Profile : MS with EPDM Gas Kit
12	• Seals : Bottom seal made of EPDM profile
13	Operator : Shaft operator, Ready to fit shaft operator, Power Input - 1 phase current 0.25 kW, Protection category IP65 (jet water protected)
14	Control : Integrated microprocessor control along with operator, Adjustable force limit and connection cable with CEE male plug in protection category IP 44, Push button on both side.
15	Standard accessories : With Crank Handle
16	Push Button : For Automatic Door

Automatic Sliding Gate

Sr .No.	Specification	Motorized Single Leaf Sliding Gate
1	Door type	Motorized Sliding Gate
2	Opening Direction	Horizontal - from left to right or reverse
3	Mounting Location area	Inside area
4	Design Pattern	Standard Tubular Design Pattern
5	Outer Tube	72 x 72 x 3.2mm MS SQ. TUBE
6	For Post	72 x 72 x 3.2mm MS SQ. TUBE
7	Innear Tube	38x38x3.20mm/40x40x3.2 MS SQ. TUBE
8	Gap Between Tubes	125mm
9	Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
10	Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
11	Guide Rollers supporter during Gate movement	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
12	Painting	2 Coats of EPOXY polyamide based enamel finish of approved colour
13	El motor make	BFT – Italy (100% imported)
14	Emergency Operation	Manual after turn the switch
15	Operating Switch	Push Button from inside
16	Safety	Photocells, Flashing Light

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 10 - 12 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Ravindra Kharat on 7410169333** For any further Clarification /Information in this Concern.

With Best Regards
Pradeep Shinde
8551096333
For NIHVA Technologies Pvt Ltd