Citadel Building System Pvt. Ltd.
C-130, Antop Hill Warehousing Co. Ltd,
V.I.T. College Rd, Wadala (E),
Mumbai – 37.
Ph: 022-20840147

Ref: - CBSPL/QTN/25-26/ 576

Date: 25/03/2025

To,
Mr. Vijay M Tarak
NIHVA Technologies Pvt Ltd
Pune
Email: - vijay.tarak@nihva.com
Contact no: 85510 93333

Subject: - Quotation for supply and Installation of Fabric Retractable Tent for your Pune project.

	DESCRIPTION	Sqft	Rate	Amount
1)	**Retractable Fabric Tent: -** Supply and Installation of Retractable Electric Tent The Retractable Electric Tent constitutes of an Accordian type of frame made out of GI pipes of different sizes. The system consists of columns, beams, cross beams, telescopic roof frame and diagonal frames. In addition, there will be a I beam on which the rail will be mounted on which the system will move. The system will move on metal casters mounted on the rail. The frame is covered with Anti-aging PVDF coated industrial fabric **Fabric** - The fabric is waterproof and leak proof with long life. The fabric weight if 650 – 750 gsm and will withstand temperatures between -30 degrees to +70 degrees. Light transmission is 6 – 8% **Color** - Standard color white and light grey, **Mode**: Motorized - Motor is China make and it is a tapered rotor motor model no : ZDY123-4. Power is 2.2 KW. Warranty on the Note: If you require any other color, additional costs will apply. **Height** - Top Roof height 2mtr **Area:** - 45m x 30m = 1350sqm **14531sqft**	14,531 Approx. Sqft	Rs.800/- Per Sqft	Rs.1,16,24,800/-

2)	**Detail design charges** Shop drawing and technical site survey			Rs.50,000/-

Note :1) Material lifting equipment provide by client.
2) MS fabrication work in Client Scope.

Terms and Conditions:

A TERMS OF PAYMENT

1. 50% in Advance.
2. 50% before material dispatch from our principal.

B TRANSPORTATION

1. Transportation at actuals to your account from Port to Site.
2. Unloading, Lifting and shifting of material to work location is in client scope.
3. Material lifting equipment provide by client.

C DELIVERY & INSTALLATION SCHEDULE

1. Supply: 8 - 10 Weeks after receipt of P.O. along with the advance payment
2. Installation: To be discussed.

D FACILITY AT SITE

1. Storage for material
2. Electrical connection near the site
3. Drinking water to be provided at site by client
4. Accommodation for labour

E. SCAFFOLDING : Is in Client Scope

F. CIVILWORK : Civil work at site is not included in our scope of work

G. VALIDITY : 15 Days.

H. GST **:** As Applicable 18%

I. Insurance **:** Transit insurance to your a/c

Look forward for your valued order. If you have any queries please feel free to contact us.

Thanking you in anticipation,

Yours Sincerely

For **Citadel Building System Pvt. Ltd.**

Vinay Kumar
9819234618