NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/16-17/0458 **Date : 26-12-2016**

Tenneco Automotive India Pvt. Ltd
Plot No.G-6, Phase - III ,MIDC Chakan
A/P- Kuruli,Tal - Khed,Pune,
Maharashtra,India

Kind Attn : Girija Jena
Email : gjena@tenneco.com
Contact No : 9922031500

Subject : Quotation for Manipulator & Air balancer with Jig Boom

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.

This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr.No	Description	Qty	Unit	Rate In INR	Net Amount INR
	Option -1				
	Manipulator : 1. Manipulator enables the safe and efficient handling of many products up to a maximum weight of 200 kg. 2. Manipulator incorporates a pneumatic cylinder to achieve the lifting action, and is normally custom built to suit the relevant working environment 3. Low noise levels and low maintenance make manipulator the ideal solution for your material handling problems 4. Three control styles ensure maximum flexibility. Auto balance, powered lift/lower, and pre-set loaded/unloaded options allow the most suitable control style to be used for each handling application **Types** : 1. Railing roof mounted 2. Floor mounted				
	 				
	1. Railing roof mounted	**2. Floor mounted**			
	Specifications :				
1	Manipulator 6 Bar : Cpacity-50kg	1	No.	4,20,000.00	4,20,000.00
	Manipulator 6 Bar : Cpacity-150kg	1	No.	6,84,000.00	6,84,000.00
	Manipulator 6 Bar : Cpacity-250kg	1	No.	7,80,000.00	7,80,000.00
2	Installation charges for above Manipulator	3	No.	20,000.00	60,000.00
3	Roof Mounted 6 x 4m Rail	1	No.	2,76,000.00	2,76,000.00
	Roof Mounted Rail of 2m	1	No.	40,000.00	40,000.00
4	Installation charges for both Railing	1	No.	35,000.00	35,000.00
Note : 1. Above prices are given for each manipulator with Hook, if gripper is required it will be different **2. If Air Booster required, that will be different 90000 each set.**					

	Option-2				
	Air Balancer with Jig Boom : The Balancer has smooth operation, variable capacity, multiple control choices, multiple mounting options and minimal air consumption. The Balancer replaces hoist applications or as part of a complete lifting system to improve ergonomics and increase production				
Specifications :					
1	Jig Boom & Air Balancer : Cpacity-50kg	1	No.	3,60,000.00	3,60,000.00
	Jig Boom & Air Balancer : Cpacity-150kg	1	No.	5,16,000.00	5,16,000.00
	Jig Boom & Air Balancer : Cpacity-250kg	1	No.	7,80,000.00	7,80,000.00
2	Installation charges for above Jig Boom & Air Balancer	3	No.	17,000.00	51,000.00
3	Roof Mounted 6 x 4m Rail	1	No.	2,76,000.00	2,76,000.00
	Roof Mounted Rail of 2m	1	No.	40,000.00	40,000.00
4	Installation charges for both Railing	1	No.	30,000.00	30,000.00
Note : Above prices are given for each air balancer with jib boom, if gripper is required it will be different **If Air Booster required, that will be different 90000 each set.**					

General Prerequisites Required at Site

1 Finished Flooring after curing (Without Water)
2 Electrical Supply on the site single phase/three phase points at different places.
3 Provide electrical cables near to the installation machinery
4 Fork lift/crane to be provided if required .
5 Scaffolding require for Installation it is in client scope.

Limit of Supply

1 Provide place to store the material to be installed .
2 Be responsible for the safe custody of all material
3 Provide place to safely store all the tools of installation
4 Provide change & rest room for the workers.

Quote/Supply is based on

1 BOM is calculated as per standard quantity measurement
2 In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3 Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1 Unloading from truck placement on site
2 Electrical connection for control panel.

Client Scope

1 Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2 Any civil / masonry/structural work required to support are in client scope
3 All structure support is in client scope
4 NIHVA Will provided structure drawing only if required
5 Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	Extra 3%
3	**Freight Notes**	:	Extra as applicable + Taxes
4	**Delivery**	:	7-8 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	**80% advance along with confirm Purchase Order & balance before dispatch**
6	**Insurance**	:	Extra at actual
7	**Sales Tax**	:	Extra as applicable at the time of dispatch. Presently @13.5% VAT (supply within Maharshtra OR @2% CST against Form C (Outside Maharashtra)
8	**Service Tax**	:	Extra @ 15%
9	**Validity**	:	Validity of Offer is 15 days from the of quotation
10	**Warranty**	:	12 Months from the date of supply

Please feel free to Contact **Mr. Mayur Derle** on **7709209333** For any further Clarification /Information in this Concern.

With Best Regards

Monika Kidgaonkar

8551091333

For Nihva Technologies Pvt Ltd