NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

ABB India Limited
Survey No.88/3 to 88/6, Kasaba Hobli, Basavanahalli Village,
Nelamangala Taluk, Bengaluru,(Rural), Karnataka,562123

Date : 06.02.2021
Quote NO : SQT.20.21.3003
Kind Attn : Mithun Pawar
Email Id : mithun.pawar@in.abb.com
Contact No: 8296962333

Subject : Quotation for ASSA ABLOY Machine Protection Door - RP300.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A)	Commercial Offer -Price Includes Customs Duty , Customs Clearance & Local Transporartion till Site - EX WORKS BANGALORE - BY SEA							
Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
	Option I	Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	ASSA ABLOY Machine Protection Door - RP300	4000	2500	2	798,000	1,596,000	20,000	40,000
				Total		1,596,000		40,000
			P&F Charges	3%		47,880		
			Total Without Taxes			1,643,880		40,000
2			Transportation Charges			Inclusive		
3			Unloading Charges @ Site			In Client Scope		
4			GST Extra @ 18%	18%		EXTRA		EXTRA

Delivery : 9 weeks = 4 weeks mfg + 5 weeks sea transport

A1	Commercial Offer -without custom duty + clearnce + Local transport - HIGH SEA SALES - BY SEA							
Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
	Option II	Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	ASSA ABLOY Machine Protection Door - RP300	4000	2500	2	715,000	1,430,000	20,000	40,000
				Total		1,430,000		40,000
			P&F Charges	3%		42,900		
			Total Without Taxes			1,472,900		40,000
2			Transportation Charges			In Client Scope		
3			Unloading Charges @ Site			In Client Scope		
4			GST Extra @ 18%	18%		EXTRA		EXTRA

Delivery : 9 weeks = 4 weeks mfg + 5 weeks sea transport

A2	Commercial Offer - Extra Air freight Rs 180,000 for 2 doors need to be considered - BY AIR

Delivery : 5 weeks = 4 weeks mfg + 1 week air transport

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Albany make Machine Protection Door RP300

Sr. No	Description	Specification
1	Door version:	Vertical Rapid Roller Door for machine protection.
2	Side Frames:	Aluminum anodized two parts, to have easy access to switches and service.
3	Door blade:	Rolltex Plus Curtain with RAL Blue 5002
4	Bottom beam	Aluminium anodized.
5	Drive unit:	Drive unit IP 55, either RH or LH as an option, with control cable (standard length = height of door)
6	Opening / closing speed:	Approx. max. 2,4 / 1,7 m/s
7	Control system:	MCC Vector Control
8	Power suppy:	3/(N)/PE 230/380/400/415 V, 50 Hz
9	Safety features:	pre running photocell.
9	Photocell	with Photocell
10	Safety limit switch:	1 Schmersal safety limit switch PL e EN ISO 13849-1, SIL 3 EN 62061 on drive side integrated in the side frame to save space.
11	Window Type	700 x 500 mm Anti UV Type
12	Window Qty	1 No

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex works Pune

Delivery : As mention above under given options with confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Shrikant Mirkute on 8551098333**

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd