NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Arun Fabricators

Date : 27.08.2019
Quote NO : SQT/19-20/1962R1
Kind Attn : Mr.P.V.Kumaran
Email Id : pur6@arunexcello.com
Contact No: 98403 29701

Subject : Quotation for Dock Leveller , Dock Shelter, Rolling Shutter and Gate.
(PROJECT NAME :- CONSTRUCTION OF FACTORY BUILDING AT SATYAVEDU MANDAL, CHITOOR DISTRICT, AP.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	4

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Dock Leveller	2400	3000	2	200,000	400,000	15,000	30,000
2	Dock Shelter	2200	4000	2	170,000	340,000	15,000	30,000
3	Motorised Rolling Shutter	2400	3000	4	82,000	328,000	20,000	80,000
4	Motorised Rolling Shutter	2000	3000	3	76,000	228,000	20,000	60,000
5	Single Leaf Sliding Gate	8000	1500	1	432,000	432,000	20,000	20,000
6	MANUAL SINGLE LEAF SWING GATE	4000	1500	2	159,000	318,000	20,000	40,000
7	Grill Sqr/mtr				1,700	1,700		
				Total		**2,047,700**		**260,000**
8	P&F Charges			3%		61,431		
	Total Without Taxes					2,109,131		260,000
	GST Extra @ 18%			18%		379,643.58		46,800
	Total With Taxes					**2,488,775**		**306,800**
9	Transportation Charges					In Client Scope		
10	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Sr. No.	Description	Specifications
1	Capacity	6 Ton
2	Dock operation mode	AC power pack hydraulically operated
3	Lip operation mode	Hydraulic
4	Operation control	Through panel
5	Loading platform height from road	1250mm
6	Travel above & below dock level	(+) 300 / (-) 250 mm
7	Platform Size (W x L)	2400 mm x 3000 mm
8	Lip size (W x L)	2400 x 400 mm
9	Shut Height	480 mm
10	Overall length	2400mm x 3000mm + Lip Length (400mm)
11	Maximum slope can be achieved	10%
12	Clear Pit dimensions (W x L x D)	(W) 2450mm x (L) 3050 mm x (D)485 mm
13	Hydraulic power pack	Standard
14	Driver type	Direct by electric Motor
15	Motor Ratings	1 H.P
16	Pump design flow	2.5 LPM
17	Pump pressure	120 bar Operating 200 bar Max.
18	Safety valve set pressure	120 Kg/cm²
19	Pump Type	Gear
20	Volume of oil receiver	7 Lit
21	No Of Deck cylinder	2 No
22	Lip Cylinder	1 No
23	Dock Bumper	Pair of Dock Bumper
Sr .No.	**Specification**	**Motorized Rolling Shutter**
1	Description:	Motorised Rolling Shutter with MS Laths with thickness of 1 mm.
2	Mounting Location area	Inside area / Outside area
3	Mounting Surface	Side Brackets: Optional = On Concrete /Steel & Side
4	Curtain Panel	The panel made of 1.0mm thick MS.
5	Curtain panel size	75mm wide
6	Curtain Profile	Curved
7	Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	Side Brackets	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	Hood Cover	Made of GI Sheet Thickness 1.2 mm GF mm with 25x25x3mm angle stiffener
12	Surface finish	PU paint or Powder coated
13	Drive Unit & Mounting Type	Electric Motor - Direct Mounting - Sprocket chain arrangement – IP54 Protection
14	Wind Pressure	1oo km/hr

NIHVA make – Motorized Sliding Gate	
Door type	Motorized Sliding Gate
Opening Direction	Horizontal - from left to right or reverse
Mounting Location area	Inside area
Design Pattern	Standard Tubular Design Pattern
OUTER TUBE	72 x 72 x 3.2mm MS SQ. TUBE
FOR POST	72 x 72 x 3.2mm MS SQ. TUBE
INNEAR TUBE	38x38x3.20mm/40x40x3.2 MS SQ. TUBE
Gap Between Tubes	125mm
Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
Guide Rollers supporter during Gate movement	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
Painting	2 Coats of EPOXY polyamide based enamel finish of approved colour
El motor make	BFT – Italy (100% imported)
Emergency Operation	Manual after turn the switch
Operating Switch	Push Button from inside
Safety	Photocells, Flashing Light

C) **General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: **Please find below List which are in Client Scope**

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) **Terms & Conditions**

Price : Ex Works Pune

Delivery : 6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil on 8551096333** For any further Clarification /Information in this Concern.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd