NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

HIRANANDANI COMMUNITIES
Mumbai
Maharashtra -India.

Date : 30.01.2020
Quote NO : SQT.19.20.2353R_B
Kind Attn : Mr. SILAMBHARASAN. P
Email Id : psilambarasan@hrealty.com
Contact No: 8939828669

Project Name & Location: HIRANANDANI PARKS, Chennai

Subject : Quotation for Sectional Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Sectional Door Lift - Standard Lift Weight : 585 Kg	7500	5000	2	4,47,000	8,94,000	15,000	30,000
2	Sectional Door Lift - Standard Lift Weight : 656 Kg	6000	7000	4	9,20,000	36,80,000	15,000	60,000
3	Sectional Door Lift - Standard Lift Weight : 213 Kg	3500	4000	3	2,91,000	8,73,000	15,000	45,000
4	Sectional Door Lift - Standard Lift Weight : 874 Kg	7000	8000	4	10,57,000	42,28,000	15,000	60,000
5	Fire Rated Rolling Shutter Weight : 938 Kg	7500	5000	2	5,09,000	10,18,000	15,000	30,000
6	Fire Rated Rolling Shutter Weight : 1260 Kg	6000	7000	4	5,42,000	21,68,000	15,000	60,000
7	Fire Rated Rolling Shutter Weight : 420 Kg	3500	4000	3	2,63,000	7,89,000	15,000	45,000
8	Fire Rated Rolling Shutter Weight : 1680 Kg	7000	8000	4	7,53,000	30,12,000	15,000	60,000
9				Total		**1,66,62,000**		3,90,000
10			P&F Charges	3%		**4,99,860**		
			Total Without Taxes			**1,71,61,860**		**3,90,000**
			GST Extra @ 18%	18%		30,89,135		70,200
			Total With Taxes			**2,02,50,995**		**4,60,200**
11			Transportation Charges	**Rs**		**1,25,000**		
12			Unloading Charges @ Site			**Included**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Sectional Door

Sr. No	Description	Specification
1	Model No	ASSA ABLOY OH1042P
2	Opening Direction & Mounting	Standard
3	Opening/Closing Speed	CDM9 0,28 m/s
5	Door Material	GI Steel
6	Panel Thickness	42 mm Square Grid, steel sheet
7	Filling	CFC-free polyurethane
8	Door sealent	All door sealants made of EPDM rubber, temperature resistant -30/+70
9	Water Penetration	EN 12425 class 3
10	Air Permealibity	EN12426 class 3
11	Thermal Transittance	EN 12428 1.10W /m2K
12	Bottom sealing	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber
13	Door saftey	Doors equiped with spring break device
14	Incase of Power failuer	Doors to be equiped with quick release fuction
15	Operator power conumption	Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W
16	Drive Unit & Mounting Type	Single phase 230V direct drive on shaft
17	Emergency Operation	by Disengagement rope manual
18	Operating Switch	Up/Down Keypad + stopbutton
19	Locks	The Lock bolt locks the door from the inside, without the use of a key. The Lock bolt is not visible from the outside.
20	Environmental Green Product Declaration Certification	As per ISO 14025 and EN 15804

Fire Rated Rolling Shutter

Sr .No.	Description	Specification
1	Rolling Shutter	Fire Rated Rolling Shutter
2	Shutter Slats	Zinc Coated Steel Solid Slats
3	Slat Thickness	1.00 mm
4	Shutter Guide	Galvanise Steel G65, 3mm Thick
5	Bottom Bar	SKB - T120
6	Fire mode	Fire Shutter will autoclose via 71 degree C Thermal Fuisable Link Fire shutter will auto close by gravitywhen recived 24V DC fire signal from control room Fire Signal of 24V DC 400mA are required
7	Operated By	Motorise 230volt 50Hz 1P with Manual override chain

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex works Site

Delivery : 13-14 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Arjun Patil on 8551096333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd