NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax
chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

TEKNOFINE FOODS PVT. LTD.
13/14 Vimal-Paras shoping center opp- jalaram mandir ranpur road
nr.ramdev hotel deesa banaskantha,Gujarat 385535

Date : 24.09.2019
Quote NO : SQT.19.20.2097
Kind Attn : Mr. Virender Sharma
Email Id : virender.sharma@teknofine.com
Contact No: 7575007425

Project Name & Location: Conveyor System; Gujarat.

Subject : Quotation for Conveyor System

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description
A.	Commercial Offer
B.	Technical Specification
C.	General Conditions
D.	Terms & Condtions

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Total length of conveyor (mm)	Width Of Conveyor (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Belt conveyor	600	439	1	1,33,799	1,33,799	Installation inclusive	
2	Buffer Conveyor (cord type belt conveyor)	1559	439	1	4,37,970	4,37,970		
3	High Speed Conveyor (Cord Type Belt conveyor)	653	439	1	3,90,593	3,90,593		
4	Pivot Conveyor with servo pusher (Cord Type Belt conveyor)	1006	439	1	5,48,635	5,48,635		
5	Output Conveyor (Cord Type Belt conveyor)	992	650	1	7,32,931	7,32,931		
				Total		**22,43,928**	**Installation inclusive**	
6	P&F Charges			3%		**67,317.84**		
	Total Without Taxes					**23,11,246**	**Installation inclusive**	
	GST Extra @ 18%			18%		4,03,907.04		
	Total With Taxes					**27,15,153**		
7	Transportation Charges					**In Client Scope**		
8	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

1 Technical Specification- Belt conveyor

Description	Specification
Length:	600 mm
width:	439 mm
Height:	1196 mm
Speed of conveyor	41 mtr/min

2 Technical Specification - Buffer Conveyor (cord type belt conveyor)

Description	Specification
Length:	1559 mm
width:	439 mm
Height:	1196 mm
Speed of conveyor	35 mtr/min

3 Technical Specification - High Speed Conveyor (Cord Type Belt conveyor)

Description	Specification
Length:	653mm
width:	439 mm
Height:	1196 mm
Speed of conveyor	45 mtr/min

4 Technical Specification - Pivot Conveyor with servo pusher (Cord Type Belt conveyor)

Description	Specification
Length:	1006 mm
width:	439 mm
Height:	1196 mm
Speed of conveyor	30 mtr/min

5 Technical Specification - Output Conveyor (Cord Type Belt conveyor)

Description	Specification
Length:	992 mm
width:	650 mm
Height:	1196 mm
Speed of conveyor	41 mtr/min

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax
chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 10- 12weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Bhavin Jain on 8551092333**

With Best Regards
Yogita
8208334981
For NIHVA Technologies Pvt Ltd