**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

## NIHVA Sales Quotation

**Depa India Pvt Ltd**
203 2nd Floor setellite silver,
Andheri –Kurla road.
Marol, Andheri East, Mumbai 400059.

**Date : 10.09.2019**
**Quote NO : SQT/19-20/1841R**
**Kind Attn : Mr. Vinod Vishwakarma**
**Email Id :** Vinod.Vishwakarma@depa.com
**Contact No: 77188 44490**

**Subject : Quotation for 2 Hrs Fire Rated Rolling Shutter and Gear Operated Rolling Shutter. (Delhi airport project)**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**


| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 3 |


**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Height (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | 2 Hrs Fire Rated Rolling Shutter | 3600 | 3500 | 16 | 2,39,000 | 38,24,000 | 20,000 | 3,20,000 |
| 2 | 2 Hrs Fire Rated Rolling Shutter | 3000 | 2600 | 12 | 1,97,000 | 23,64,000 | 20,000 | 2,40,000 |
| 3 | 2 Hrs Fire Rated Rolling Shutter | 3500 | 3500 | 2 | 2,36,000 | 4,72,000 | 20,000 | 40,000 |
| 4 | Gear Operated Rolling Shutter(Grill) | 3600 | 3500 | 10 | 92,000 | 9,20,000 | 20,000 | 2,00,000 |
| | | | **Total** | | | **61,88,000** | | **5,60,000** |
| 5 | P&F Charges | | | 3% | | 1,85,640 | | |
| | **Total Without Taxes** | | | | | 63,73,640 | | 5,60,000 |
| | GST Extra @ 18% | | | 18% | | 11,47,255.20 | | 1,00,800 |
| | **Total With Taxes** | | | | | **75,20,895** | | **6,60,800** |
| 6 | Transportation Charges | | | | | In Client Scope | | |
| 7 | Unloading Charges @ Site | | | | | In Client Scope | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

| Sr .No. | Specification | Nihva Fire Rated Rolling Shutter. |
|---|---|---|
| 1 | Shutter Curtain | Single Skin Design |
| 2 | Guide Rail | powder coated |
| 3 | Bottom Bar | powder coated |
| 4 | Type of Mounting | Standard |
| 5 | Motor Drive Unit | Power Source: 110v 60Hz 1 phase<br>220v 60Hz 1 phase<br>230v 50Hz 1 phase<br>400v 50Hz 3 phase<br>Insulation Class E<br>Manual Chain Override<br>One unit push button switch<br>Gravity drop level<br>Auto close by relay switch after receive of 24vdc fire signal |

| Sr .No. | Specification | Grill Gear Operated Rolling Shutter |
|---|---|---|
| 1 | Description: | Gear Operated Rolling Shutter with Galvanised Steel Laths with thickness of 1 mm. |
| 2 | Mounting Location area | Inside area / Outside area |
| 3 | Mounting Surface | Side Brackets: Optional = On Concrete /Steel & Side. |
| 4 | Curtain Panel | The panel made of 1 mm thick GI steel. |
| 5 | Curtain panel size | 75mm wide. |
| 6 | Curtain Profile | Curved. |
| 7 | Bottom Profile | M. S. Plate 100 mm x 2.5 mm thick with angle stiffener. |
| 8 | Side Guide Profile | M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension). |
| 9 | Roller Shaft | M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Dia -100 to 300 mm as per w x h. |
| 10 | Side Brackets | MS Plate 3 mm to 10 mm thick, as per the opening dimension. |
| 11 | Hood Cover | Made of GI Sheet Thickness 0.9 mm with 25x25x3mm angle stiffener. |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description | Remark |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | In Client Scope |
| 2 | Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site | In Client Scope |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | In Client Scope |
| 4 | Any civil / masonry/structural work required | In Client Scope |
| 5 | All structure support required | In Client Scope |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | In Client Scope |
| 7 | Conduits, Cables required | In Client Scope |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

Please feel free to Contact **Mr. Ravindra Kharat on 7410169333** For any further Clarification /Information in this Concern.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd