NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Supply & Installtion of Telescopic belt conveyor

Technical Specifcations - Telescopic Belt conveyor

DOC REF STD-LE-BQ-R0-RFP-TELESCOPIC BELT CONVEYOR

DRG NO LT000025

LOGIC DOC NA

CA-TS-35		Manufacturer Name	Typ		Supplier to Specify	Forbo make belt
CA-TS-36		Tension Surface	Typ		Top	NA
CA-TS-37		Type of Conveyor Frame	Typ		Mild Steel	Mild steel with powder coated/painted
CA-TS-38		Section Dims - Conveyor Frame Section	mm		Supplier to Specify	As per design
CA-TS-39		Type of Slider Bed	mm		Pre-Coated ; Cold Formed Steel	Mild steel with powder coated/painted
CA-TS-40		Max Angle of Inclination	Degree		NA	NA
CA-TS-41		Section Dims - Conveyor Slider Bed Width	mm		1200 Max	As per design
CA-TS-42		Section Dims - Conveyor Slider Bed Section	mm		First Bend 40; Second Bend 15; Thk 2	As per design
CA-TS-43		Slider Bed - Length b/w Lap Joints (Nom)	mm		2400	As per design
CA-TS-44		Legs for Frame	Typ		Cold Formed Mild Steel	Mild steel with powder coated/painted
CA-TS-45		Length of Leg	mm		Supplier to Specify	As per design
CA-TS-46		Section Dims - Conveyor Legs	mm		Supplier to Specify	As per design
CA-TS-47		Section Dims - Conveyor Legs-Cross Support	mm		Supplier to Specify	As per design
CA-TS-48		No of Cross Supports/Leg Assy	#		Supplier to Specify	As per design
CA-TS-49		No of Leg per Assy	#		3	As per design
CA-TS-50		No of Feet / Leg Assy	#		2	As per design
CA-TS-51		Spacing of Legs over Conveyor Length	mm		2400	As per design
CA-TS-52		Max Angle of Inclination	Degree		Upto 7 Degree Adjustable	4 degree of inclination is ok ,
CA-TS-53		Belt Direction	Typ		Bi Directional	Ok
CA-TS-54	Availabilty Test	Availability Test Applicable	yes/no		Entire System as per FEM 9.222	**User Acceptance after commissioning of TBC**
CA-TS-55		Time for Availability Test	Typ		60 days post commissioning	Max 30-45 days
CA-TS-56		Tenure of Availability Test	Hrs		40	Ok
CA-TS-57		Initial Availability (During Testing)	%		> 90%	90%
CA-TS-58		Complete System Availability	%		> 99%	99%
CA-TS-59	Noise	Default (measuring procedure in accordance with advertisement)	dB		60	Noise of machine will be below 60 dB
CA-TS-60	Warranties	Warranty Period of 24 Months	yes/no		Vendor to Confirm	24 month Warranty Period begins after the Client Issues a Certificate of Completion of Commissioning
CA-TS-61		Consumables List Provided	yes/no		Vendor to provide	Ok after PO approval
CA-TS-62		Frequency of Periodic Maintenance Offered within the Warranty Period	Weeks		Vendor to provide	Ok after PO approval
CA-TS-63	Mainteance Arrangements					
CA-TS-64						
CA-TS-65		Frequency of Periodic Maintenance Offered in the AMC	Weeks		Vendor to specify	We will let you know after PO approval
CA-TS-66		Necessity for maintenance (e.g. lubrication) between Periodic maintenance	yes/no		Vendor to specify	We will let you know after PO approval
CA-TS-67		Future Expansion for Conveyors Considered	yes/no		yes	Please specify future expansion plan

Supplier Name NIHVA Technologies

Contact No Vijay 8551093333

Address Pune maharashtra

Manufacturer name NIHVA Technologies

NIHVA TECHNOLOGIES PVT. LTD.

Supply & Installtion of Telescopic belt conveyor

Technical Specifcations - Telescopic Belt conveyor

DOC REF STD-LE-BQ-R0-RFP-TELESCOPIC BELT CONVEYOR

DRG NO LT000025

LOGIC DOC NA

Supplier Name					**NIHVA Technologies**	
Contact No					**Vijay 8551093333**	
Address					**Pune maharashtra**	
Manufacturer name					**NIHVA Technologies**	
CA-TS-68	**Bought Out Parts**	Drive Motors & VFDs	Name		SEW Euro drive	All Drives need to be suitable for Network
CA-TS-69		Starters / Contactors	Name		SEW/Siemens	Siemens/Schiender
CA-TS-70		Switchgear Cabinet	Name		Rittal	Ok IP54
CA-TS-71		Terminal Boxes	Name		Rittal	Ok
CA-TS-72		Control Panel Cabinet	Name		Rittal (Model supplied to conform to IP 64)	We considered IP 54
CA-TS-73		Ingress Protection	Class		IP54	OK
CA-TS-74		PLC's	Name		Siemens / Mitsubishi	Siemens 4 " HMI
CA-TS-75	**Safety Guidelines**	Chain/Belt Guards	yes/no		yes	All Moving / Rotating members should have suitable & adequate Safety Guards / Rails as necessary to avoid ingress
CA-TS-76		Auto Stop Safety Guard	yes/no		yes	Ok
CA-TS-77		Conveyor / Load Unit Guides	yes/no		NA	NA
CA-TS-78		Safety Railings around the System	yes/no		Yes required	Ok MS powder coated/ painted
CA-TS-79		Access Ladders to the Maintenance Platforms	yes/no		NA	NA
CA-TS-80		Emergency Pull Cord along the Length of the Conveyor	yes/no		NA	NA
CA-TS-81		Focus Lights	yes/no		2 nos at front of the conveyor	2 no, focus light / 1 tube light
CA-TS-82		E-Stop Buttons at regular intervals	yes/no		At conveyor front & middle of system & Panels	1 at front , one at rear and one on panel
IMPORTANT NOTES						

1	ANY DEVIATIONS FROM THE SPECIFICATIONS MENTIONED IN THE TECH SPECS SHEET SHOULD BE HIGHLIGHTED TO US AND RECORDED IN DEVIAION TEMPLATE ONLY.
2	ANY DEVIAIOTN WILL NOT BE ACCEPTED AT ANY STAGE OF THIS PROJECT UNLESS ARE OTHERWISE DISCUSSED AND APPROVED BY US.
3	VENDOR SHOULD ENSURE ALL THE REQUIREMENTS MENTIONED IN DESIGN MANDATORY POINTS ARE STRICTLY FOLLOWED. DEVIATIONS WILL NOT BE ACCEPTED.
4	Electrical power drop will be given only to one drop point. Distribution within the overall system is in the scope of Vendor.
5	All the Rotating parts throughout the conveyor to be 100% covered to avoid finger ingress. (Shafts, End sections, Conveyor Bottom, Dirve units)
6	All Control panels to be provided with barrications for all the 4 sides upto 1800mm with Front door, rubber mat,earth protection device, arc flash boundary.warning signs etc.
7	The Gaps between the conveyors is indicative. Supplier to ensure that the Gaps have to be suitably designed for seamless movement of Load Units
8	Widths mentioned are as per the Drawing. However, the same need to be as per the Design Requirement based on the Load
9	All Pick-up & Drop Points to have necessary Safety Guards & Bumpers
10	The Lengths mentioned here have been rounded off and are for the purpose of proposal only. On the event of being awarded the contract, the Supplier is responsible for Detail Engineering to the exact Millimeters as required
11	Supplier is responsible for the Detailed Design / Manufacture / Supply / Implementation of the Overall System
12	The Transfer from belt conveyor to roller conveyors shall be smooth and roller conveyors shall have rough/rubberized surface for efficient transfer
13	Quoted cost shall include all the costs for all the provisions/accessories unless specified as 'Optional'
14	Availability Tests shall be after a min. period of 2 Months after issue of Completion of Commissioning Certificate
15	In the case of repeatation of Availability Tests due to Conveyor Vendor, Conveyor Vendor shall bear the costs of the remaining Vendors & Consultants for Repeat test
16	Supplier to ensure that all key Makes mentioned are available in India
17	Supplier shall indicate in detail along with specifications, all the facilities required from other Suppliers / Contractors along with their proposal. For instance, Pit for Lift etc